

**KARAGANIS & WHITE LTD.**

ATTORNEYS AT LAW

414 NORTH ORLEANS STREET-SUITE 810

CHICAGO, ILLINOIS 60610

TELEPHONE

(312) 836-1177

TELEFAX

(312) 836-9083

JOSEPH V. KARAGANIS

A. BRUCE WHITE

BARBARA ANNE MAGEL

MARK D. ERZEN

ELLEN LOIS ZISOOK

JAMES D. BRUSSLAN

JANICE E. HICKS

DANIEL SWARTZMAN  
OF COUNSEL

October 17, 1990

Barbara Russell  
RCRA Enforcement Unit  
5HR-12  
U.S.EPA Region V  
230 South Dearborn Street  
Chicago, Illinois 60604



Re: Closure Information - Croda Inks, Niles,  
Illinois Facility


Dear Ms Russell:

Enclosed please find a copy of the Closure Plan submitted to the Illinois Environmental Protection Agency for the container storage area and underground tank at the Croda Inks, Niles, Illinois facility. As I indicated during our phone conversation, all elements of the closure activities, including removal and proper disposal of all containers, removal of the underground tank and surrounding soils, testing of soils and cleaning of the storage pad have been completed with IEPA concurrence.

A question does remain as to the use of Attachment 7 for volatile compounds analysis which relates to the detection of methylene chloride in certain samples. Croda has never used methylene chloride at the facility and the compound was also detected in the laboratory blanks. At this point, Croda is re-analyzing several samples to determine if methylene chloride is in fact present. Once that issue is resolved, Croda believes it will have completed closure in accordance with all of IEPA's requirements.

I have also enclosed a copy of the sample results obtained through the closure activities for your information. If you have any questions with respect to the enclosed materials, please feel free to give me a call. I apologize for not providing you with these materials earlier.

Very truly,

A handwritten signature in cursive script, appearing to read "Barbara Magel". The signature is written in dark ink and is positioned above the printed name.

Barbara Magel



Engineers & Scientists  
Environmental Services  
Waste Management  
Water Resources  
Site Development  
Special Structures  
Geotechnical Analysis

0253-088071

October 6, 1989  
40045

Mr. Lawrence W. Eastep, P.E.  
Manager - Permit Section  
Division of Land Pollution Control  
Illinois Environmental Protection Agency  
2200 Churchill Road  
Springfield, Illinois 62794-9276

RE: Revised Closure Plan  
Croda Inks Corporation  
Niles, Illinois

Dear Mr. Eastep:

Enclosed are four copies of the revised Closure Plan for the Croda Inks Corporation (Croda) requested by the Illinois Environmental Protection Agency (IEPA) in its August 31, 1989 letter to Croda. Presented below is Croda's response to each of the deficiency items listed in the IEPA's August 31, 1989 letter to Croda:

1. Description of the Waste Management Units. The drum storage area has been designated as S01 and the former underground storage tank (UST) as S02 and will be closed as two separate units. Separate "Description" and "Location of Samples" discussions have been included for each storage unit (i.e., Refer to Sections 1.4, 1.5, 2.2 and 2.3 in the Closure Plan).
2. Map of Facility. Figure 3 (i.e., Proposed Boring Location Map) is a schematic map, drawn to scale, of the facility which designates both storage units and other items of interest. Figure 1 is a United States Geologic Survey (USGS) map of the area which designates the township, range, etc. Section 1.3.1 of the Closure Plan also lists the township, range etc.
3. Detailed Drawing of the Unit(s). Refer to Item 2 above.

4. Decontamination of Tanks, Structures and Soils. Since the former UST was already removed in December of 1988, this section is not applicable. Potential remediation alternatives are discussed in Section 4.3 of the Closure Plan.
5. Soil Cleanup Levels. The IEPA's March 2, 1989 Closure Plan Instructions lists the clean closure final objectives as "drinkable leachate" and "edible soils." It goes on to reference the United States Environmental Protection Agency's (U.S. EPA) "Surface Impoundment Clean Closure Guidance Manual" as a reference document, as well as outline potential exposure pathways and required background information. The exposure assessment and resulting soil cleanup levels presented in the Closure Plan have been based on the referenced U.S. EPA document, as well as other applicable U.S. EPA guidance manuals used to evaluate Comprehensive Environmental Recovery, Compensation and Liability Act (CERCLA) and RCRA sites. The soil cleanup levels presented in the Closure Plan have also been designed to meet the clean closure criteria presented in IEPA's Closure Plan Instructions. The wording of the Closure Plan also allows for the modification of the soil cleanup levels if additional contaminants or potential exposure pathways are identified.

The IEPA has approved soil cleanup criteria prior to soil sampling at other sites. Sufficient information is already available regarding potential contaminants, regional hydrogeology and water usage and potential exposure pathways to develop soil cleanup criteria for the Croda site prior to performing the Closure Plan soil sampling activities. The exposure assessment approach used in the Closure Plan appears to be more applicable and relevant in the development of cleanup criteria for the soils present at the Croda site than fish bioassay toxicity data (e.g., 0.1 times the 96 hour TLM) typically used by the IEPA. If the IEPA elects not to accept the soil cleanup criteria presented in the Closure Plan, Croda would request that the IEPA provide, in writing, the basis for that decision.

6. Sampling Plan and Analytical Methods. The following is the response to individual items mentioned in this section:
  - Three borings have been located in the former UST area. Refer to Figure 3 and Sections 2.2 and 2.3 for the modified proposed boring locations;
  - The five drum storage area borings will be located where the most significant surface deterioration has occurred. The Closure Plan has been revised to reflect this modification;

- Refer to Section 2.5 of the Closure Plan for arguments concerning the use of split spoon sampling for volatile organic compounds (VOCs) in lieu of sampling methods presented in Attachment 7 of the IEPA's Closure Plan Instructions;
  - Including both total lead and chromium and E.P. Toxicity for lead and chromium in the sampling plan would incrementally increase the Closure Plan cost estimate by approximately \$17,000 to \$36,000. Based on the relative immobility of lead and chromium in clay soil environments, as well as the low levels of lead and chromium detected in laboratory analyses presented in the Appendices of the Closure Plan, analysis for VOCs and PNAs should be sufficient to assess the area for potential contamination and establish necessary cleanup criteria. It should also be noted that the IEPA has recently approved a Closure Plan for a paint manufacturing facility, currently being performed by Warzyn Engineering Inc. (Warzyn), which only requires soil samples to be analyzed for VOCs. The waste streams generated by Croda are very similar to those generated by the paint manufacturing facility since identical types of pigments, solvents and other raw materials are used in the manufacture of both paint and ink products (refer to Section 2.1 of the Closure Plan for a more detailed discussion).
  - Since it was not known if the stockpiled soil had been contaminated by the contents of the UST at the time of the UST removal, and the soil was immediately containerized once a hazardous waste determination was made, the bare ground area where the stockpiled soil was stored should not be part of the Closure Plan. The analytical results of the stockpiled soil show that no hazardous waste characteristic criteria were exceeded, and that xylene and toluene levels detected are well below typical levels found in non-hazardous gasoline-contaminated soil. The stockpiled soil was covered with plastic prior to being containerized in order to minimize rainwater infiltration. Based on the levels of VOCs detected in the stockpiled soil, it is not likely that the bare ground underneath the stockpiled soil would have been impacted by the presence of the soil. Refer to Section 2.3 of the Closure Plan for a more detailed discussion.
7. Certification Statement. A copy of the required certification documents has been included in Appendix F of the Closure Plan.
8. Signatory Requirements. A signed copy of the Closure Plan Certification Statement has been included in Appendix F of each of the enclosed Closure Plans.

Since it is expected to take more than 180 days to complete the closure process, an extension is requested as part of the IEPA approval of the Closure Plan. If you have questions regarding the contents of this letter or the Revised Closure Plan, please contact Mr. Mark Rothas of Warzyn at (312) 691-5064. Representatives of Croda would also be willing to meet with the IEPA to discuss the contents of the Closure Plan.

Sincerely,

WARZYN ENGINEERING INC.

*Mark Rothas*

Mark S. Rothas  
Senior Project Engineer

[WP3]  
40045L12MSR/dms/JAH





**Report**  
**Project No. 40045.02**

**Revised Closure Plan**  
**Croda Inks Corporation**  
**Niles, Illinois**

Prepared for:

**Croda Inks Corporation**  
**Niles, Illinois**

Prepared by:

**Warzyn Engineering Inc.**  
**Chicago, Illinois**

October 1989

REVISED CLOSURE PLAN FOR CRODA INKS CORPORATION  
NILES, ILLINOIS FACILITY

Prepared For:

CRODA INKS CORPORATION

Prepared by:

WARZYN ENGINEERING INC.  
2100 Corporate Drive  
Addison, Illinois 60101

October 6, 1989



## TABLE OF CONTENTS

	<u>PAGE NUMBER</u>
1. INTRODUCTION .....	1
1.1 Regulatory Status.....	1
1.2 Description of Facility.....	2
1.3 Regional Geology and Groundwater Usage.....	2
1.3.1 Site Topography.....	2
1.3.2 Groundwater Usage.....	3
1.3.3 Regional Geology.....	4
1.3.4 Regional Hydrogeology.....	5
1.4 Description of Drum Storage Area (S01).....	6
1.5 Description of Former Underground Storage Tank (S02)....	6
1.6 Description of Hazardous Waste Generation.....	7
1.7 Schedule for Closure.....	7
2. SOIL SAMPLING PLAN.....	9
2.1 Parameters to be Analyzed.....	9
2.2 Locations of Drum Storage Area Samples (S01).....	11
2.3 Locations of UST Area Samples (S02).....	12
2.4 Selection of Samples to be Analyzed.....	13
2.5 Sampling Methods.....	14
2.6 Sample Custody.....	15
2.6.1 Field Documentation.....	15
2.6.2 Laboratory Chain-of-Custody.....	17
2.6.3 Final Evidence File.....	17
2.7 Equipment Decontamination.....	17
2.8 Site Health and Safety Plan.....	18
3. ANALYTICAL METHODS AND QA/QC.....	19
3.1 Analytical Methods.....	19
3.2 QA/QC Procedures.....	19
3.2.1 Calibration Procedures.....	19
3.2.2 Quality Control Checks.....	20
3.2.3 Precision, Accuracy and Completeness.....	20
3.2.4 Corrective Action.....	20
3.2.5 Data Reduction, Validation and Reporting.....	20
4. WASTE DISPOSAL PLAN.....	21
4.1 Remaining Drums.....	21
4.2 Soil Cleanup Levels.....	21

**TABLE OF CONTENTS**  
(continued)

4.2.1	Exposure Pathway Assessment.....	22
4.2.2	Soil Cleanup Level Calculations.....	23
4.2.2.1	Soil Cleanup Level Calculations for Carcinogenic Chemicals.....	23
4.2.2.2	Soil Cleanup Level Calculations for Non-Carcinogenic Chemicals.....	25
4.2.3	Application of Soil Cleanup Levels.....	26
4.2.4	Exposures to Multiple Chemicals.....	28
4.2.5	Statement of Qualification.....	29
4.3	Soil Remediation Plan.....	29
5.	STATUS OF AREA AFTER CLOSURE.....	32
6.	CLOSURE COST ESTIMATE.....	33
7.	CERTIFICATION OF CLOSURE.....	34
8.	REFERENCES .....	35

**LIST OF TABLES**

Table 1	- Sample Quantities, Bottles, Preservation and Packaging for Soil Samples
Table 2	- Soil Cleanup Levels for Carcinogenic Compounds
Table 3	- Soil Cleanup Levels for Non-Carcinogenic Compounds

**LIST OF FIGURES**

1	USGS Map
2	Private Well Location Map
3	Boring Location Map
4	Chain-of-Custody Record
5	Chain-of-Custody Seal
6	Sample Label

### LIST OF APPENDICES

- A Hazardous Waste Analyses
- B Material Safety Data Sheets for Primary Raw Material and Cleaning Solvents
- C Representative Manifests for Off-Site Disposal
- D Soil Analytical Results From Base of UST Excavation
- E RCRA Characterization of Stockpiled Soil From UST Excavation
- F Closure Certification Documents
- G ISWS Well Logs

## **SECTION 1** **INTRODUCTION**

### **1.1 Regulatory Status**

The Croda Inks Corporation (Croda) is submitting this closure plan to the Illinois Environmental Protection Agency (IEPA) with the intention of returning the status of its Niles, Illinois facility to a Resource Conservation and Recovery Act (RCRA) hazardous waste generator. The facility's drum and former underground tank storage areas have been designated as RCRA storage units based on cited deficiencies in the large quantity generator 90-day storage time limit. The deficiencies are outlined in an April 17, 1989 enforcement letter from the IEPA to Croda as a result of a March 28, 1989 IEPA inspection of the facility.

The hazardous waste drum (S01) and former underground tank (S02) storage areas will be closed in accordance with the closure performance standards presented in Title 35, Subtitle G, Section 725.211 of the State of Illinois Rules and Regulations. The criteria used to determine "clean closure" are presented in Section 4.2 ("Soil Removal Criteria"). All hazardous waste storage activities will be discontinued in the area during the closure period. Soil potentially impacted by surface spills of hazardous wastes will be remediated to the extent necessary to protect human health and the environment. Future hazardous waste generation will be disposed of within the required generator storage time allowance. Following the completion of closure activities, the drum storage area will either be used for general storage, or continue to be utilized as a 90-day large quantity generator hazardous waste drum storage area.

Since the drum storage area is believed to have always been asphalt paved, a phased soil sampling approach is being recommended. Sampled soil borings down to 10 feet will be initially performed. If necessary, based on the results of the initial soil sampling, a scope of work outlining additional soil sampling and/or the installation of groundwater monitoring wells will be prepared.

## 1.2 Description of Facility

Croda's Niles, Illinois facility (Refer to Figure 1 for United States Geologic Survey Map) primarily manufactures made-to-order small batch flexible packaging printing inks and adhesives (SIC Codes 2891 and 2893), primarily for the food and soft drink industries. The facility was built around 1964, and is believed to have always been an ink manufacturing operation. Prior to 1978, the facility was not owned and operated by Croda. The primary raw materials used in past and present operations include aliphatic, aromatic and chlorinated solvents, solvent-based resins and ink bases and organic and inorganic pigments. Lead and chromium oxide pigment usage has been phased out of ink formulations manufactured at the facility within the last two years. Operations performed at the site include roller mill dispersion, blending and manual filling into 55-gallon drums and various other container sizes. Based on a review of available data for the area, the overall groundwater gradient in the surficial aquifers appears to be relatively flat, with flow probably to the west towards the North Branch of the Chicago River, which is located approximately one-half mile west of the site.

## 1.3 Regional Geology and Groundwater Usage

### 1.3.1 Site Topography

The Croda facility is located in the Northeast Quarter of the Southwest Quarter of the Northwest Quarter of Section 29, Township 41 North, Range 13 East in Cook County, Illinois. Based upon a site visit and a study of the Park Ridge, Illinois 7.5 minute topographic quadrangle map, it appears that the area surrounding the facility is highly industrialized. The area beyond these industrial facilities is densely populated and primarily occupied by residential buildings and occasional commercial buildings. A United States Geologic Survey (USGS) map showing the Croda facility and surrounding vicinity is presented in Figure 1.

The surficial topography around the site exhibits low relief with a gentle slope to the west, in the direction of the North Branch of the Chicago River. The nearest body of water is a small, unnamed pond approximately 1,100 feet south of the site. The North Branch Chicago River, located approximately one-half mile to the west, is the nearest major body of water in the vicinity of the Croda facility. The North Branch flows southward through the Chicago metropolitan area and becomes the Chicago Sanitary and Ship Canal, which flows southwestward and discharges into the Des Plaines River north of Joliet, Illinois. Natural drainage in the site vicinity has been altered by roadways and other man-made features. Surface water run-off flows from the site into storm sewers, which are believed to be routed to the North Branch Chicago River.

#### 1.3.2 Groundwater Usage

Warzyn obtained records from the Illinois State Water Survey (ISWS) of the private wells located in Sections 19, 20, 29, 30 and 32 of Township 41 North, Range 13 East, which indicate that there are, or were, six water supply wells located in those sections. There were no well logs available for Sections 21, 28 and 31. The Croda site is located in the Southwest Quarter of Section 29 and each of the above mentioned sections was obtained in order to provide well log information within a one mile radius of the site. A map showing the approximate locations of each of the private wells is presented in Figure 2, while Appendix E contains the ISWS well logs.

In review of the six ISWS drilling logs, it was noted that four appear to have been installed at private residences, or farms; one was a municipal well for the Village of Morton Grove; and one well was on Cook County Forest Preserve District property. It is not presently known how many of the wells are still operational. Four of the wells were drawing water from the dolomitic limestone aquifer at depths of between 86 and 179 feet below ground surface, while the municipal well and one of the farm wells were drawing water from a dolomite and sandstone aquifer from between 568 and 1,462 feet below ground surface.

During a phone interview with Mr. Scott Jochim, Civil Engineer with the Village of Niles Engineering Department, Warzyn was informed that all of the commercial, industrial and residential buildings west of Lehigh Avenue and east of the Des Plaines River under the jurisdiction of the Village of Niles receive water obtained from Lake Michigan. The water is purchased by the Village of Niles from the City of Chicago and is received into their own reservoir via underground pipeline. A similar conversation with Ms. Joan Anundson of the Village of Morton Grove Public Works Department disclosed that the Village of Morton Grove also purchases Lake Michigan water from the City of Chicago.

### 1.3.3 Regional Geology

A review of available geologic literature indicates the site is on lake plain deposits most typically formed on the floor of glacial Lake Chicago, the precursor to the current Lake Michigan (Lineback, 1979; Willman et.al., 1975; Willman, 1971). These lake plain deposits belong to the Carmi Member of the Equality Formation, deposited during the Pleistocene epoch. The soils of the Carmi were deposited during the Wisconsin glacial stage between approximately 7,000 and 22,000 years before present (BP). The area in the vicinity of the Croda site is generally characterized by areas of low relief, formed as deposits on the floor of the glacial lake and flattened by wave action.

The Carmi Member is predominantly silt or clay interbedded with sorted sediments; it is composed primarily of sheet-like deposits of silt and clay-sized particles with localized deposits of fine sand near prehistoric lake shorelines. The thickness of the Carmi Member ranges typically between 20 and 40 feet. The relatively thin sediments of the Carmi are underlain by the Wadsworth Till of the Wedron Formation, also of Pleistocene age. The Wadsworth Till is a gray till, interbedded with sorted sediments. This till is composed primarily of silt and clay-sized particles separated by beds of

waterlaid sand, gravel and silt. The combined thickness of the unconsolidated deposits of the Carmi and Wadsworth Formations in the vicinity of the site is approximately 100 feet.

Based upon studies of the literature (Willman et.al., 1967; Suter et.al., 1959; Visocky et.al., 1985), the unconsolidated sediments in the region unconformably overlie bedrock of Silurian age. The Niagaran and Alexandrian Formation, the uppermost bedrock units expected, are a carbonate deposit which will vary from dolomite to a dolomitic limestone. The Silurian formations were most typically formed as reef deposits built while Illinois laid under a shallow sea between 400 and 435 million years BP (Levin, 1978). The thickness of the Silurian in the vicinity of the site is approximately 200 to 250 feet. Underlying the Silurian bedrock units is the approximately 200-foot thick Maquoketa Shale Group, deposited during the Ordovician period. The Maquoketa Group is composed of several individual shale formations and a limestone formation deposited approximately 435 to 600 million years BP. The older Ordovician and Cambrian bedrock units beneath the Maquoketa are composed primarily of limestones and sandstones and are typically in excess of 2,000 feet thick.

#### 1.3.4 Regional Hydrogeology

The silts and clays of the Carmi and the till layer of the Wadsworth generally do not provide sufficient yields to be utilized as drinking water sources due to their low permeabilities. The localized interbedded sand, silt and gravel deposits can yield moderate quantities of groundwater due to higher permeabilities created by greater pore space and more extensive pore interconnections which allow for the migration of groundwater (Fetter, 1988; Freeze et.al, 1979). Recharge to the silts and clays of the Carmi and the till and associated localized sand, silt and gravel units of the Wadsworth typically occurs locally from precipitation.



The bedrock unit immediately below the unconsolidated materials in the northern Illinois area is considered a usable aquifer. Groundwater in the Niagaran and Alexandrian aquifers is primarily obtained from joints, fissures and solution cavities. These water-bearing openings are irregularly distributed both vertically and horizontally in the units. Typical groundwater wells placed in the Niagaran and Alexandrian dolomitic limestone bedrock can yield several hundred gallons per minute. Beneath the Maquoketa Shale, a low permeability unit, underlying the Silurian limestones, are the higher yielding Ordovician and Cambrian age sandstone and limestone units. These units are the most frequently used aquifers in the northeastern Illinois region.

#### 1.4 Description of Drum Storage Area (S01)

The hazardous waste drum storage area is approximately 125 feet long by 20 feet wide and is located immediately adjacent to the eastern outside wall of the building (see Figure 3). The surface of the drum storage area is presently asphalt. A metal overhang, approximately 20 feet high, was added to protect the drum storage area from precipitation. The ground along the eastern boundary of the drum storage area is part of a yard area and is not paved (i.e. bare surface). The drum storage area is also bordered by the caustic room to the north, the building to the east and an asphalt paved parking lot to the south. The maximum volume of hazardous waste stored in 55-gallon drums and other miscellaneous smaller containers was 6100 gallons. Hazardous waste drums are presently being stored indoors (see Section 4.1) and are disposed of off-site within the 90-day accumulation time period.

#### 1.5 Description of Former Underground Storage Tank (S02)

A 2000-gallon underground storage tank (UST) was removed from the southern corner of the drum storage area in December of 1988. The UST, required for insurance purposes, was originally installed approximately 20 years ago to collect indoor spills. The UST had been utilized for at least the last two years of its service as a hazardous waste accumulation tank. The 2000-gallon UST was filled to capacity at the time it was taken out-of-service.

### 1.6 Description of Hazardous Waste Generation

Prior to 1986, ink manufacturing equipment cleaning was performed using a caustic bath located in an addition to the main building on the northern end of the drum storage area. Spent caustic solution was disposed of at Chem-Clear, Inc. in Chicago, Illinois. The caustic bath was replaced with a kerosene washer unit in 1986. The unit is located in the mixing room adjacent to the main manufacturing area. The spent kerosene was regenerated and reused by allowing the solids from the ink residue to settle out in 55-gallon drums and decanting the liquid. Small volumes of predominantly toluene, xylene and methyl isobutyl ketone (MIBK) have also been used to clean the roller mills and mixing tubs.

All of the spent equipment cleaning solutions (i.e. caustic and solvent) qualify as K086 RCRA listed hazardous wastes (Ink Formulation Industry). Ink sludges, generated either from contaminated or off-specification products or settled sludges from container bottoms, are generated in small volumes on an intermittent basis. The ink sludges qualify as characteristic flammable hazardous wastes (D001). Refer to Appendix A for available RCRA hazardous waste analyses, Appendix B for Material Safety Data Sheets (MSDSs) for Croda's primary raw material and cleaning solvents and Appendix C for representative manifests for off-site disposal (including recent disposal of waste streams cited in IEPA's April 17, 1989 enforcement letter). Wastewater generated from the cleaning of equipment associated with adhesive manufacturing operations does not qualify as a hazardous waste.

### 1.7 Schedule for Closure

Presented below is the anticipated schedule for closure completion. The schedule allows for the excavation and disposal of potentially contaminated soil that may be found. The execution of the Closure Plan, if soil excavation is necessary, is expected to take a total of 37 weeks from the time approval of the plan is received. Since it is expected to take more than 180 days to complete the closure process, an extension is requested as part of IEPA approval of the Closure Plan.

<u>Activity</u>	<u>Week Number</u>
1. Approval of Closure Plan	0
2. Soil Sampling and Analysis	1-8
3. Submittal of Analytical Results to IEPA and IEPA Review	9-15
4. Develop Scope of Remediation	16-21
5. Permit Soil for Disposal	22-33
6. Soil Excavation/Disposal	34-36
7. Closure Report/Certification	34-37

## SECTION 2

### SOIL SAMPLING PLAN

#### 2.1 Parameters to be Analyzed

The subsurface soil samples will be analyzed for parameters representative of the waste streams generated by the facility. This includes kerosene and polynuclear aromatic hydrocarbon (PNA) constituents of kerosene, as well as volatile organic compounds (VOCs) which are used as on-site cleaning solvents and/or are present as ingredients in Croda's ink formulations. Since mineral spirits is the primary solvent system used in Croda's solvent-based ink formulations, it will also be included in the parameter list. The parameters to be analyzed for in subsurface soil samples include:

- pH,
- RCRA VOCs,
- PNAs, and
- total petroleum hydrocarbons (TPH) as both kerosene and mineral spirits.

TPH as kerosene will be analyzed to verify that the source of detected PNAs are associated with waste kerosene. Other potential sources of PNA presence include leaching from the asphalt surface and the surface runoff of automotive fuels.

Since spent kerosene is the primary waste stream generated by Croda, and VOCs are potentially the most mobile of the contaminants that may be present, analyzing for these parameters should be sufficient to assess the area for the presence of potential contamination and establish necessary cleanup criteria. Since ink sludge residues only comprise approximately 10% of Croda's hazardous waste generation volume (and raw material pigments only comprise approximately 30% of the ink sludge residue volume), and heavy metals are relatively immobile in the clay soil environment at the site, total lead and chromium analysis, as well as Extraction Procedure (E.P.) Toxicity Analysis for lead and chromium, have not been included in the

sampling plan. Within the last two years, Croda has phased out most of its usage of lead and chromium oxide pigments in the ink formulations manufactured at the Niles, Illinois facility. Total lead and chromium and E.P. Toxicity for lead and chromium levels in soil samples collected from both the base of the former UST excavation (refer to Appendix D) and the excavated soil stockpiled from the UST excavation (refer to Appendix E) do not appear to be elevated, nor do they exceed RCRA hazardous waste characteristic criteria. A hazardous waste characterization analysis performed on the ink sludge removed from the former UST (Refer to Appendix A) shows E.P. Toxicity levels for lead and chromium to be well below the respective characteristic criteria for being classified as a hazardous waste.

Including both total lead and chromium and E.P. Toxicity for lead and chromium in the sampling plan would incrementally increase the Closure Plan cost estimate by approximately \$17,000 to \$36,000. The incremental cost estimate increase includes the addition of ten background soil borings (i.e. minimum of 20 additional soil samples) required by IEPA's March 2, 1989 Closure Plan Instructions. The \$17,000 end of the cost estimate range assumes the background samples would only be analyzed for total lead and chromium and E.P. Toxicity for lead and chromium, while the \$36,000 end of the range assumes the background soil samples would be analyzed for all of the sampling parameters outlined in the Closure Plan, which is usually required by the IEPA.

Based on the relative immobility of lead and chromium in clay soil environments, as well as the low levels of lead and chromium detected in the past analysis of the hazardous waste sludge previously stored in the former UST, analysis for VOCs and PNAs should be sufficient to assess the area for potential contamination and establish necessary cleanup criteria. Analysis of soils associated with the UST removal also do not show elevated levels of lead and chromium. The information that may be gained by including total

lead and chromium and E.P. Toxicity for lead and chromium in the sampling plan would not justify the resulting incremental cost increase to perform the Closure Plan.

## 2.2 Locations of Drum Storage Area Samples (S01)

Due to the dimensions of the drum storage area (i.e. 100 feet by 20 feet), a regular interval linear sampling grid of five borings (B1-B5) will be located along the midline of the drum storage area. The first boring will be located approximately 15 feet south of the caustic storage tank room, and subsequent borings will be at 20-foot intervals along the midline of the drum storage area. The five drum storage area borings will be located in areas where the most significant surface deterioration has occurred. This determination will be made during soil sampling activities in the field. Even though deterioration of the asphalt surface is evident, a visual inspection of the drum storage area did not reveal any cracks or defects which expose the surface underneath it. No visual evidence of surface spills was observed on the asphalt surface. Six additional borings (B10-B14) will be located at identical intervals, approximately one to two feet east of the limit of the drum storage area, to evaluate impacts to soils from runoff of materials from the storage area. A detailed Boring Location Map is provided in Figure 3.

Soil samples will be collected with a standard 2-inch split spoon sampler (ASTM D1586) from each boring. Samples will be obtained from the intervals 6-inches to 2-feet (below the asphalt surface), 3-feet to 4.5-feet, 5.5-feet to 7-feet and 8-feet to 9.5-feet. All of the samples will be screened with an organic vapor analyzer (OVA) or photoionization detector (HNU). If OVA or HNU levels exceed background readings and/or visible evidence of releases is detected at the 8 to 9.5-foot interval, split spoon sampling (i.e. two samples per five feet) will continue to a depth of 5 feet below the absence of OVA or HNU levels in excess of background levels or visible evidence of releases.

### 2.3 Locations of UST Area Samples (S02)

Three borings (B6-B8) will be located within the former UST excavation area, one at each end of the excavation and one in the middle. Boring B9 will be located outside of the fence line south of the drum storage area in order to assess potential migration of vapor and liquid phase materials originating from the former UST towards the sanitary storm sewer system situated in the main parking lot area. Boring B15 will be located approximately one to two feet east of the limit of the drum storage area in order to assess potential contamination migration in that direction.

Soil samples will be collected with a standard 2-inch split spoon sampler (ASTM D1586) from each boring. Sampling for borings B6 to B8, located within the former UST excavation, will begin at the termination of the pea gravel backfill material. Since borings B9 and B15 will be used to assess potential migration of materials originating from the former UST, sampling will begin at the depth established during borings B6 to B8 as the termination of the pea gravel backfill material. Two samples per five foot interval will be collected to a depth of five feet below the absence of OVA or HNu levels in excess of background levels or visible evidence of releases.

The bare ground area adjacent to the drum storage area where the soil from the excavation of the former UST was stockpiled has not been included in the Closure Plan for the following reasons:

- At the time the soil was stockpiled, it was not known if the soil had been contaminated by the contents of the UST. A composite of the stockpiled soil was submitted for laboratory analysis. Refer to Appendix E for the detailed analytical results;
- Based on the analytical results, the stockpiled soil did not exceed any RCRA hazardous waste characteristic criteria. The soil was classified as a K086 listed hazardous waste due to the presence of trace levels of xylene and toluene (i.e. 15 to 491 parts per billion total VOCs). The detected xylene and toluene levels are less than what can be detected in typical gasoline-contaminated soils which do not qualify as hazardous wastes; and

- The stockpiled soil was containerized in roll-off boxes immediately following the determination that it could possibly be considered a K086 hazardous waste. Based on the levels of VOCs detected in the stockpiled soil, as well as the short time frame that the soil remained uncontainerized, it is not likely that the bare ground underneath the stockpiled soil would have been impacted by the presence of the soil.

#### 2.4 Selection of Samples to be Analyzed

Depending on the results of field screening activities with an HNu or OVA, one of the following scenarios will be followed in the selection of samples to be analyzed to verify the absence or attenuation of potential contamination:

- If neither VOC presence nor visible evidence of releases are detected in any of the samples, the samples collected from depths of 6-inches to 2-feet and 3-feet to 4.5-feet (except borings B6 to B9 and B15) will be analyzed for the parameters outlined in Section 2.1. The first two samples below the depth of the backfill material will be analyzed from borings B6 to B9 and B15.
- If elevated OVA or HNu readings and/or visible evidence of releases are uniformly detected at depths below 5 feet (or 5 feet below the depth of the backfill material within the UST excavation), a representative number of samples, which will be used to characterize the entire area, will be analyzed for the parameters outlined in Section 2.1. The samples selected to represent each sampling depth will be taken from the same boring(s). At least one boring will be selected from the drum storage area, one from the UST excavation and one from the surface runoff area. Levels of compounds detected in the analyzed samples will be assumed to be representative of levels present throughout the entire corresponding storage unit or surface runoff area.
- If VOCs and/or visible evidence of releases are detected in isolated samples, samples where HNu or OVA levels exceed background readings or visible evidence of releases are detected will be analyzed for the parameters outlined in Section 2.1. Two sample intervals (i.e. five feet) below the depth where HNu or OVA levels exceed background readings or visible evidence of releases is detected will also be analyzed to verify that attenuation of subsurface contamination has occurred. In addition to samples with HNu or OVA levels exceeding background readings or visible evidence of releases, the samples outlined above which would be analyzed if neither VOC presence nor visible evidence of releases are detected would also be analyzed. These samples would be analyzed to confirm the isolated occurrence of any detected compounds.



If extensive subsurface impacts are identified, a further scope of work will be developed based upon the data collected. A further scope of work may include additional soil borings and/or the installation of groundwater monitoring wells. The location and depths of additional subsurface soil borings or groundwater monitoring wells will be based on the initial sampling results.

## 2.5 Sampling Methods

Subsurface soil samples will be collected using a truck-mounted drill rig equipped to drive a standard 2-inch split spoon sampler. The boring hole cuttings and split spoon samples will be screened for VOCs using an OVA or HNu. Samples will be collected at depths outlined in Section 2.2. The samples will be transferred from the split spoon sampler to the sample jar using a stainless steel spoon or spatula.

To minimize volatilization, VOC samples will be collected directly from the split spoon sampler and placed into a 4-ounce glass wide mouth soil jar. The VOC jar will be filled as full as possible. One 8-ounce glass wide mouth soil jar will be filled to 3/4 capacity for PNA and TPH (as both kerosene and mineral spirits) analyses.

Soil samples for VOC analysis will be collected using a split spoon sampler versus soil sampling procedures outlined in Attachment 7 of the IEPA Closure Plan Instructions (Attachment 7) for the following reasons:

- The sampling methods outlined in the Closure Plan have been accepted in numerous Quality Assurance Project Plans and associated sampling plans for investigation of Comprehensive Environmental Recovery, Compensation and Liability Act (CERCLA) sites;
- It is not possible to characterize the subsurface hydrogeology or field screen the borings with an HNu or OVA using sampling procedures outlined in Attachment 7. By field screening borings with an HNu or OVA, it is often possible to avoid the additional costs which may be incurred due to the multiple phases of soil sampling often required in the absence of field screening techniques. Two borings per boring location (i.e. side by side

borings) would be required if sampling procedures outlined in Attachment 7 are used, which would increase the Closure Plan costs associated with drilling activities while not providing better quality data;

- Soil samples are not being mixed or composited using sampling methods outlined in the Closure Plan. Filling the VOC jar as much as possible serves to minimize potential volatilization. Placing the sample into a jar also creates a more homogeneous sample for analytical purposes than sampling methods outlined in Attachment 7;
- It is not possible to determine the sample recovery using sampling procedures outlined in Attachment 7. If recovery is poor, sufficient sample volume may not be available to run all of the required analyses; and
- There is no documentation which shows that VOC volatilization would be less using sampling methods outlined in Attachment 7 versus those outlined in the Closure Plan. Because of the sample handling requirements to perform the analytical tests, the potential for VOC volatilization due to sample handling should be equivalent for both sampling methods. The potential for VOC volatilization during shipping should be less using the sampling methods outlined in the Closure Plan due to the tight seal provided by the teflon lid on the soil jar and the filling of the soil jar to minimize the head space.

Sample bottles will be placed into coolers for storage and shipment and chilled to 4 degrees centigrade for preservation purposes. Ice will be sealed in ziplock plastic bags to prevent leakage. A detailed description of the sampling procedures outlined above is presented in Table 1. Any necessary monitoring well construction or additional sampling information will be supplied at the time the need for further sampling is determined.

## 2.6 Sample Custody

### 2.6.1 Field Documentation

All samples will be collected under chain-of-custody procedures. Chain-of-Custody protocol used will follow National Enforcement Investigation Center (NEIC) policies and procedures and User's Guide to the Contract Laboratory Program (CLP) Protocol including use of chain-of-custody forms, custody seals, sample tags, container labels, and field notebooks for sample documentation. The documentation in the field notebook will include

sampling time, location, tag numbers, samplers, weather conditions, and any field modifications of sampling strategy. Standard forms including chain-of-custody record forms, sample labels, and chain-of-custody seals will be maintained throughout the sampling activities.

An example copy of the chain-of-custody form to be used for Croda is shown in Figure 4. Form requirements include:

- Use of one form per shipping container (steel foam cooler).
- Carrier service does not need to sign form if custody seal remains intact during shipment.
- Use for all samples submitted for analysis.

An example of the chain-of-custody seal to be used for sample shipping for Croda is shown in Figure 5. Seal requirements include:

- Two (2) chain-of-custody seals per shipping container attached across the cooler lid to provide evidence that the samples have not been subject to tampering.
- Covering seals with clear tape prior to shipping sample containers.

A copy of the sample label to be used for Croda is shown in Figure 6. Label requirements include:

- Each sample bottle having a sample label affixed to it. Labels will specify sample date, parameters for analysis (if applicable) and preservative used (if applicable).
- Recording sample label numbers on the chain-of-custody form and sample identification record form.
- Use for on samples collected.

The documentation accompanying the samples shipped to the laboratory will be sealed in a plastic bag taped to the inside of the cooler lid. The lid of the sample cooler will be securely taped shut and sealed with a chain-of-custody label prior to shipment. The Sampling Coordinator will be responsible for collecting the samples, completing the sample documentation, and properly packaging the samples for shipment to the laboratory. Once in the laboratory's possession, sample custody will be the responsibility of the laboratory sample custodian.

#### 2.6.2 Laboratory Chain-of-Custody

Laboratories used for analyses are required to have written and approved standard operating procedures detailing internal chain-of-custody. Laboratory chain-of-custody protocol used will follow NEIC policies and procedures for the CLP.

#### 2.6.3 Final Evidence File

All original data generated through the laboratory will be retained by the contractor collecting the samples. Copies of laboratory data and original field data will be retained by the contractor who will maintain and provide a custodian for the final evidence file. Upon completion of the project, the contractor will maintain the evidence file to document completeness.

#### 2.7 Equipment Decontamination

In order to prevent cross-contamination of samples, non-dedicated reusable sampling equipment will be decontaminated between the collection of each sample. Equipment will also be decontaminated prior to use and before removal from the site. The equipment decontamination procedure will be as follows:

- Trisodium phosphate and water wash,
- Potable water rinse,
- Distilled water rinse, twice.

The outside of sample bottles will be decontaminated, if necessary, by immersing the bottle up to the neck in distilled water. Solvents will not be used in the external washing of sample bottles.

Since the drum storage area is paved and no evidence of surface spillage is observable, the drill rig should not require decontamination before leaving the site. Decontamination of the augers used for drilling will be performed at a cleaning station removed from the drum storage area. The augers will be cleaned using a high pressure hot water or steam cleaning unit. Additional scrubbing may be required to remove encrusted materials. The augers will either be cleaned inside of a containment trough, or a sump area will be constructed using plastic sheeting, containment curbing and a lined catch basin (e.g. half drum sunk into the ground). Decontaminated equipment will be stored on plastic sheeting and/or platforms above the ground surface. Decontamination of the drill augers will occur prior to the start of work and when leaving the site, as well as between each borehole. Rinse water generated will be collected and analyzed for hazardous waste parameters. The rinse water will either be discharged to the sanitary sewer system or disposed of off-site at an approved disposal facility.

## 2.8 Site Health and Safety Plan

A site specific health and safety plan will be prepared prior to the beginning of closure activities. The plan will address hazard evaluation, site work plan tasks, necessary levels of protection, decontamination procedures, and emergency response information. All personnel involved in the closure activities will have the necessary training required to perform their assigned tasks and be given a copy of the Site Health and Safety Plan. All on-site workers must meet all applicable training, medical surveillance requirements etc. as specified in 29 CFR 1910 for hazardous site operations.

### SECTION 3

#### ANALYTICAL METHODS AND QA/QC

##### 3.1 Analytical Methods

RCRA VOCs will be analyzed according to SW-846 method 8240 by GC/MS. Non-target VOCs, if present, will be identified through a library search. PNAs will be analyzed according to SW-846 method 8310 by high performance liquid chromatography (HPLC) fluorescence detection. TPH (as mineral spirits and kerosene) will be analyzed according to ASTM method D3328 by GC FID. TPH and PNA samples will be prepared according to SW-846 method 3550.

##### 3.2 QA/QC Procedures

The QA objectives of laboratory analyses with respect to accuracy, precision, and sensitivity are to achieve acceptable data based on specified performance criteria. It is anticipated that at least 95% of the analyses will provide results meeting acceptance criteria. The general QC objective for such measurement data is to obtain reproducible and comparable measurements to a specified degree through the documented use of standardized procedures. Specific provisions for laboratory QA/QC are given below. For quality control purposes, one field duplicate per ten drum storage area soil samples will be collected and analyzed for the parameters outlined in Section 2.1. A field blank, matrix spike and matrix spike duplicate will also be prepared and analyzed for the parameters outlined in Section 2.1. Refer to the Quality Assurance Project Plan (QAPP) for a more detailed presentation of QA/QC procedures, analytical detection limits etc.

##### 3.2.1 Calibration Procedures

Samples analyzed for RCRA VOCs and PNAs will follow calibration and continuing calibration procedures outlined in SW-846 methods. Samples analyzed for TPH will follow calibration and continuing calibration procedures according to the laboratories standard operating procedure (SOP) for petroleum hydrocarbons.

### 3.2.2 Quality Control Checks

Internal quality control checks for VOC and PNA analyses will follow specifications outlined in SW-846 methods. Internal quality control checks for petroleum hydrocarbons will follow specifications outlined in Warzyn's SOP.

### 3.2.3 Precision, Accuracy and Completeness

Procedures to address precision, accuracy and completeness for VOCs and PNAs are outlined in SW-846 methods. Procedures for precision, accuracy and completeness for TPH are outlined in the laboratories SOP.

### 3.2.4 Corrective Action

If quality control audits result in the detection of unacceptable conditions or data, corrective action taken may include the following:

- re-analysis of the sample if holding time allowances permit;
- re-sampling and re-analysis;
- evaluating and amending sampling and analytical procedures; or
- accepting data, acknowledging the level of uncertainty.

### 3.2.5 Data Reduction, Validation and Reporting

Data reduction, validation and reporting is the responsibility of Warzyn Engineering Inc. Data reporting from the laboratory will be consistent with the CLP deliverable format. Laboratory results will be checked by Warzyn Engineering Inc. to determine the fraction of analyses that meet specified QC criteria.

## SECTION 4

### WASTE DISPOSAL PLAN

#### 4.1 Remaining Drums

All of the hazardous waste drums present on-site during the March 28, 1989 IEPA inspection have already been shipped to Avganic Industries, Inc. in Cottage Grove, Wisconsin for off-site disposal (Refer to Appendix C for copy of manifests). The central hazardous waste drum storage area has subsequently been relocated indoors to the mixing room adjacent to the main manufacturing area. It is intended to make this area the central hazardous waste drum storage area on a permanent basis. Hazardous waste storage will not occur in the present drum storage area during the time period required to complete the closure process. Any remaining pallets, or other debris remaining in the drum storage area, at the time of closure will either be reused on-site or disposed of in the plant's general refuse. Any ink residue on the pallets or debris will be scraped off and disposed of along with the D001 flammable hazardous waste ink sludges generated by manufacturing operations.

#### 4.2 Soil Cleanup Levels

Health-based cleanup levels were developed for the primary VOCs used in Croda's operations, as well as for carcinogenic PNAs. Based on Warzyn's experience, PNAs would be expected to be present in the spent kerosene waste stream. Since very little toxicity data exists for the other PNAs, the selected cleanup criteria for all of the carcinogenic PNAs is based on benzo(a)pyrene (B(a)P). Because of the relatively low toxicity of the primary VOCs (refer to Table 3) used at the site (xylene, toluene, MIBK), the selected cleanup criteria for total VOCs is based on the calculated level for methylene chloride, an identified potential carcinogen. The use of methylene chloride as the basis for total VOCs provides an extremely conservative approach in the establishment of health-based cleanup criteria. Individual health-based cleanup levels were developed for the following compounds:



- xylene,
- toluene,
- MIBK,
- methylene chloride,
- B(a)P.

Of the above mentioned compounds, methylene chloride and B(a)P presently qualify as potential carcinogens. Xylene, toluene and MIBK presently qualify as non-carcinogens.

#### 4.2.1 Exposure Pathway Assessment

Although groundwater is a possible source of human exposure to VOCs at the Croda site, it is not a likely source of human exposure. A subsurface hydrogeological investigation of the Croda site has yet to be performed. Based on regional hydrogeological data, it is probable that a saturated clay layer lies below the Croda site to a depth of approximately 60 feet. Based on the regional hydrogeology, as well as the distances from the site and depths of water wells known to exist within a one mile radius of the Croda site, potential contamination originating from the hazardous waste drum storage area would not be expected to impact existing water wells. Because of its low hydraulic conductivity and storage capacity, it is not anticipated that groundwater present in the clay layer could ever be used as a drinking water source. Furthermore, there are currently no water supply wells on-site, and the areas around the Croda facility are serviced by water from Lake Michigan supplied by the City of Chicago. For the reasons stated, groundwater was not considered as a source of human exposure to VOCs originating from the Croda site. Unlike the VOCs, any PNAs present in on-site soils would not be expected to migrate to the water table because of their high affinities for clay soils and low water solubilities. Because of the above-mentioned conditions, soil ingestion is expected to present the prime route of human exposure to chemicals originating from the Croda site.

#### 4.2.2 Soil Cleanup Level Calculations

Similar procedures were used to calculate soil cleanup levels for non-carcinogens and carcinogens in soil. In general, United States Environmental Protection Agency (EPA) risk assessment guidelines were used as a basis to calculate health based soil cleanup levels (Superfund Public Health Evaluation Manual (SPHEM), 1986). The following sections outline the procedures used to calculate the soil cleanup criteria for carcinogens and non-carcinogens.

4.2.2.1 Soil Cleanup Levels for Carcinogenic Chemicals. To determine the risk of cancer from exposure to carcinogenic chemicals in soil, the daily intake of the chemical from soil ingestion is multiplied by the chemical's EPA cancer potency factor. The result is a qualified estimate of an individual's likelihood of developing cancer as a result of exposure to the carcinogenic chemical at given concentrations and intake rates. The cancer risk due to the chemical exposure is calculated using Equation 1.

#### Equation 1: Cancer Risk

$$R = CPF \times DI$$

Where: R = Cancer risk level  
DI = Daily intake of chemical, mg/kg/day  
CPF = Cancer potency factor, (mg/kg/day)<sup>-1</sup>

The daily intake (DI) of the chemical is dependent upon the concentration of the chemical in soil, the rate of soil ingestion and the persons body weight. The daily intake of a chemical is calculated using Equation 2.

The cancer potency factor relates the level of chemical exposure to the probability of the occurrence of cancer in humans. The cancer potency factor was developed by the EPA after reviewing pertinent epidemiology studies, long term cancer bioassays and utilizing specific extrapolation procedures to predict cancer rates at low doses of chemical exposure. The cancer potency factor was derived to predict cancer rates based on the assumption that a person is exposed to the chemical for their entire life

(i.e., 70 years). It is unlikely that a person would be exposed to the Croda site for 70 years; therefore, the soil cleanup levels calculated should error on the conservative side.

Equation 2: Daily Intake-Carcinogens and Non-Carcinogens

$$DI = \frac{SCL (IR)}{(M) (1000^a)}$$

Where: DI = Daily intake of chemical, mg/kg/day  
SCL = Soil concentration (i.e., soil cleanup level), mg/kg  
IR = Soil ingestion rate, 0.1 g/day  
M = Average mass of an adult human, 70 kg  
a = Conversion factor, kg soil to g soil

This amount of soil intake appears to over-estimate the likely soil exposure at the Croda facility. The area of contamination is not used as an active work area, but rather as a storage area. Employees would likely be in contact with the area for only a brief period of time during the work day. The Croda facility is secured with a fence and is located in an industrial park. It was, therefore, assumed that adults would be the primary population exposed at the site. The weight for a typical adult specified by the EPA is assumed to be 70 kilograms (kg) (SEAM, 1987). An adult soil ingestion rate of 100 milligrams per day (mg/day) was used as the level of soil exposure (Superfund Exposure Assessment Manual (SEAM), 1987 and January 27, 1989 EPA interim final guidance). The soil concentration of the chemical will be used as the health based soil cleanup concentration.

To estimate the soil cleanup level, an acceptable risk of cancer was established and Equations 1 and 2 were combined to solve for the acceptable concentration of the chemical in soil (see Equation 3).

Equation 3: Carcinogenic Soil Cleanup Level

$$SCL = \frac{R}{CPF} \times \frac{M}{IR} 1000^a$$

Where: SCL = Soil cleanup level, mg/kg  
R = Risk level (e.g.,  $10^{-6}$ )  
CPF = EPA carcinogenic potency factor for the compound,  
(mg/kg/day)<sup>-1</sup>  
M = Average mass of an adult human, 70 kg  
IR = Soil ingestion rate, 0.1 g/day  
a = Conversion factor, g soil to kg soil

The proposed soil cleanup levels for B(a)P and methylene chloride, as well as their associated cancer potency factors, are presented in Table 2. Since the soil ingestion rate, as well as the application of the B(a)P and methylene chloride cleanup levels to the sum of all carcinogenic PNAs and VOCs, respectively, are believed to be extremely conservative estimates, a cancer risk factor of  $10^{-5}$  was used to calculate the corresponding carcinogenic cleanup levels.

4.2.2.2 Soil Cleanup Level Calculations for Non-Carcinogenic Chemicals. To estimate if the soil concentration of a non-carcinogen chemical poses a hazard to human health, the daily intake is determined and compared to the EPA reference dose (Rfd) for the chemical. The exposure assumptions that were used to calculate the soil cleanup levels for carcinogens were applied to the non-carcinogens. The reference dose is defined as the daily dose of a chemical which should not result in any signs of deleterious human health effects. There are daily doses determined for subchronic (AIS) and chronic (AIC) exposure periods. To determine the soil cleanup levels for the Croda facility, chronic reference doses were used as a conservative approach.

To determine if a chemical may pose a hazard, hazard indices (HI) were determined for each chemical. A HI is defined as the ratio of the daily intake over the AIC (see Equation 4).

Equation 4: Hazard Indices for Non-carcinogens

$$HI = \frac{DI}{AIC}$$

Where: HI = Hazard Index

DI = Daily chemical intake, mg/kg/day

AIC = Acceptable daily intake due to chronic exposure, mg/kg/day

If the daily intake is equal to the acceptable daily intake (Rfd), the HI is equal to 1. If the HI is equal to or less than 1, the chemical is not anticipated to pose a hazard to human health. To calculate the soil cleanup level, the HI is set equal to 1 (i.e.,  $DI = Rfd$ ). Equations 2 and 4 are combined and rearranged to solve for the soil chemical concentration which will result in an HI of 1 (see Equation 5).

Equation 5: Non-Carcinogenic Soil Cleanup Level

$$SCL = RFD \times \frac{M}{IR} \times 1000^a$$

Where: SCL = Soil cleanup level, mg/kg

RFD = EPA reference dose (AIC), mg/kg/day

M = Average mass of an adult human, 70 kg

IR = Soil ingestion rate, 0.1 g/day

a = Conversion factor, g soil to kg soil

The health-based soil standard for the specified non-carcinogenic compounds, as well as their respective reference doses, are presented in Table 3. These values are presented for reference purposes only since they are not incorporated in the final cleanup criteria.

4.2.3 Application of Soil Cleanup Levels

As mentioned previously, PNAs may be present at the Croda facility. Little pertinent toxicological data exists on PNAs. Of the PNAs, the most complete toxicology data base exists for B(a)P. This is the only PNA for which the EPA has calculated a cancer potency factor. No reference doses have been determined for the non-carcinogenic PNAs.

B(a)P is considered the most potent chemical carcinogen in its class. Because of this, the soil cleanup level that is calculated for B(a)P is generally applied to the other carcinogenic PNAs as a conservative soil cleanup criteria. This assumption will be made for the Croda facility. The sum of the soil concentrations of all carcinogenic PNAs found at the site will be calculated and compared to the B(a)P cleanup level (i.e., 0.6 milligrams per kilogram), which is based on an accepted cancer risk level of  $10^{-5}$ . The following PNAs are considered carcinogenic:

- benzo(a)anthracene
- benzo(a)pyrene
- benzo(b)fluoranthene
- chrysene
- dibenzo(a,h)anthracene

It will be assumed that the reduction of carcinogenic PNAs below the established cleanup criteria of 0.6 milligrams per kilogram (mg/kg) will also reduce the non-carcinogenic PNAs to acceptable health-based levels. The following PNAs qualify as non-carcinogenic:

- |                        |                           |
|------------------------|---------------------------|
| • acenaphthene         | • benzo(k)fluoranthene    |
| • acenaphthylene       | • fluoranthene            |
| • anthracene           | • fluorene                |
| • benzo(g,h,i)perylene | • indeno(1,2,3-c,d)pyrene |
| • pyrene               | • phenanthrene            |

Because of the relatively low toxicity (refer to Table 3) of the primary VOCs used at the site (xylene, toluene, MIBK), the selected cleanup criteria for total VOCs is based on the calculated level for methylene chloride. The sum of the soil concentrations of all SW-846 Method 8240 VOCs found at the site will be calculated and compared to the methylene chloride cleanup level (i.e. 900 milligrams per kilogram), which is based on an accepted cancer risk level of  $10^{-5}$ . Comparing total VOCs levels to the health-based standard developed for methylene chloride represents a very conservative approach to the development of cleanup criteria for the primary VOCs (xylene, toluene, MIBK) used at the site.

#### 4.2.4 Exposures to Multiple Chemicals

Since the total concentrations of both the VOCs and carcinogenic PNAs will already be summed up and compared to a conservative health-based standard, the potential additive effects of multiple chemicals within a given group of compounds have already been accounted for in the analysis. The potential does exist, though, for more than one carcinogen to be detected in the analyses (e.g. B(a)P and methylene chloride). Equations 6 and 7 would be utilized, if necessary, to evaluate the additive effects of multiple carcinogenic and non-carcinogenic compounds:

##### Equation 6: Combined Carcinogenic Effects

$\text{Risk} = (\text{CPF}_1 \times \text{DI}_1) + (\text{CPF}_2 \times \text{DI}_2) \dots + (\text{CPF}_n \times \text{DI}_n)$  for n compounds

Where: CPF and DI have been previously defined in Equations 1 and 2, respectively.

##### Equation 7: Combined Hazard Indices

$\text{HI}_n = \frac{C_1}{\text{SCL}_1} + \frac{C_2}{\text{SCL}_2} + \frac{C_n}{\text{SCL}_n}$  for n compounds

Where: C = Concentration of chemical in soil, mg/kg

SCL = Corresponding soil cleanup level for chemical, mg/kg

In the case of the combined carcinogenic effects, the sum of the products will be compared against a carcinogenic risk factor of  $10^{-5}$ . If the sum is less than  $10^{-5}$ , the soil concentrations of the chemicals will be assumed to be safe. If the sum exceeds  $10^{-5}$ , the applicable cleanup levels will be considered exceeded. A similar comparison is used for the combined hazard index for non-carcinogenic compounds. If the sum of all the ratios is less than one, the soil concentrations of the chemicals will be assumed to be safe. If the sum of the ratios is greater than one, the applicable cleanup levels will be considered exceeded. Both approaches assume the adverse effects of multiple chemicals are additive, intakes are small and no synergistic effects occur between compounds.

#### 4.2.5 Statement of Qualification

The soil cleanup criteria were developed only for the classes of chemicals discussed in this section. If other chemicals potentially of concern are detected at the Croda site, a similar approach would be used to develop additional cleanup criteria. If the subsurface hydrogeology differs significantly from the regional hydrogeology, the soil cleanup criteria would have to be modified to reflect potential groundwater exposure to the identified chemicals. If materials originating from the drum storage area are found to be impacting the storm sewer system discharging to the North Branch Chicago River, applicable water quality criteria might have to be incorporated into the risk assessment.

#### 4.3 Soil Remediation Plan

Soil within the drum storage area will be excavated to a depth of 2 feet using a backhoe if contamination in excess of the cleanup criteria (i.e. 0.6 mg/kg total carcinogenic PNAs or 900 mg/kg total VOCs) is detected in the 6-inch to 2-foot interval samples throughout the drum storage area. Excavated soil will be loaded directly into dump trucks and hauled away for final disposal. Staging will be done on plastic sheeting in order to catch any contaminated soil which is spilled during the loading process. If detected contamination in excess of the cleanup criteria is believed to be in isolated areas, excavation activities will be limited to the isolated grid interval(s) of contamination. If contamination in excess of the cleanup criteria is detected in the soil samples from areas impacted by surface runoff from the storage area (i.e. boring B8 to B13), the excavation activities will include the bare ground area along the entire eastern boundary of the drum storage area up to a distance of 5 feet away from the edge of the asphalt surface.

In the absence of soil contamination which would require excavation of the drum storage area, any residue adhering to the asphalt surface will be removed by scraping and/or brushing. The asphalt surface will then be steam



cleaned and triple rinsed. All wash and rinse water will be collected, analyzed for RCRA hazardous waste characteristics and disposed of in a proper manner.

If a K086 listed hazardous waste constituent is present, excavated soil will be disposed of at a secure hazardous waste landfill or incinerated. If the waste is classified as non-hazardous (or Illinois Special Waste), the excavated soil will be disposed of at an approved sanitary landfill. An appropriate disposal site will be selected once the analytical results are reviewed for RCRA hazardous waste classification, and it is determined if constituents affected by the RCRA landfill ban are present. Contaminated soil which qualifies as a K086 hazardous waste is presently covered by the "soft hammer" provisions of the RCRA landfill ban. In order to verify the effectiveness of the remediation, four discrete soil samples will be collected from the base of the excavated area and analyzed for the contaminants identified during the initial sampling activities.

If the levels of compounds of concern in excess of cleanup criteria extend below the 6-inch to 2-foot interval, an additional scope of work will be developed. The additional scope of work may include excavation of contaminated soil to lower depths, a second phase of soil borings and sampling to define the extent of contamination, the installation of groundwater monitoring wells (depending on the depth to the water table) or alternative methods of remediation (e.g. soil vapor extraction, bioremediation). The development of an additional scope of work also applies to potential contamination in excess of cleanup criteria originating from the former UST (i.e. samples collected from borings B6 and B7).

Even though the clay soil environment typical of the regional geology would be expected to attenuate any potential contamination originating from the drum storage area, it is recognized that off-site migration of VOCs via the water table could result in vapor migration into neighboring storm sewer pipes, utilities, basements etc. If the levels of detected contaminants (or

remaining contaminants following the excavation of two feet of surface soil) are below the applicable soil cleanup criteria, and migration to the depth of the water table has yet to occur, a further scope of work would be developed if the potential for migration to the water table exists (based on the levels of detected contaminants, geologic conditions and depth to the water table). An additional scope of work would be expected to include the installation of groundwater monitoring wells, both within the drum storage area and at selected locations near the perimeter of the site. The wells would be sampled on a periodic basis, for a specified period of time, to evaluate the potential for off-site migration of any remaining contaminants.

A similar scope of work would also apply if remaining contaminant levels are below soil cleanup criteria, but migration of those contaminants has already impacted the water table. In this case, the locations of the monitoring wells would be designed to monitor both the rate and attenuation of potential off-site migration. In either case, an alternative remediation method (e.g. pump and treat impacted groundwater, excavate the source of contamination) would be specified if the potential exists for off-site migration of liquid or vapor phase materials originating from the hazardous waste drum storage area.

**SECTION 5**  
**STATUS OF AREA AFTER CLOSURE**

Closure of the drum storage and UST areas will be complete after the Closure Plan is executed. The facility would then qualify as a large quantity generator, and will generate and store more than 1000 kilograms per month of hazardous waste for less than 90 days. There is presently no intention of utilizing the drum storage area for hazardous waste storage in the future. Future hazardous waste storage will be moved indoors. If the area is considered clean after analysis of the soil samples, it will be left as is. If contaminated soil is excavated, it will be replaced with clean fill material. The area will be paved with asphalt or concrete prior to re-utilizing it for equipment storage.

**SECTION 6**  
**CLOSURE COST ESTIMATE**

A breakdown of the closure cost estimate by activity is presented below. The cost estimate includes the excavation and off-site landfilling of 360 cubic yards of soil (i.e. 125-feet by 30-feet by 2-foot depth assuming a 30% bulking factor) as a K086 hazardous waste. Off-site soil disposal would only be required if contamination is identified during soil sampling activities. It was assumed that only the first 5 feet of each boring would be analyzed. Analytical costs for running all of the parameters mentioned in Sections 2.1 are included for 20 soil samples from the drum storage area, 10 soil samples from the UST area, three field duplicates, one field blank, one matrix spike, one matrix spike duplicate, four excavation clean-up verification samples and RCRA hazardous waste characterizations for the rinse water and excavated soil. Oversight costs by an independent professional engineer were included for the soil sampling and soil excavation activities.

**Closure Cost Estimate**

I. Soil Sampling (assumes two days)	
-Sampling (includes safety protection)	\$ 12,000
-Analytical	\$ 42,000
II. Soil Removal, Transportation and Disposal	
-Excavation and Disposal (includes safety protection and backfill), if necessary	\$ 72,000
-Oversight	\$ 5,000
III. Closure Report/Certification	<u>\$ 11,000</u>
TOTAL CLOSURE COSTS	\$142,000

## SECTION 7 CERTIFICATION OF CLOSURE

The Closure Plan will be executed by an independent environmental engineering firm in conjunction with Croda, and certified by a responsible corporate officer of Croda and an independent professional engineer registered in the State of Illinois (Refer to Appendix D for certification documents). Certification will be completed within 60 days upon completion of closure. The independent professional engineer will be present during soil sampling and any necessary soil removal activities. Croda will notify the designated representative of the IEPA prior to the performance of any critical activities. Documentation supporting the professional engineer's certification will be furnished upon request until Croda has been released from its financial assurance requirements.

Upon completion of closure, a Closure Documentation Report, along with closure certification will be submitted to the IEPA documenting closure activities. This report will include:

- the volume of waste and soil removed,
- a description of the method of waste handling and transportation,
- manifest numbers for off-site disposal,
- a description of the sampling and analysis methods used,
- a chronological summary of closure activities and costs,
- photo documentation of closure,
- all analytical results.

**SECTION 8**  
**REFERENCES**

Fetter, C.W., Applied Hydrogeology, Second Edition, Merrill Publishing Co., 1988.

Freeze, R.A. and J.A. Cherry, Groundwater, Prentice-Hall Inc., 1979.

Levin, H.L., The Earth Through Time, W.B. Saunders Company, 1978.

Lineback, J.A., Quaternary Deposits of Illinois, 1 Plate, Illinois State Geological Survey, 1979.

U.S. EPA, 1987. Superfund Exposure Assessment Manual, U.S. EPA, Office of Emergency and Remedial Response, Washington, D.C.

U.S. EPA, 1986. Superfund Public Health Evaluation Manual, U.S. EPA/540/1-86/060 (OSWER Directive 9285. 4-1), U.S. EPA Office of Emergency and Remedial Response, Washington, D.C.

United States Geological Survey, "Park Ridge, Illinois Quadrangle", 7.5 Minute Series (Topographic), 1 Plate, United States Geological Survey, 1963, Photorevised 1972 and 1980.

Willman, H.B. and others, Geologic Map of Illinois, 1 Plate, Illinois State Geological Survey, 1967.

Willman H.B. and others, Handbook of Illinois Stratigraphy, Bulletin 95, Illinois State Geological Survey, 1975.

William H.B., Summary of the Geology of the Chicago Area, Circular 460, Illinois State Geological Survey, 1971.

Table 1

Sample Quantities, Bottles Preservation and Packaging  
Requirements for Soil Samples  
Croda Inks Corporation

ANALYSIS	BOTTLES AND JARS	PRESERVATION	HOLDING TIME	VOLUME OF SAMPLE	SHIPPING	PACKAGING
SOIL						
CLP Protocol						
Low Concentration (Organics)						
PNAs and Total Petroleum Hydrocarbons	One 8-oz. wide mouth glass jar. with teflon cap	Iced to 4°C	7 days extraction	Fill 3/4 full Priority One	Federal Express Priority One	No. 1 foam liner or vermiculite
Volatiles	One 4-oz. wide mouth glass jar. with teflon cap	Iced to 4°C	14 days	Fill completely no head space	Federal Express Priority One	No. 1 foam liner or vermiculite

[WP1]  
40045R01MSR/gmg/JAH

Table 2

Soil Cleanup Levels For Carcinogenic Compounds  
Based On An Adult Population

<u>Compound</u>	<u>Target Cleanup Level (mg/kg)<sup>1</sup></u>	<u>Carcinogenic Potency Factor (mg/kg/day)<sup>-1</sup></u>
benzo(a)pyrene <sup>2</sup>	0.6	11.5
methylene chloride <sup>3</sup>	900	.0075

Notes:

1. Based on cancer risk factor of  $10^{-5}$  and adult soil ingestion as the only potential human exposure pathway.
2. Target cleanup level applies to sum of all carcinogenic PNA concentrations.
3. Target cleanup level applies to sum of all VOC concentrations.

WP1  
40045R01MSR/gmg/JAH



Table 3


Soil Cleanup Levels For Non-Carcinogenic Compounds  
Based On An Adult Population

<u>Compound</u>	<u>Target Cleanup Level (mg/kg)<sup>1</sup></u>	<u>Reference Dose (mg/kg/day)</u>
methyl isobutyl ketone	35,000	.05
toluene	210,000	0.3
xylylene	1,400,000	2.0

Notes:

1. Based on adult soil ingestion as the only potential human exposure pathway.

WP1  
40045R01MSR/gmg/JAH



## NOTES:

BASE MAP DEVELOPED FROM PARK RIDGE,  
ILLINOIS 7.5 MINUTE USGS TOPOGRAPHIC  
QUADRANGLE MAP DATED 1963,  
PHOTOREVISED 1972 & 1980.



north

SCALE: 1" = 2000'

WARZYN



USGS MAP


CRODA INKS CORPORATION  
NILES, ILLINOIS

DWN. D.L.L. APP'D. MBR DATE 10/5/89 40045.02-A1

FIGURE 1



ASTER BLUE PRINT NO. 510245



#### LEGEND

B1 ♦ PROPOSED BORING LOCATION & NUMBER

#### NOTES:

BASE MAP DEVELOPED FROM SITE PLAN PROVIDED BY CRODA INKS CORP., DATED MARCH 1, 1980.

ALL BORING LOCATIONS ARE APPROXIMATE.



SCALE: 1" = 20'

PROPOSED BORING LOCATION MAP	
Client: CRODA INKS CORPORATION NILES, ILLINOIS	Project Number: 40045.02-B1
Drawn By: D.L.L.	Checked By:
Designed By:	DATE:
Approved By:	REFERENCE:
WARZYN INCORPORATED 1000 N. WILSON AVENUE NILES, ILLINOIS 60057 TEL: (815) 398-1000 FAX: (815) 398-1001	

FIGURE 3



# CHAIN OF CUSTODY RECORD

PROJ. NO.		PROJECT NAME				NO. OF CON- TAINERS	<div></div> REMARKS													
SAMPLERS: (Signature)																				
LAB NO.	DATE	TIME	COMP.	GRAB	STATION LOCATION															
Relinquished by: (Signature)			Date / Time		Received by: (Signature)			Relinquished by: (Signature)			Date / Time		Received by: (Signature)							
Relinquished by: (Signature)			Date / Time		Received by: (Signature)			Relinquished by: (Signature)			Date / Time		Received by: (Signature)							
Relinquished by: (Signature)			Date / Time		Received for Laboratory by: (Signature)						Date / Time									
Remarks																				

FIGURE 4 CHAIN OF CUSTODY FORM




FIGURE 5 CHAIN OF CUSTODY SEAL

Project #	_____	Lab #	_____
Sample Description	_____		
Date Collected	_____	By	_____
Preservative:	HNO <sub>3</sub>	H <sub>2</sub> SO <sub>4</sub>	NaOH
	Filtered	None	Other _____
			Unfiltered

FIGURE 6 SAMPLE LABEL

**APPENDIX A**  
**HAZARDOUS WASTE ANALYSES**



8  
312 967 2232  
CHEM-CLEAR/CH60

312 967 2232 CRODA INKS NILES

02/89 08:45

004

TEL No.1 312 868 5408

May 31, 89 13:44 P.03

# CleanHarbors

## LABORATORY WASTE DISPOSAL DECISION FORM

R 32871

LABORATORY

Profile Sheet Number

A waste analysis report ( ☒ has ) ( ☐ has not ) been prepared. If not, none is required according to company policy because

- ☐ waste is a virgin product.
- ☐ waste has been previously received.
- ☐ waste is not sampleable.
- ☐ non hazardous waste.

I have reviewed the profile sheet and analytical report (if required) and find the waste as represented by the profile sheet

- ☒ may be received at the facility.
- ☐ may not be received at the facility.

Reason: \_\_\_\_\_

### CONDITIONS OF ACCEPTANCE

Chemical Conditions (pH, flash point, etc.): \_\_\_\_\_

Physical Conditions: \_\_\_\_\_

Packaging Conditions (weight, container type, etc.): \_\_\_\_\_

CLHB Code CCR 11 C.T. Disposal Outlet CWH Chicago

Alt. Rec. Code(s) \_\_\_\_\_ Alt. Disp. Outlet(s) \_\_\_\_\_

Technical Manager Signature: Marjorie C. Mahoney 3-6-89  
Date

SALES

MAR 15 1989

Reviewed by \_\_\_\_\_

8  
312 967 2232  
CHEM-CLEAR/CHGO

312 967 2232 CRODA INKS NILES

5/02/89 08:46

005

TEL No.1 312 868 5408

May 31,89 13:45 P.04

# Clean Harbors

## CUSTOMER SERVICE WASTE DISPOSAL DECISION FORM

CONTRACT: CR0230

GENERATOR: Croda Inc

PROFILE #: 132811

DESCRIPTION: waste cleaning soln

CAT. CODE: CCR

RECEIVING CODE(S): CCI

RATE: \_\_\_\_\_

COST: \_\_\_\_\_

CUSTOMER CTL#: \_\_\_\_\_

-- PRICING COMMENTS --

KILN PAC = 200 EA

-- TREATMENT STATUS --

Heat Incineration

PACKAGING REQUIREMENTS

Kiln packed 200 lb. wt limit

DOT NAME:

Registries Waste Liquid N.O.S

HAZARD CLASS:

ORM-E

UNNA # 149189

EPA Waste #

KOPG

LANDFILLABLE (Y/N):

N

LOG DATE: \_\_\_\_\_

APPROVED (Y/N): Y

APPROVAL DATE: \_\_\_\_\_

LOT NO.: 8132

CUSTOMER CODE: CH113

COMMENTS: Need generator signature

SAVE THIS RECORD? (Y/N): \_\_\_\_\_

MAR 14 1989

CHEM-CLEAR/CHGO

312 967 2232 CRODA INKS NILES

02/89 08:46

006

B1 312 868 5408

TEL No. 1 312 868 5408

May 31, 89 13:45 P.05



## WASTE MATERIAL PROFILE SHEET

8132 R 32811

Profile Number

LOCATION CRODA INK (AS THE DEPT. SA MANAGER)  
 FACILITY ADDRESS 7777 HARRING  
WILCO, ILL. 60448  
 CUSTOMER CONTACT JOHN SIMPSON  
 CUSTOMER PHONE 312-968-0440  
 GENERATOR U.S. EPA ID # 11LD01022931124  
 TECHNICAL CONTACT DEAN ROEING TITLE SALES PHONE 312-967-7578  
 GENERATOR'S COMMON NAME FOR WASTE WASTE CLEANING SOLUTION / Ink  
 PROCESS GENERATING WASTE INK REMOVAL SERVICE

## B. PHYSICAL CHARACTERISTICS OF WASTE

STATE ILL FM RANGE 100-140 % ORGANIC HALOGEN NO COLOR NO  
 FLASH POINT (°F) < 100 100-140 141-200 > 200 NO FLASH

## C. COMPOSITION (INCLUDE INERT COMPONENTS, SEE B. ETC.)

SOLIDS - Ink  
Acetone / Ink / Solvent  
Surfactant / Ink  
Resin up to 40

## RANGES ARE PERMISSIBLE

## D. DOT, OR TRANSPORTATION SHIPPING INFORMATION

D.O.T. HAZARDOUS MATERIAL ☐ YES ☒ NO

D.O.T. SHIPPING NAME

D.O.T. HAZARD CLASS K096

UNHA # REPORTABLE QUANTITY VALUE

## E. SHIPMENT METHOD

☐ BULK LIQUID ☐ BULK SOLID ☐ DRUM (200L)☐ OTHER (SPECIFY)

## F. ANTICIPATED VOLUME

QUANTITY PER 12 ☐ BULK ☒ DRUMS ☐ CUBIC YDS.  
☐ ONE TIME ☐ QUARTER ☐ YEAR

## G. WASTE DISPOSAL STATUS

U.S. EPA HAZARDOUS WASTE ☐ YES ☒ NO

U.S. EPA HAZARDOUS WASTE NUMBER

STATE HAZARDOUS WASTE ☐ YES ☒ NO

STATE HAZARDOUS WASTE NUMBER

IS THIS WASTE BANNED FROM LAND DISPOSAL UNDER FEDERAL REGULATIONS?

☐ YES ☒ NOSPECIFIC GENERATOR REQUESTS FOR DISPOSAL PLEASE QUOTE TOJOHN SIMPSON - CHICAGO FIELD SERVICE312-968-0440

## PHYSICAL STATE &amp; TYPE

(CHECK SEVERAL BOXES IF APPLICABLE)

☐ THICK VISCOUS LIQUID ☐ SOLID WITHOUT FREE LIQUIDS  
☐ LIQUID WITH NO SETTLED SOLIDS ☐ POWDER  
☒ UNDESIGNATED NATURE

% LIQUID 5 % SOLID 95  
 H. METALS ☐ TOTAL (PPM) ☐ EPA EXTRACTION PROCEDURE (PPM) WUR

ARSENIC (As)	_____	SELENIUM (Se)	_____
BARIUM (Ba)	_____	SILVER (Ag)	_____
CADMIUM (Cd)	_____	COPPER (Cu)	_____
CHROMIUM (Cr)	_____	NICKEL (Ni)	_____
CHROMIUM HEX. (Cr)	_____	ZINC (Zn)	_____
LEAD (Pb)	_____	TIN (Sn)	_____
MERCURY (Hg)	_____	OTHER	_____

I. OTHER COMPONENTS - TOTAL PPM WUR

CYANIDES \_\_\_\_\_ PCBs \_\_\_\_\_  
 SULFIDES \_\_\_\_\_ PESTICIDES ☐ YES ☒ NO SPECIFY \_\_\_\_\_  
 WATER REACTIVE ☐ YES ☒ NO DIOXINE ☐ YES ☒ NO

## J. SAMPLE STATUS

☒ REPRESENTATIVE SAMPLE HAS BEEN SUPPLIED  
 CLEAN HARBORS HAS WAIVED THE SAMPLE REQUIREMENT FOR THE FOLLOWING REASON

- ☐ WASTE IS AN UNUSED (MIGN) PRODUCT (ATTACH MEDS)  
☐ WASTE HAS BEEN PREVIOUSLY RECEIVED BY CLEAN HARBORS  
☐ WASTE CAN NOT BE SAMPLED  
☐ WASTE IS NON HAZARDOUS  
☐ WASTE WAS GENERATED FROM A SPILL

## K. OTHER COMMENTS (FOR CUSTOMER'S USE)

NO SIGNATURE AVAILABLE UNTIL R10  
APPROVED

## L. FOR CLEAN HARBORS USE

## GENERATOR'S CERTIFICATION

I hereby certify that all information submitted in this and attached documents is correct to the best of my knowledge. I certify that the waste is not radioactive, pyrophoric, explosive or shock sensitive. I also certify that any samples submitted are representative of the actual waste.

CIR 100

AUTHORIZED SIGNATURE

NAME (PRINT)

DATE

8  
01 312 868 5408  
CHEM-CLEAR/CHGO  
ENT BY: A

12 967 2232 CRODA INKS NILES

02/89 08:47 008

TEL No. 1 312 868 5408  
1 5-1-89 4:55PM

Jun 01, 89 14:46 P.02  
02/89 01 312 868 5408

# Clean Harbors

## WASTE ANALYSIS REPORT/DECISION SHEET

8132

LAB SAMPLE TRACKING #

154

BOX RETAIN #

R 32810

PROFILE SHEET #

DATE IN 3-6-89 DATE OUT \_\_\_\_\_ LAB # 022203

ANALYSIS: Accept RESULT/NOTE \_\_\_\_\_ ANALYST: VND

PHYSICAL DESCRIPTION: single phase liquid

APPEARANCE: gray

% SOLID: 0

PH: 9

WATER MIX: soluble

IGNITABLE SCREEN: >140

BTU: POOR

% CHLORINE: ND

REACTIVE CYANIDES SCREEN: ND

REACTIVE SULFIDES SCREEN: ND

PCB'S: —

TOC: —

SUPPLEMENTAL ANALYSIS: \_\_\_\_\_

RESULTS APPROVED: Maryelle C. Mahoney DATE: 3-6-89  
LABORATORY MANAGER

☐ APPROVED

☐ DISAPPROVED

DISPOSAL OUTLET: Waste Management B. TOC / Trine

CODE: H82

## APPENDIX B

### MATERIAL SAFETY DATA SHEETS FOR PRIMARY RAW MATERIAL AND CLEANING SOLVENTS

## MATERIAL SAFETY DATA SHEET

UNOCAL 76  
UNOCAL CHEMICALS DIVISION  
PETROCHEMICALS GROUPProduct Name: THINNER 23716  
Product Code No: 23716Page 1 of 7  
Issue Date 10/04/88

## MANUFACTURER


UNOCAL CHEMICALS DIVISION  
UNION OIL COMPANY OF CALIFORNIA  
1345 N. MEACHAM  
SCHAUMBURG, ILLINOIS 60196CONTACT FOR FURTHER INFORMATION:  
MSDS COORDINATOR (312) 619-2644

## Transportation Emergencies:

Call CHEMTREC  
(800) 424-9300 Cont. U.S.  
(202) 483-7616 (Collect)  
from Alaska & HawaiiHealth Emergencies:  
CALL LOS ANGELES POISON  
INFORMATION CENTER (24 hrs.)  
(800) 356-3129

## PRODUCT IDENTIFICATION

PRODUCT NAME: THINNER 23716  
GENERIC NAME: SOLVENT BLEND  
DOT PROPER SHIPPING NAME: PAINT RELATED MATERIAL  
ID NUMBER: NA1263  
DOT HAZARD CLASSIFICATION: FLAMMABLE LIQUID



## SECTION I - HAZARDOUS INGREDIENTS/EXPOSURE LIMITS

HAZARDOUS INGREDIENTS	CAS NUMBER	TLV/PEL	UNITS	AGENCY	TYPE
LACTOL SPIRITS	64742-89-8	NONE			
CYCLOHEXANE 3	110-82-7	300 300 375	PPM PPM PPM	OSHA ACGIH ACGIH	TWA TWA STEL
HEPTANE 35	142-82-5	500 400 500	PPM PPM PPM	OSHA ACGIH ACGIH	TWA TWA STEL
TOLUENE 27	108-88-3	200 100 150 300 500 200	PPM PPM PPM PPM PPM PPM	OSHA ACGIH ACGIH OSHA OSHA CAL OSHA	TWA TWA STEL CEIL EXCUR EXCUR
METHYL CYCLOHEXANE 35 100%	108-87-2	500 400 500	PPM PPM PPM	OSHA ACGIH ACGIH	TWA TWA STEL
C6-C8 PARAFFINS	NONE	NONE			
C6-C8 CYCLOPARAFFINS	NONE	NONE			

042-002

02. 21. 89 02:00 PM \*UNOCAL CHEMICALS

P03

Product Name: THINNER 23716  
Product Code No: 23716

Page 2 of 7  
Issue Date 10/04/88

SECTION IA - THIS PRODUCT CONTAINS THE FOLLOWING CHEMICALS SUBJECT TO  
THE REPORTING REQUIREMENTS OF SARA 313 AND 40 CFR 372:

LISTED INGREDIENTS	CAS NUMBER	WEIGHT PERCENT RANGE
TOLUENE	108-88-3	14.45 - 22.10
CYCLOHEXANE	110-82-7	0.95 - 2.85



# MATERIAL SAFETY DATA SHEET

EFFECTIVE DATE: AUGUST 17, 1985.

42074

Union Carbide Corporation urges the customer receiving this Material Safety Data Sheet to study it carefully to become aware of hazards, if any, of the product involved. In the interest of safety you should (1) notify your employees, agents, and contractors of the information on this sheet, (2) furnish a copy to each of your customers for the product, and (3) request your customers to inform their employees and customers as well.

## I. IDENTIFICATION

PRODUCT NAME: CELLOSOLVE® ACETATE

CHEMICAL NAME: 2-Ethoxyethyl Acetate

CHEMICAL FAMILY: Esters

FORMULA:  $\text{CH}_3\text{COOC}_2\text{H}_4\text{OC}_2\text{H}_5$

MOLECULAR WEIGHT: 132.16

SYNONYMS: Ethylene Glycol Monoethyl Ether Acetate; 2-Ethoxyethanol Acetate

DEPARTMENT OF  
TRANSPORTATION

Hazard Classification  
Shipping Name

Combustible liquid  
Ethylene Glycol Monoethyl Ether Acetate

CAS # 11-15-9

CAS NAME

Ethanol, 2-ethoxy-, Acetate

## II. PHYSICAL DATA

BOILING POINT,  
760 mm Hg

156.3°C (313.3°F)

FREEZING POINT

-61.7°C  
(-79.1°F)

SPECIFIC GRAVITY  
( $\text{H}_2\text{O} = 1$ )

0.9748 at 20/20°C

VAPOR PRESSURE  
at 20°C

2 mm Hg

VAPOR DENSITY  
(air = 1)

4.6

SOLUBILITY IN  
WATER, % by wt.

22.9 at 20°C

PERCENT VOLATILES  
BY VOLUME

100

EVAPORATION RATE  
(Butyl Acetate = 1)

0.21

APPEARANCE AND ODOR

Water-white liquid; mild odor.

## III. INGREDIENTS

MATERIAL	%	TLV	HAZARD
2-Ethoxyethyl Acetate	100	See Section V	Irritant; toxic; combustible

## IV. FIRE AND EXPLOSION HAZARD DATA

FLASH POINT	126°F, Tag closed cup, ASTM D 56; 134°F, Tag open cup, ASTM D 1310		
FLAMMABLE LIMITS IN AIR, % by volume	LOWER	1.7	UPPER 6.7
EXTINGUISHING MEDIA	Use water spray, carbon dioxide, dry chemical, alcohol-type, or universal-type foams applied by manufacturers' recommended techniques.		
SPECIAL FIRE FIGHTING PROCEDURES	Use supplied breathing air and protective clothing.		
UNUSUAL FIRE AND EXPLOSION HAZARDS	None		

EMERGENCY PHONE NUMBER • 304/744-3487 • This number is available days, nights, weekends, and holidays.



Name	1, 1, 1-Trichloroethane	Synonyms and trade names	Methyl Chloroform α-Trichloroethane Chlorothene® VG Chlorothene® NU
Chemical class	Chlorinated Hydrocarbon		
Formula	CH <sub>3</sub> CCl <sub>3</sub>	M. W.	133

### Summary of hazards

Principal hazards	Breathing of high vapor concentrations may cause dizziness and incoordination; if prolonged, death due to respiratory failure.					
Flammability category (OSHA)	Flammable <input type="checkbox"/> IA <input type="checkbox"/> IB <input type="checkbox"/> IC Combustible <input type="checkbox"/> II <input type="checkbox"/> IIIA <input checked="" type="checkbox"/> IIIB <input type="checkbox"/> Nonflammable and not burnable					
Photochemically reactive components	Olefinic or Cyclo-Olefinic	0 vol %	Toluene	0 vol %	Trichloroethylene	0 vol %
	Aromatic C8 and above (xEB)	0 vol %	Ethyl Benzene	0 vol %	Ketones (branched hydrocarbon struc)	0 vol %

### Physical data

Boiling point at 760 mm	165 °F	74 °C	Vapor pressure at 68°F (20°C)	100 mm Hg
Melting (freezing) point at 760 mm	-36 °F	-38 °C	Vapor density at 60-90°F (15-32°C)	4.6 (air = 1)
Specific gravity at 39.2°F (4°C)	1.32	(H <sub>2</sub> O = 1)	Evaporation rate	7.5 (BuAc = 1)
Solubility in water at 68°F (20°C)	0.07	g/100 g H <sub>2</sub> O	Volatile at 70°F (21°C)	100 vol %
Appearance	Colorless liquid		Odor	Like ether, sweet

### Fire and explosion hazard data

Flash point closed <input type="checkbox"/> open cup	None °F	None °C	Flammable or explosive limits	Upper	10.5	vol %
Autoignition temperature	932 °F	500 °C		Lower	8.0	vol %
Firefighting hazards	Emits highly toxic fumes of hydrogen chloride, some phosgene.					

### Health hazard data

Occupational exposure standard: USOS <input checked="" type="checkbox"/> air <input type="checkbox"/> skin (eight-hour time weighted average)		1,900 mg/M <sup>3</sup>	350 ppm
Lethal dosage (* = principal route of absorption)	Oral LD 50 rat	10,300 mg/kg	Inhalation I <sub>h</sub> LC 50 rat * 8,000 <sup>7hr</sup> ppm
	Percutaneous LD 50 rat	mg/kg	Skin Skn LD 50 rabbit >15,800 mg/kg
Toxic level (human)	Breathing 2000 ppm: disturbance of equilibrium; concentrated vapors for 30 min: death due to respiratory failure.		
Skin and eye irritation	Mild.		
Relevant symptoms of exposure	Dizziness, lack of coordination.		
Effects of chronic exposure	Organic injury not expected due to stability and rapid excretion by lungs.		

NOTE: See Data Supplement for properties common to Organic Solvents.  
Deviations or comments are indicated in the following space.

First aid treatment: If unconscious, do not administer adrenalin.

Materials to avoid: Water; slow hydrolysis produces corrosive acid.

### Other data

Solubility of water in solvent at 20°C	0.05	g/100 g solvent	Solubility parameter
--	------	-----------------	----------------------

Name	Methylene Chloride	Synonyms and trade names	Dichloromethane Methylene Dichloride
Chemical family	Chlorinated Hydrocarbon		
Formula	CH <sub>2</sub> Cl <sub>2</sub>		
		M. W.	85

### Summary of hazards

Principal hazards	High volatility readily produces anesthetic concentrations; exposure may result in inebriation and dizziness; at very high concentrations, rapid unconsciousness.					
Flammability category (OSHA)	Flammable <input type="checkbox"/> IA <input type="checkbox"/> IB <input type="checkbox"/> IC      Combustible <input type="checkbox"/> II <input type="checkbox"/> IIIA <input checked="" type="checkbox"/> IIIB <input type="checkbox"/> Nonflammable and not burnable					
Photochemically reactive components	Olefinic or Cyclo-Olefinic	0 vol %	Toluene	0 vol %	Trichloroethylene	0 vol %
	Aromatic C8 and above (XEB)	0 vol %	Ethyl Benzene	0 vol %	Ketones (branched hydrocarbon struc)	0 vol %

### Physical data

Boiling point at 760 mm	104 °F	40 °C	Vapor pressure at 68°F (20°C)	340 mm Hg
Melting (freezing) point at 760 mm	-142 °F	-97 °C	Vapor density at 60-90°F (15-32°C)	2.9 (air = 1)
Specific gravity at 39.2°F (4°C)	1.34 (H <sub>2</sub> O = 1)		Evaporation rate	27.5 (BuAc = 1)
Solubility in water at 68°F (20°C)	1.3 g/100 g H <sub>2</sub> O		Volatile at 70°F (21°C)	100 vol %
Appearance	Colorless liquid		Odor	Sweet unpleasant

### Fire and explosion hazard data

Flash point <input type="checkbox"/> closed <input type="checkbox"/> open cup	None °F	None °C	Flammable or explosive limits	Upper	None vol %
Autoignition temperature	1139 °F	616 °C		Lower	None vol %
Firefighting hazards	Emits highly toxic fumes of phosgene or hydrogen chloride. Vapors form explosive mixture with air having high oxygen content.				

### Health hazard data

Occupational exposure standard: USOS <input checked="" type="checkbox"/> air <input type="checkbox"/> skin (eight-hour time weighted average)		1740 mg/M <sup>3</sup>	500** ppm		
Lethal dosage (* = principal route of absorption)	Oral Orl LD 50 rat	mg/kg	Inhalation Ihl LC 50 rat	*	ppm
	Percutaneous LD 50 rat	mg/kg	Skin Skn LD 50 rabbit		mg/kg
Toxic level (human)	Breathing 500 ppm: CNS and blood effects.				
Skin and eye irritation	Irritates skin. Eye contact is painful but not injurious unless confined.				
Relevant symptoms of exposure	Headache, dizziness, nausea, stupor, numbness and tingling of limbs, lethargy.				
Effects of chronic exposure	Dermatitis due to defatting action. No organic injury expected; rapidly excreted unchanged by the lungs.				

NOTE: See Data Supplement for properties common to Organic Solvents.  
 Deviations or comments are indicated in the following space.

\*\*Ceiling concentration 1000 ppm; maximum peak 2000 ppm for 5 minutes in any 2 hours. Reports of systemic injury were probably due to presence of impurities. FDA permits restricted use as solvent for certain food additives. (see CFR 121.1039) and as no-residue fluent for fruit and vegetable marking inks.  
 First aid treatment: If unconscious, do not administer adrenalin.

### Other data

Solubility of water in solvent at 20°C	0.20 g/100 g solvent	Solubility parameter	9.9
--	----------------------	----------------------	-----



# MATERIAL SAFETY DATA SHEET

EFFECTIVE DATE: APRIL 1, 1985

42-063

APR 29 1988

Union Carbide Corporation urges the customer receiving this Material Safety Data Sheet to study it carefully to become aware of hazards, if any, of the product involved. In the interest of safety you should (1) notify your employees, agents, and contractors of the information on this sheet, (2) furnish a copy to each of your customers for the product, and (3) request your customers to inform their employees and customers as well.

## I. IDENTIFICATION

PRODUCT NAME: BUTYL CELLOSOLVE®

CHEMICAL NAME: 2-Butoxyethanol

CHEMICAL FAMILY: Glycol Ethers

FORMULA:  $C_4H_9OC_2H_4OH$

MOLECULAR WEIGHT: 118.18

SYNONYMS: Ethylene Glycol Monobutyl Ether

DEPARTMENT OF  
TRANSPORTATION

Hazard Classification  
Shipping Name

Combustible liquid  
Combustible liquid, NOS

CAS # 111-76-2

CAS NAME

Ethanol, 2-butoxy

## II. PHYSICAL DATA

BOILING POINT,  
760 mm Hg

171.2°C (340.2°F)

FREEZING POINT

-70.4°C  
(-94.7° F)

SPECIFIC GRAVITY  
( $H_2O = 1$ )

0.9022 at 20/20°C

VAPOR PRESSURE  
at 20°C

0.6 mm Hg

VAPOR DENSITY  
(air = 1)

4.1

SOLUBILITY IN  
WATER, % by wt.

Complete

PERCENT VOLATILES  
VOLUME

100

EVAPORATION RATE  
(Butyl Acetate = 1)

0.08

APPEARANCE AND ODOR Colorless liquid; mild odor

## III. INGREDIENTS

MATERIAL	%	TLV	HAZARD
2-Butoxyethanol	100	25 ppm (skin) ACGIH 50 ppm (skin) OSHA	Toxic; Eye Irritant; Combustible

## IV. FIRE AND EXPLOSION HAZARD DATA

FLASH POINT	150°F, Tag Closed Cup, ASTM D 56; 157°F, Tag Open Cup, ASTM D 1310			
FLAMMABLE LIMITS IN AIR, % by volume	LOWER	1.1	UPPER	10.6
EXTINGUISHING MEDIA	Use water spray, carbon dioxide, dry chemical, alcohol-type, or universal-type foams applied by manufacturers' recommended techniques.			
SPECIAL FIRE FIGHTING PROCEDURES	Use self-contained breathing apparatus and protective clothing.			
UNUSUAL FIRE AND EXPLOSION HAZARDS	None			

EMERGENCY PHONE NUMBER • 1-800-UCC-HELP • This number is available days, nights, weekends, and holidays.



# MATERIAL SAFETY DATA SHEET



EFFECTIVE DATE: AUGUST 1, 1985

42-062A

Union Carbide Corporation urges the customer receiving this Material Safety Data Sheet to study it carefully to become aware of hazards, if any, of the product involved. In the interest of safety you should (1) notify your employees, agents, and contractors of the information on this sheet, (2) furnish a copy to each of your customers for the product, and (3) request your customers to inform their employees and customers as well.

## I. IDENTIFICATION

PRODUCT NAME: CELLOSOLVE® SOLVENT

CHEMICAL NAME: 2-Ethoxyethanol

CHEMICAL FAMILY: Glycol Ethers

FORMULA:  $C_2H_5OC_2H_4OH$

MOLECULAR WEIGHT: 90.12

SYNONYMS: Ethylene Glycol Monoethyl Ether

DEPARTMENT OF  
TRANSPORTATION

Hazard Classification  
Shipping Name

Combustible liquid  
Ethylene Glycol Monoethyl Ether

CAS # 110-80-5

CAS NAME

Ethanol, 2-ethoxy-

## II. PHYSICAL DATA

BOILING POINT,  
760 mm Hg

135.6°C (276.1°F)

FREEZING POINT

-90°C  
(-130°F)

SPECIFIC GRAVITY  
( $H_2O = 1$ )

0.9311 at 20/20°C

VAPOR PRESSURE  
at 20°C

4 mm Hg

VAPOR DENSITY  
(air = 1)

3.1

SOLUBILITY IN  
WATER, % by wt.

Complete at 20°C

PERCENT VOLATILES  
BY VOLUME

100

EVAPORATION RATE  
(Butyl Acetate = 1)

0.41

APPEARANCE AND ODOR

Colorless liquid; mild and nonresidual odor

## III. TOXICOLOGICAL DATA

MATERIAL	%	TLV	HAZARD
2-Ethoxyethanol	100	See Section V	Irritant; toxic; combustible

## IV. FIRE AND EXPLOSION HAZARD DATA

FLASH POINT	108°F, Tag closed cup, ASTM D 56; 120°F, Tag open cup, ASTM D 1310		
FLAMMABLE LIMITS IN AIR, % by volume	LOWER	1.7 at 200°F	UPPER 15.6 at 200°F
EXTINGUISHING MEDIA	Use water spray, carbon dioxide, dry chemical, alcohol-type, or universal-type foams applied by manufacturers' recommended techniques.		
SPECIAL FIRE FIGHTING PROCEDURES	Use self-contained breathing apparatus and protective clothing.		
UNUSUAL FIRE AND EXPLOSION HAZARDS	None		



SEP 2 1988

EMERGENCY PHONE NUMBER - 304/744-3487 - This number is available days, nights, weekends, and holidays.




# MATERIAL SAFETY DATA SHEET

EFFECTIVE DATE: September 1, 1983

42-061



Union Carbide Corporation urges the customer receiving this Material Safety Data Sheet to study it carefully to become aware of hazards, if any, of the product involved. In the interest of safety you should (1) notify your employees, agents, and contractors of the information on this sheet, (2) furnish a copy to each of your customers for the product, and (3) request your customers to inform their employees and customers as well.



## I. IDENTIFICATION

PRODUCT NAME: METHYL CELLOSOLVE®  
CHEMICAL NAME: 2-Methoxyethanol CHEMICAL FAMILY: Glycol Ethers  
FORMULA: CH<sub>3</sub>OC<sub>2</sub>H<sub>4</sub>OH MOLECULAR WEIGHT: 76.09  
SYNONYMS: Ethylene Glycol Monomethyl Ether

DEPARTMENT OF TRANSPORTATION Hazard Classification Combustible liquid  
Shipping Name Ethylene Glycol Monomethyl Ether

CAS # 109-86-4 CAS NAME Ethanol, 2-methoxy-

## II. PHYSICAL DATA

BOILING POINT, 760 mm Hg	124°C (256.1°F)	FREEZING POINT	-85.1°C (-121.2°F)
SPECIFIC GRAVITY (H <sub>2</sub> O = 1)	0.9663 at 20/20°C	VAPOR PRESSURE at 20°C	6.17 mm Hg
VAPOR DENSITY (air = 1)	2.62	SOLUBILITY IN WATER, % by wt	Complete
PERCENT VOLATILES BY VOLUME	100	EVAPORATION RATE (Butyl Acetate = 1)	0.62

APPEARANCE AND ODOR Water-white liquid; mild and characteristic odor.

## III. INGREDIENTS

MATERIAL	%	TLV	HAZARD
2-Methoxyethanol	100	See Section V	Toxic; Combustible

## IV. FIRE AND EXPLOSION HAZARD DATA

FLASH POINT	103°F, Tag closed cup ASTM D 56 110°F, Tag open cup ASTM D 1310		
FLAMMABLE LIMITS IN AIR, % by volume	LOWER	2.5	UPPER 19.8
EXTINGUISHING MEDIA	Use water spray, carbon dioxide, dry chemical, alcohol-type or universal-type foams applied by manufacturer's recommended technique.		
SPECIAL FIRE FIGHTING PROCEDURES	Use supplied breathing air and protective clothing.		
UNUSUAL FIRE AND EXPLOSION HAZARDS	None		

EMERGENCY PHONE NUMBER • 304/744-3487 • This number is available days, nights, weekends, and holidays.

IRANSLCHEM.  
3/31/86

042-054-H

Alan Spacing

PAGE 1 OF 4

Badische Corporation

Badische

# MATERIAL SAFETY DATA SHEET (300)

## PRODUCT NAME:

CYCLOHEXANONE

## ADDRESS

602 Copper Road, Freeport, Texas 77541

## PHONE NO.

(409)238-6100

## CHEMICAL NAME AND SYNONYMS:

Cyclohexanone; Anone; Cyclohexyl Ketone

APR 1986

## TRADE NAME AND SYNONYMS:

Cyclohexanone

## CHEMICAL FAMILY:

Ketone

## FORMULA:

C<sub>6</sub>H<sub>10</sub>O

## CAS REGISTRY NO.

108-94-1

## ISSUE DATE:

OCTOBER 1985

## REVISION DATE

New

## HAZARDOUS INGREDIENTS/COMPOSITION INFORMATION

Cyclohexanone - 99.8% minimum

## HEALTH HAZARD SUMMARY

### NS AND SYMPTOMS OF EXPOSURE:

Overexposure to cyclohexanone can cause irritation to the eyes, nose and throat. Eye contact with the liquid can cause moderately severe irritation and reversible corneal injury. Vapor contact is mildly irritating to the eyes. Liquid cyclohexanone is a moderate skin irritant. Repeated or prolonged contact can defat the skin resulting in irritation or dermatitis. Minor absorption can occur through skin contact. Cyclohexanone vapor is irritating to the nose and throat and excessive exposure can cause narcosis, headache, tremors and other central nervous system effects.

### PRIMARY ROUTES OF EXPOSURE:

SKIN CONTACT  
EYE CONTACT  
INHALATION

### EXPOSURE LIMITS:

OSHA PEL: 50 ppm (200 mg/m<sup>3</sup>) TWA

ACGIH TLV (1985-86): 25 ppm (100 mg/m<sup>3</sup>) TWA  
(skin)

### TOXICOLOGICAL PROPERTIES:

Oral - Rat LD50: 1.62 g/kg

Dermal - Rabbit LD50: 1.0 g/kg

INH - Rat: Exposure for 4 hours @ 20,000 ppm resulted in death of one of six animals.

INH - Guinea Pig: Exposure for 6 hours @ 4,000 ppm caused central nervous system depression and lacrimation.

INH - Monkey: Exposure for 6 hours/day for 50 days @ 190 ppm caused slight liver and kidney damage.

Cyclohexanone can cause irritation of the eyes, nose and throat in humans at 50 ppm. Because it can be detected at 25 ppm in air, its good odor warning properties should prevent injury. The TLV was set at 25 ppm to prevent irritation and possible liver and kidney damage.

This information relates to the particular product described and is the best available data possessed by Badische Corporation on the subject. This data may not be relevant to any end use product which combines other substances with this product. It is the User's responsibility to determine the accuracy and completeness of this information in the context of its own business purposes. BADISCHE CORPORATION MAKES NO REPRESENTATIONS OR WARRANTIES AS TO THE ACCURACY OR COMPLETENESS OF THIS INFORMATION, AND BADISCHE CORPORATION ASSUMES NO RESPONSIBILITY WHATSOEVER IN CONNECTION WITH THE USE OF SUCH INFORMATION BY USER.

BASF



# MATERIAL SAFETY DATA SHEET

PAGE 1

EXXON CHEMICAL AMERICAS • P.O. BOX 3272, HOUSTON, TEXAS 77001  
A Division of EXXON CHEMICAL COMPANY, A Division of EXXON CORPORATION

06/13/88

NO. 92160000

## SECTION I PRODUCT IDENTIFICATION & EMERGENCY INFORMATION

**PRODUCT NAME****Methyl Isobutyl Ketone****CHEMICAL NAME**

4-Methyl-2-Pentanone

CAS 108-10-1

**CHEMICAL FAMILY**

Ketone

**PRODUCT APPEARANCE**

Clear colorless liquid with a characteristic pungent odor.

**EMERGENCY TELEPHONE NUMBERS:** EXXON CHEMICAL AMERICAS 713-870-6000  
CHEMTREC 800-424-9300

## SECTION II HAZARDOUS INGREDIENT INFORMATION

This product is hazardous as defined in CFR1910.1200.


OSHA HAZARD

Flammable

PEL: TLV

Eye irritant

For additional information see Section III.



## SECTION III HEALTH INFORMATION AND PROTECTION

### NATURE OF HAZARD

**EYE CONTACT:**

Irritating, and may injure eye tissue if not removed promptly.

**SKIN CONTACT:**

Frequent or prolonged contact may irritate and cause dermatitis.

Low order of toxicity.

**INHALATION:**

High vapor concentrations are irritating to the eyes and the respiratory tract, may cause headaches and dizziness, are anesthetic and may have other central nervous system effects.

Low order of toxicity.

**INGESTION:**

Low order of toxicity.

Small amounts of the liquid aspirated into the respiratory system during ingestion, or from vomiting, may cause bronchiopneumonia or pulmonary edema.

### FIRST AID

**EYE CONTACT:**

Immediately flush eyes with large amounts of water for at least 15 minutes. Get prompt medical attention.

**SKIN CONTACT:**

Immediately flush with large amounts of water; use soap if available.

Remove contaminated clothing, including shoes, after flushing has begun.

**INHALATION:**

Using proper respiratory protection, immediately remove the affected victim from exposure. Administer artificial respiration if breathing is stopped. Keep at rest. Call for prompt medical attention.

## EMERGENCY AND FIRST AID PROCEDURES

**EYE CONTACT:** Immediately flush eyes for 15 minutes with water. Include under eyelids. Obtain medical attention. Contact lenses should not be worn when working with this chemical.

**SKIN CONTACT:**

Remove contaminated clothing. Flush contaminated skin with soap or mild detergent and water. If irritation persists, obtain medical attention.

**INHALATION:**

Remove to fresh air. Restore breathing if necessary and immediately obtain medical attention. Keep the affected person warm and at rest.

**INGESTION:** Obtain medical attention immediately. If exposed person is conscious, immediately give large quantities of water and induce vomiting by touching back of throat. Do not attempt to make unconscious person vomit.

## PHYSICAL DATA

<b>BOILING POINT:</b> 156.7°C	<b>SPECIFIC GRAVITY (H<sub>2</sub>O=1):</b> 0.95 @ 20/20°C
<b>VAPOR PRESSURE:</b> 2 mm Hg @ 20°C	<b>VAPOR DENSITY (AIR=1):</b> 3.4
<b>FREEZING POINT:</b> -45°C	<b>MOLECULAR WT.:</b> 98.16
<b>SOLUBILITY IN WATER:</b> 9 g/100g @ 20°C	<b>APPEARANCE AND ODOR:</b> Water - white to pale yellow oily liquid with an odor of peppermint and acetone.

Odor threshold is 0.24 ppm.

## FIRE AND EXPLOSION HAZARD DATA

<b>FLASH POINT (METHOD USED):</b> 44°C (T.C.C.)	<b>AUTOIGNITION TEMPERATURE:</b> 420°C	<b>FLAMMABLE LIMITS (% BY VOLUME)</b> LEL 1.1 UEL 8.1
<b>EXTINGUISHING MEDIA:</b>  Water mist, CO <sub>2</sub> , dry chemical, foam		
<b>UNUSUAL FIRE AND EXPLOSION HAZARDS:</b>  Use water <u>spray</u> to cool containers, to dilute leaking materials and to diffuse vapors. Vapors are heavier than air, and may travel to a source of ignition causing flashback. Firefighters should use self-contained breathing apparatus.		

## REACTIVITY DATA

<b>STABILITY</b> Unstable		<b>CONDITIONS TO AVOID:</b>  Excessive heat; Ignition sources.
<b>Stable</b>	X	
<b>INCOMPATIBILITY (Materials to avoid):</b> Strong oxidizing agents (such as nitric acid), reducing agents, nitrates, aldehydes, nitric acid + hydrogen peroxide, mercaptans. Cyclohexanone can attack many plastics, resins and rubbers.		
<b>HAZARDOUS DECOMPOSITION PRODUCTS:</b> Incomplete thermal oxidation can produce carbon monoxide and carbon dioxide.		
<b>HAZARDOUS POLYMERIZATION</b> May occur		<b>CONDITIONS TO AVOID:</b>  Stable under normal storage conditions.
<b>Will not occur</b>	X	



**FXON**

# MATERIAL SAFETY DATA SHEET

PAGE 4

CH<sub>2</sub> ALS 06/13/88 Methyl Isobutyl Ketone

NO. 92160000

042-052

## SECTION VIII TYPICAL PHYSICAL & CHEMICAL PROPERTIES

SP. GRAVITY 0.8 at 68/68	REF. TEMP., °F	VAPOR PRESSURE, mmHg at °F 0.75 at 50
SOLUBILITY IN WATER, WT. % at °F 2 68	VISCOSITY OF LIQUID, cST at °F 0.7 at 68	
SP. GRAVITY OF VAPOR, at 1 ATM AIR=1 3.45	FREEZING MELTING POINT/RANGE, °F -119.2	
E VAPORATION RATE, n-BU ACETATE=1 1.7	BOILING POINT/RANGE, °F 236.84 to 242.96	

## SECTION IX REACTIVITY DATA

STABILITY? Stable	HAZARDOUS POLYMERIZATION OCCUR? Will not occur
CONDITIONS TO AVOID INSTABILITY Not Applicable	CONDITIONS TO AVOID HAZARDOUS POLYMERIZATION Not Applicable

### MATERIALS AND CONDITIONS TO AVOID INCOMPATIBILITY

ustic, amines, alkanolamines, aldehydes, ammonia, strong oxidizing agents, and chlorinated compounds.

### HAZARDOUS DECOMPOSITION PRODUCTS

None

## SECTION X TRANSPORT AND STORAGE

DOT CLASSIFICATION Flammable liquid	UN NUMBER U.S. DOT Identification Number: UN 1993
ELECTROSTATIC ACCUMULATION HAZARD Yes, use proper grounding procedure	
STORAGE TEMPERATURE, °F Ambient	LOADING/UNLOADING TEMPERATURE, °F Ambient
ORAGE/TRANSPORT PRESSURE, mmHg Atmospheric	VISCOSITY AT LOADING/UNLOADING TEMPERATURE, cST 0.7

## SECTION XI OTHER INFORMATION

REFERENCE NUMBER HDHA-C-00027	DATE PREPARED JUNE 16, 1988	SUPERCEDES ISSUE DATE JUNE 9, 1988
----------------------------------	--------------------------------	---------------------------------------

FOR ADDITIONAL PRODUCT INFORMATION CONTACT YOUR TECHNICAL SALES REPRESENTATIVE

06/14/88

NO. 92050000

## SECTION I PRODUCT IDENTIFICATION & EMERGENCY INFORMATION

**PRODUCT NAME**

Methyl Ethyl Ketone

**CHEMICAL NAME**

Methyl ethyl ketone

CAS 78-93-3

**CHEMICAL FAMILY**

Ketone

**PRODUCT APPEARANCE**

Clear colorless liquid.

EMERGENCY TELEPHONE NUMBERS: EXXON CHEMICAL AMERICAS  
 CHEMTREC

713-870-6000  
 800-424-9300

## SECTION II HAZARDOUS INGREDIENT INFORMATION

This product is hazardous as defined in CFR1910.1200.

**OSHA HAZARD**

Flammable

PEL; TLV

Eye irritant



For additional information see Section III.

AUG 1 1 1988

## SECTION III HEALTH INFORMATION AND PROTECTION

### NATURE OF HAZARD

**EYE CONTACT:**

Severely irritating. If not removed promptly, will injure eye tissue, which may result in permanent damage.

**SKIN CONTACT:**

Frequent or prolonged contact may irritate and cause dermatitis. Low order of toxicity.

**INHALATION:**

High vapor concentrations are irritating to the eyes and the respiratory tract, may cause headaches and dizziness, are anesthetic and may have other central nervous system effects. Low order of toxicity.

**INGESTION:**

Low order of toxicity. Small amounts of the liquid aspirated into the respiratory system during ingestion, or from vomiting, may cause bronchiopneumonia or pulmonary edema.

### FIRST AID

**EYE CONTACT:**

Immediately flush eyes with large amounts of water for at least 15 minutes. Get prompt medical attention.

**SKIN CONTACT:**

Immediately flush with large amounts of water; use soap if available. Remove contaminated clothing, including shoes, after flushing has begun.

**INHALATION:**

Using proper respiratory protection, immediately remove the affected victim from exposure. Administer artificial respiration if breathing is stopped. Keep at rest. Call for prompt medical attention.

## MATERIAL SAFETY DATA SHEET

**UNOCAL**UNOCAL CHEMICALS DIVISION  
PETROCHEMICALS GROUPProduct Name: ACETONE  
Product Code No: 15450

42-050

Page 1 of 5  
Issue Date: 5/23/87**MANUFACTURER:**UNOCAL CHEMICALS DIVISION  
UNION OIL COMPANY OF CALIFORNIA  
1345 N. MEACHAM  
SCHAUMBURG, ILLINOIS 60196CONTACT FOR FURTHER INFORMATION:  
MSDS COORDINATOR (312) 490-2500**Transportation Emergencies:**Call CHEMTREC  
(800) 424-9300 Cont. U.S.  
(202) 483-7616 (Collect)  
from Alaska & Hawaii**Health Emergencies:**  
CALL LOS ANGELES POISON  
INFORMATION CENTER (24 hrs.)  
(213) 664-2121**PRODUCT IDENTIFICATION****PRODUCT NAME:** ACETONE**SYNONYMS:**AMSCO SOLV 5450  
BETA-KETOPROPANE  
DIMETHYL KETONE  
DIMETHYLFORMALDEHYDE  
DIMETHYLKETAL  
KETONE PROPANE  
METHYL KETONE  
PROPANONECRODA INKS CORP.  
Miles, Illinois  
**RECEIVED****GENERIC NAME:** VOLATILE SOLVENT**ICAL FAMILY:** OXYGENATED HYDROCARBON**DOT PROPER  
SHIPPING NAME:** ACETONE**DOT NUMBER:** UN1090**DOT HAZARD  
CLASSIFICATION:** FLAMMABLE LIQUID**CAS NUMBER:** 67-64-1

SEP 6 1988

**SECTION I - HAZARDOUS INGREDIENTS/EXPOSURE LIMITS CAS NO. TLV UNITS AGENCY TYPE**

ACETONE	100%	67-64-1	750.0000 PPM	ACGIH	TWA
			1000.0000 PPM	ACGIH	STEL
			1000.0000 PPM	OSHA	TWA
			3000.0000 PPM	CAL OSHA	CELL

**SECTION II - EMERGENCY AND FIRST AID PROCEDURES****\*\*\*EMERGENCY\*\*\***Have physician call LOS ANGELES POISON  
INFORMATION CENTER (24 hrs.) (213) 664-2121**EYE CONTACT:**IMMEDIATELY MOVE VICTIM AWAY FROM EXPOSURE TO VAPORS AND INTO FRESH AIR. IF  
IRRITATION OR REDNESS DEVELOPS, FLUSH EYES WITH CLEAN WATER AND SEEK IMMEDIATE  
MEDICAL ATTENTION. FOR DIRECT CONTACT, FLUSH THE AFFECTED EYE(S) WITH CLEAN WATER FOR  
AT LEAST 20 MINUTES. SEEK IMMEDIATE MEDICAL ATTENTION.

112-022



CHEMCENTRAL/Atlanta P.O. Box 47280 Atlanta, Georgia 30362  
Alchemy Place Doraville, Georgia 30360 (404) 448-7123

# MATERIAL SAFETY DATA SHEET

APR 07 1986

MATERIAL Solvent Xylene	
MSDS NO. 313	DATE 3/85

## I. MATERIAL IDENTIFICATION

MATERIAL / TRADE NAME Solvent Xylene

SYNONYMS Xylene 112-022

CHEMICAL FAMILY / FORMULA Aromatic Hydrocarbon/C<sub>8</sub>H<sub>10</sub>

CAS NO. Mixture

24 HOUR EMERGENCY TELEPHONE  
TENNECO 504/279-9481  
CHEMTREC 800 424-9300

## HAZARD RATING\*

☐ 2 HEALTH  
☐ 3 FIRE  
☐ 0 REACTIVITY

0 LEAST 3 HIGH  
1 SLIGHT 4 EXTREME  
2 MODERATE

## II. INGREDIENTS

### COMPOSITION

Meta Xylene (CAS #108-38-3)  
Ethyl Benzene (CAS #100-41-4)

Ortho Xylene (CAS #95-47-6)  
Para Xylene (CAS #106-42-3)

%

>65

>25

3

2

### TOXICITY DATA

Human, Inhalation  
TCLo 200 ppm  
(Irritation)

Rat, Oral  
LD50 4.3 g/kg.  
Rat Inhalation  
LC50 6700 ppm/4 hr. (29 mg/L)

## III. PHYSICAL DATA

BOILING POINT, 760mmHg - 137.7°F (58.7°C) IBP

SOLUBILITY IN H<sub>2</sub>O, % BY WEIGHT - Insoluble

SPECIFIC GRAVITY, H<sub>2</sub>O=1 - 0.87

EVAPORATION RATE, BUTYL ACETATE=1 - 0.5 Approximately

VAPOR PRESSURE, mmHg - 8.5 @ 25°C

Molecular Weight - 106.17

VAPOR DENSITY, AIR=1 - 3.0

VOLATILES, % BY VOLUME - 100

APPEARANCE AND ODOR: Clear, colorless liquid with aromatic hydrocarbon odor

## IV FIRE AND EXPLOSION DATA

### FLASH POINT AND TEST METHOD

81°F (27.2°C) TCC

### AUTO IGNITION TEMPERATURE

800°F (426.7°C)

### FLAMMABILITY LIMITS IN AIR, % BY VOLUME

LOWER 1.0 UPPER 7.0

### EXTINGUISHING MEDIA

Foam, dry chemical, Halon, CO<sub>2</sub>. Water may not be effective. Water spray (fog) may be used to cool containers. Water stream may splash and spread flaming liquid.

### SPECIAL FIRE FIGHTING PROCEDURES

Class IC flammable liquid. Vapors can readily form explosive mixtures with air. Heavier than air vapors can flow along surfaces to distant ignition sources and flash back. Firefighters should use self-contained breathing equipment in an enclosed area.

### UNUSUAL FIRE AND EXPLOSION HAZARDS

Keep away from heat, sources of ignition, oxidizers.

MATERIAL SAFETY  
DATA SHEET

## Ashland Chemical Company

DIVISION OF ASHLAND OIL, INC.

P. O. BOX 2219, COLUMBUS, OHIO 43216 • (614) 889-3333

24-HOUR EMERGENCY TELEPHONE (606) 324-1133



## KEROSENE

Page: 1

THIS MSDS COMPLIES WITH 29 CFR 1910.1200 (THE HAZARD COMMUNICATION STANDARD)

Product Name: KEROSENE  
S NUMBER: 8008-20-6

05 88 092 3140118-060

Data Sheet No: 0000584-004  
Prepared: 12/09/86  
Supersedes: 11/04/85CRODA INKS CORP.  
ATTN: DEAN ROEING  
7777 NORTH MERRIMAC AVENUE  
NILES, IL 60648-3490PRODUCT:  
INVOICE: REGST  
INVOICE DATE: 09/23/88  
TO:

## SECTION I. PRODUCT IDENTIFICATION

Chemical or Generic ID: ALIPHATIC HYDROCARBON

Hazard Classification: COMBUSTIBLE (173.115)

## SECTION II. COMPONENTS

The composition of this product is being withheld as a trade secret.

If present, IARC, NTP and OSHA CARCINOGENS ARE IDENTIFIED IN THIS SECTION  
SEE DEFINITION PAGE FOR CLARIFICATION

Gradient	% (by WT)	PEL	TLV	Note
KEROSENE	100			(1)

## Notes:

1) PEL/TLV NOT ESTABLISHED FOR THIS MATERIAL

NIOSH RECOMMENDS A LIMIT OF 100MG/M3 FOR 10 HR.

## SECTION III. PHYSICAL DATA

Boiling Point	for PRODUCT	320.00 - 365.00 Deg F ( 160.00 - 185.00 Deg C )
Vapor Pressure	for PRODUCT	5.00 mm Hg ( 77.00 Deg F 25.00 Deg C )
Relative Vapor Density	AIR = 1	4.5
Specific Gravity		.825 ( 60.00 Deg F 15.55 Deg C )
Percent Volatiles		45-50%
Evaporation Rate	(N-BUTYL ACETATE = 1)	.04

## SECTION IV. FIRE AND EXPLOSION INFORMATION

Flash Point(TCC ) 120.0 - 125.0 Deg F ( 48.9 - 51.7 Deg C )

Explosive Limit (PRODUCT) LOWER - .7%

Extinguishing Media: REGULAR FOAM OR CARBON DIOXIDE OR DRY CHEMICAL

Hazardous Decomposition Products: MAY FORM TOXIC MATERIALS: CARBON DIOXIDE AND CARBON MONOXIDE, VARIOUS HYDROCARBONS, ETC.

Firefighting Procedures: WEAR SELF-CONTAINED BREATHING APPARATUS WITH A FULL FACEPIECE OPERATED IN THE POSITIVE PRESSURE DEMAND MODE WHEN FIGHTING FIRES.

Special Fire &amp; Explosion Hazards: VAPORS ARE HEAVIER THAN AIR AND MAY TRAVEL ALONG THE GROUND OR BE MOVED BY WIND. VENTILATION AND IGNITED BY HEAT, PILOT LIGHTS, OTHER FLAMES AND IGNITION SOURCES AT LOCATIONS DISTANT FROM MATERIAL HANDLING POINT.

NEVER USE WELDING OR CUTTING TORCH ON OR NEAR DRUM (EVEN EMPTY) BECAUSE PRODUCT (EVEN JUST RESIDUE) CAN IGNITE EXPLOSIVELY.

ALL FIVE GALLON PAILS AND LARGER METAL CONTAINERS INCLUDING TANK CARS AND TANK TRUCKS SHOULD BE GROUNDED AND/OR BONDED WHEN MATERIAL IS TRANSFERRED.

Hazard Codes: HEALTH- 2 FLAMMABILITY- 2 REACTIVITY- 0

## SECTION V. HEALTH HAZARD DATA

Routes of Exposure Level: SEE SECTION II

Effects of Acute Overexposure: FOR PRODUCT

Exposure can cause severe irritation, redness, tearing, blurred vision.  
 Prolonged or repeated contact can cause moderate irritation, defatting, dermatitis.  
 Breathing - excessive inhalation of vapors can cause nasal and respiratory irritation, central nervous system effects including dizziness, weakness, fatigue, nausea, headache and possible unconsciousness, and even death.

42-007

013 \*\*\*

M A T E R I A L   S A F E T Y   D A T A   S H E E T

PAGE 1

REV: 1/25/86

OF MTECH INDUSTRIES, INC.  
655 DES PERES ROAD  
P.O. BOX 31000  
ST LOUIS, MO 63131  
PHONE: (314) 966-9900

PROD 0047  
B/L 444207

HEALTH = \_ REACTIVITY = \_  
FIRE = \_ EQUIPMENT = \_

HAZARD RATINGS : 0 = LEAST 1 = SLIGHT  
2 = MODERATE 3 = HIGH  
4 = EXTREME

SECTION I ===== PRODUCT DESCRIPTION =====

PRODUCT NAME: NO. 1 FUEL OIL

SYNONYMS: KEROSENE

CHEMICAL FAMILY: ALIPHATIC HYDROCARBON

SECTION II ===== PRODUCT COMPOSITION =====

INGREDIENT	VOL %	CAS #	TLV
HYDROCARBON	100	64742-96-7	NE

SECTION III ===== PHYSICAL PROPERTIES =====

BOILING RANGE: 347-345 F

SPECIFIC GRAVITY (WATER=1): .81

VAPOR PRESSURE AT 20C (MM OF HG): @ 100 F LESS THAN 1

VAPOR DENSITY (AIR=1): 4.5

SOLUBILITY IN WATER: NEGLIGIBLE

EVAPORATION RATE: 0.10

PERCENT VOLATILES: 100

APPEARANCE AND ODOR: CLEAR, LIGHT YELLOW ODOR: MILD, RESIDUAL

OTHER:

SECTION IV ===== FIRE AND EXPLOSION DATA =====

FLASH FLAMMABILITY LIMITS (% IN AIR): 0.7 - 5

FLASH POINT (AND METHOD): T.C.C. 138 F

FLAMMABILITY CLASSIFICATION: CLASS II

42-003

4. -003 H  
42-080**TRIANGLE REFINERIES, Inc.**

SPECIALTY PRODUCTS DIVISION

3020 KNIGHT STREET • SUITE 130 • SHREVEPORT, LOUISIANA 71105  
TELEPHONE (800) 548-3417 (318) 861-0954

A SUBSIDIARY OF KERR-MCGEE REFINING CORPORATION

*Mineral spirits also present  
in products*~~42-080-11~~**MATERIAL SAFETY DATA SHEET**

MSDS NUMBER

CV-1321

EMERGENCY TELEPHONE

COMPANY

405/270-2526

CHEMTREC

800/424-9300

**I. PRODUCT IDENTIFICATION**

PRODUCT				CHEMICAL NAME			
KERMAC 180-210 Naphtha				Light Aliphatic Solvent Naphtha			
CHEMICAL FAMILY				FORMULA		CAS NUMBER	
Petroleum Hydrocarbon Naphtha				C <sub>6</sub> -C <sub>10</sub>		64742-89-8	
NATIONAL FIRE PROTECTION ASSOCIATION HAZARD RATING CODES				HEALTH CODE		FIRE CODE	
Least - 0      Slight - 1				1		3	
Moderate - 2      High - 3      Extreme - 4						0	

**II. HAZARDOUS COMPONENTS**

INGREDIENT	%	OSHA LIMIT	TLV
Naphtha	100	Petroleum distillates (naphtha) TWA-500 ppm	Similar to VM&P Naphtha TWA-300 ppm STEL-400 ppm
Benzene	< 0.1	TWA-10 ppm Ceiling-25 ppm	TWA-10 ppm STEL-25 ppm
Toluene	< 0.1	TWA-200 ppm Ceiling-300 ppm	TWA-100 ppm STEL-150 ppm


**III. PHYSICAL AND CHEMICAL PROPERTIES**

BOILING POINT	VAPOR PRESSURE	EVAPORATION (ETHYL ETHER = 1)
180-210°F	196 mmHg @ 100°F	Estimated 7 Times Slower
PERCENT VOLATILE BY VOLUME (%)	MOLECULAR WEIGHT	APPEARANCE
100	99	Water White Liquid
ODOR AND THRESHOLD	MELTING POINT	VAPOR DENSITY (AIR = 1)
Petroleum Naphtha-Approx. 10 ppm	Not Available	3.3
SPECIFIC GRAVITY (H <sub>2</sub> O = 1)	VISCOSITY	SOLUBILITY (G/100G WATER AT 20 °C)
0.69	<32 SUS @ 100°F	Negligible

## APPENDIX C

### REPRESENTATIVE MANIFESTS FOR OFF-SITE DISPOSAL





STATE OF WISCONSIN  
Chapter 144, Wis. Stats.  
Form 4400-86

Rev. 7-87

State of Wisconsin  
Department of Natural Resources  
Bureau of Solid Waste Mgt.  
Box 8094  
Madison, Wisconsin 53708

FOR DNR USE ONLY

1. See instructions on reverse side of copy 0.  
2. See instructions on reverse side of copy 0.  
3. See instructions on reverse side of copy 0.  
4. See instructions on reverse side of copy 0.  
5. See instructions on reverse side of copy 0.  
6. See instructions on reverse side of copy 0.  
7. See instructions on reverse side of copy 0.  
8. See instructions on reverse side of copy 0.  
9. See instructions on reverse side of copy 0.  
10. See instructions on reverse side of copy 0.  
11. See instructions on reverse side of copy 0.  
12. See instructions on reverse side of copy 0.  
13. See instructions on reverse side of copy 0.  
14. See instructions on reverse side of copy 0.  
15. See instructions on reverse side of copy 0.  
16. See instructions on reverse side of copy 0.  
17. See instructions on reverse side of copy 0.  
18. See instructions on reverse side of copy 0.  
19. See instructions on reverse side of copy 0.  
20. See instructions on reverse side of copy 0.  
21. See instructions on reverse side of copy 0.  
22. See instructions on reverse side of copy 0.  
23. See instructions on reverse side of copy 0.  
24. See instructions on reverse side of copy 0.  
25. See instructions on reverse side of copy 0.  
26. See instructions on reverse side of copy 0.  
27. See instructions on reverse side of copy 0.  
28. See instructions on reverse side of copy 0.  
29. See instructions on reverse side of copy 0.  
30. See instructions on reverse side of copy 0.  
31. See instructions on reverse side of copy 0.  
32. See instructions on reverse side of copy 0.  
33. See instructions on reverse side of copy 0.  
34. See instructions on reverse side of copy 0.  
35. See instructions on reverse side of copy 0.  
36. See instructions on reverse side of copy 0.  
37. See instructions on reverse side of copy 0.  
38. See instructions on reverse side of copy 0.  
39. See instructions on reverse side of copy 0.  
40. See instructions on reverse side of copy 0.  
41. See instructions on reverse side of copy 0.  
42. See instructions on reverse side of copy 0.  
43. See instructions on reverse side of copy 0.  
44. See instructions on reverse side of copy 0.  
45. See instructions on reverse side of copy 0.  
46. See instructions on reverse side of copy 0.  
47. See instructions on reverse side of copy 0.  
48. See instructions on reverse side of copy 0.  
49. See instructions on reverse side of copy 0.  
50. See instructions on reverse side of copy 0.  
51. See instructions on reverse side of copy 0.  
52. See instructions on reverse side of copy 0.  
53. See instructions on reverse side of copy 0.  
54. See instructions on reverse side of copy 0.  
55. See instructions on reverse side of copy 0.  
56. See instructions on reverse side of copy 0.  
57. See instructions on reverse side of copy 0.  
58. See instructions on reverse side of copy 0.  
59. See instructions on reverse side of copy 0.  
60. See instructions on reverse side of copy 0.  
61. See instructions on reverse side of copy 0.  
62. See instructions on reverse side of copy 0.  
63. See instructions on reverse side of copy 0.  
64. See instructions on reverse side of copy 0.  
65. See instructions on reverse side of copy 0.  
66. See instructions on reverse side of copy 0.  
67. See instructions on reverse side of copy 0.  
68. See instructions on reverse side of copy 0.  
69. See instructions on reverse side of copy 0.  
70. See instructions on reverse side of copy 0.  
71. See instructions on reverse side of copy 0.  
72. See instructions on reverse side of copy 0.  
73. See instructions on reverse side of copy 0.  
74. See instructions on reverse side of copy 0.  
75. See instructions on reverse side of copy 0.  
76. See instructions on reverse side of copy 0.  
77. See instructions on reverse side of copy 0.  
78. See instructions on reverse side of copy 0.  
79. See instructions on reverse side of copy 0.  
80. See instructions on reverse side of copy 0.  
81. See instructions on reverse side of copy 0.  
82. See instructions on reverse side of copy 0.  
83. See instructions on reverse side of copy 0.  
84. See instructions on reverse side of copy 0.  
85. See instructions on reverse side of copy 0.  
86. See instructions on reverse side of copy 0.  
87. See instructions on reverse side of copy 0.  
88. See instructions on reverse side of copy 0.  
89. See instructions on reverse side of copy 0.  
90. See instructions on reverse side of copy 0.  
91. See instructions on reverse side of copy 0.  
92. See instructions on reverse side of copy 0.  
93. See instructions on reverse side of copy 0.  
94. See instructions on reverse side of copy 0.  
95. See instructions on reverse side of copy 0.  
96. See instructions on reverse side of copy 0.  
97. See instructions on reverse side of copy 0.  
98. See instructions on reverse side of copy 0.  
99. See instructions on reverse side of copy 0.  
100. See instructions on reverse side of copy 0.

Form Approved. OMB No. 2050-0039. Expires 9-30-88


<b>UNIFORM HAZARDOUS WASTE MANIFEST</b>		1. Generator's US EPA ID No. ILD 002293124		Manifest Document No. 01010119		2. Page 1 of		Information in the shaded areas is not required by Federal law.					
3. Generator's Name and Mailing Address Croda Inks Corp. 7777 N. Merrimac Avenue Niles, IL 60648						A. State Manifest Document Number WI G 72059							
4. Generator's Phone (312) 967-7575						B. State Generator's ID							
5. Transporter 1 Company Name Avganic Industries, Inc.			6. US EPA ID Number WID 000808824			C. State Transporter's ID							
7. Transporter 2 Company Name			8. US EPA ID Number			D. Transporter's Phone							
9. Designated Facility Name and Site Address Avganic Industries, Inc. 114 S. Main St. Cottage Grove, WI 53529			10. US EPA ID Number WID 000808824			E. State Transporter's ID							
						F. Transporter's Phone							
						G. State Facility's ID							
						H. Facility's Phone							
1. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)						12. Containers No.		13. Total Quantity		14. Unit We/Vol		15. Waste No.	
a. Hazardous Waste Liquid NOS, RQ ORM-E NA 9189						12. Containers No. 120		13. Total Quantity 1100		14. Unit We/Vol G		15. Waste No. K10 816	
Additional Descriptions for Materials Listed Above						K. Handling Codes for Wastes Listed Above							
3. Special Handling Instructions and Additional Information 10589-R-20841 P.O.# 9408													
3. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national governmental regulations and according to the requirements of the Wisconsin Department of Natural Resources. If I am a large quantity generator, I also certify that I have a program in place to reduce the volume and toxicity of waste generated to the degree I have determined to be economically practicable and I have selected the practicable method of treatment, storage, or disposal currently available to me which minimizes the present and future threat to human health and the environment;  OR, if I am a small quantity generator, I have made a good faith effort to minimize my waste generation and select the best waste management method that is available to me and that I can afford.													
intended/Typed Name & Position Title EDWIN E. BROWN - GENERAL MANAGER						Signature <i>Edwin E Brown</i>						Date Month Day Year	
17. TRANSPORTER 1 Acknowledgement of Receipt of Materials												Date	
intended/Typed Name & Position Title						Signature						Month Day Year	
18. TRANSPORTER 2 Acknowledgement of Receipt of Materials												Date	
intended/Typed Name & Position Title						Signature						Month Day Year	
19. Discrepancy Indication Space													
FACILITY OWNER OR OPERATOR: Certification of receipt of hazardous materials covered by this manifest except as noted in Item 19.													
intended/Typed Name & Position Title						Signature						Date Month Day Year	

PA Form 8700-22 (Rev. 9-86) Previous editions are obsolete.

Copy Distribution: 1 - Wis. DNR 4 - Facility  
2 - Generator 5 - Generator  
3 - Wis. DNR 6 - Transporter  
Copies 1 & 3 mail to Wis. DNR at above address.

Emergency 24 Hour Assistance Telephone Number  
in Wisconsin (800) 266-3232  
Outside Wisconsin (800) 424-8802

COPY 1 -



STATE OF WISCONSIN  
Chapter 144, Wis. Stats.  
Form 4400-66

Rev. 7-87

RECEIVED  
JUN - 8 1989

State of Wisconsin  
Department of Natural Resources  
Bureau of Solid Waste Mgt.  
Box 8094  
Madison, Wisconsin 53708

FOR DNR USE ONLY

Please print or type. Form designed for use on elite (12-pitch) typewriter.

Form Approved. OMB No. 2050-0039. Expires 9-30-88

<b>UNIFORM HAZARDOUS WASTE MANIFEST</b>		1. Generator's US EPA ID No. ILD 002293124		Manifest Document No. 000016		2. Page 1 of 1		Information in the shaded areas is not required by Federal law.			
3. Generator's Name and Mailing Address CRODA INKS CORP. 7777 N. MERRIMAC AVE. NILES, IL 60648				A. State Manifest Document Number WI G 72057							
4. Generator's Phone (312) 967-7575				B. State Generator's ID N/A							
5. Transporter 1 Company Name AVGANIC				6. US EPA ID Number WID 000808824		C. State Transporter's ID 2266					
7. Transporter 2 Company Name N/A				8. US EPA ID Number N/A		D. Transporter's Phone 608-257-1414					
9. Designated Facility Name and Site Address Avganic Cottage Grove, WI 53527				10. US EPA ID Number WID 000808824		E. State Transporter's ID					
						F. Transporter's Phone					
						G. State Facility's ID					
						H. Facility's Phone 608-257-1414					
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)				12. Containers No. Type		13. Total Quantity		14. Unit Wt/Vol		15. Waste No.	
a. WASTE FLAMMABLE LIQUID, N.O.S., R.Q.				36 DM		2760		G		D001	
b.											
c.											
d.											
Additional Descriptions for Materials Listed Above AUPH # 10580-R-20153						K. Handling Codes for Wastes Listed Above					
15. Special Handling Instructions and Additional Information D001, K086											
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national governmental regulations and according to the requirements of the Wisconsin Department of Natural Resources. If I am a large quantity generator, I also certify that I have a program in place to reduce the volume and toxicity of waste generated to the degree I have determined to be economically practicable and I have selected the practicable method of treatment, storage, or disposal currently available to me which minimizes the present and future threat to human health and the environment;  OR, if I am a small quantity generator, I have made a good faith effort to minimize my waste generation and select the best waste management method that is available to me and that I can afford.											
Printed/Typed Name & Position Title DEAN ROEING, GOVERNMENT AFFAIRS MANAGER						Signature [Signature]			Date 12/1/87		
17. TRANSPORTER 1 Acknowledgement of Receipt of Materials									Date		
Printed/Typed Name & Position Title MIKE WADDER DRIVER						Signature [Signature]			Month Day Year 25 JUL 87		
18. TRANSPORTER 2 Acknowledgement of Receipt of Materials									Date		
Printed/Typed Name & Position Title						Signature			Month Day Year		
19. Discrepancy Indication Space											
FACILITY OWNER OR OPERATOR: Certification of receipt of hazardous materials covered by this manifest except as noted in Item 19.											
Printed/Typed Name & Position Title MICHAEL SPELIGER DM						Signature [Signature]			Date 12/1/87		

PLEASE TYPE

(Form designed for use on elite (12-pitch) typewriter.)

EPA Form 8700-22 (Rev. 9-86)

Form Approved, OMB No. 2050-0039, Expires 9-30-91

<b>UNIFORM HAZARDOUS WASTE MANIFEST</b>		1. Generator's US EPA ID No.		Manifest Document No.	2. Page 1 of 1	Information in the shaded areas is not required by Federal law, but is required by Illinois law.	
Generator's Name and Mailing Address		Location If Different:		A. Illinois Manifest Document Number <b>IL 4115266</b>		MANIFEST FEE PAID	
Croda Ink Corporation 7777 North Merrimac Avenue, Niles, Illinois 60648				B. Illinois Generator's ID <b>0312015011</b>			
4. Generator's Phone (312) 967-7578		6. US EPA ID Number		C. Illinois Transporter's ID <b>0670</b>		D. (312) 720-0700 Transporter's Phone	
5. Transporter 1 Company Name Mr. Frank Inc.		8. US EPA ID Number		E. Illinois Transporter's ID <b>0070</b>		F. Transporter's Phone	
7. Transporter 2 Company Name		10. US EPA ID Number		G. Illinois Facility's ID <b>0316000051</b>		H. Facility's Phone <b>(312) 646-6202</b>	
9. Designated Facility Name and Site Address Chem-Clear 800 S. Stony Island Av. Chicago IL 60617				11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)		12. Containers No.	13. Total Quantity
						14. Unit Wt/Vol	1. Waste No.
a. <del>Adhesive Wast</del> Not Hazardous By DOT		31 2-3		1-2-5		1	EPA HW Number XX Authorization Number 0316000051
b. Croda Seal Not Hazardous By DOT		15		1245		1	EPA HW Number XX Authorization Number 0316000051
c.		40					EPA HW Number XX Authorization Number 0316000051
d.							EPA HW Number XX Authorization Number 0316000051
Additional Descriptions for Materials Listed Above				K. Handling Codes for Wastes Listed Above In Item #14 1 = Gallons 2 = Cubic Yards			
15. Special Handling Instructions and Additional Information							
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national government regulations. If I am a large quantity generator, I certify that I have a program in place to reduce the volume and toxicity of waste generated to the degree I have determined to be economically practicable and that I have selected the practicable method of treatment, storage, or disposal currently available to me which minimizes the present and future threat to human health and the environment; OR, if I am a small quantity generator, I have made a good faith effort to minimize my waste generation and select the best waste management method that is available to me and that I can afford.							
Printed/Typed Name Dean Roelue				Signature		Date 5/5/89	
17. Transporter 1 Acknowledgement of Receipt of Materials				Signature		Date	
Printed/Typed Name				Signature		Month/Day/Year	
18. Transporter 2 Acknowledgement of Receipt of Materials				Signature		Date	
Printed/Typed Name				Signature		Month/Day/Year	
19. Discrepancy Indication Space							
J. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in item 19.						Date	
Printed/Typed Name				Signature		Month/Day/Year	

This Agency is authorized to require, pursuant to Illinois Revised Statutes, Chapter 119, Section 21, that this information be submitted to the Agency. Failure to provide the information may result in a civil penalty against the owner or operator of not to exceed \$25,000 per day of violation. Falsification of this information may result in a fine up to \$50,000 per day of violation and imprisonment up to 5 years. This form has been approved by the Forms Management Center.

COPY 6. GENERATOR COPY

Office of Emergency Response at 217/782-9761 and the National Response Center at 800/424-8802 or 202/426-2015.



COMMONWEALTH OF MASSACHUSETTS  
DEPARTMENT OF ENVIRONMENTAL QUALITY ENGINEERING  
DIVISION OF SOLID AND HAZARDOUS WASTE  
One Winter Street  
Boston, Massachusetts 02108

Print or type. (Form designed for use on elite (12-pitch) typewriter.)

<b>UNIFORM HAZARDOUS WASTE MANIFEST</b>		1. Generator US EPA ID No. <b>ILD0002293124000115</b>		Manifest Document No. <b>000115</b>		2. Page 1 of 1		Information in the shaded areas is not required by Federal law.	
3. Generator's Name and Mailing Address <b>CRODA INKS CORP. 7777 N. MERRIMAC AVE. NILES, IL 60648</b>						A. State Manifest Document Number <b>MA C 446489</b>			
4. Generator's Phone (312) 967-7575						B. State Gen. ID <b>SAME</b>			
5. Transporter 1 Company Name <b>CLEAN HARBOR'S OF KINGSTON</b>						6. US EPA ID Number <b>MA D 039322250</b>			
7. Transporter 2 Company Name						C. State Trans. ID <b>MA 42696</b>			
8. US EPA ID Number						D. Transporter's Phone ( )			
9. Designated Facility Name and Site Address <b>CLEAN HARBORS OF BRAINTREE INC. 305 QUINCY AVENUE BRAINTREE, MA 02184</b>						E. State Trans. ID			
10. US EPA ID Number <b>MA D 05345126137</b>						F. Transporter's Phone ( )			
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)						G. State Facility's ID <b>Not Required</b>			
a. <b>HAZARDOUS WASTE LIQUID N.O.S. R.Q. ORM-E NA 9189</b>						H. Facility's Phone (617) 849-1807			
b.						12. Containers			
c.						13. Total Quantity			
d.						14. Unit Wt/Vol			
e.						15. Waste No.			
f.						g.			
g.						h.			
h.						i.			
i.						j.			
j.						k.			
k.						l.			
l.						m.			
m.						n.			
n.						o.			
o.						p.			
p.						q.			
q.						r.			
r.						s.			
s.						t.			
t.						u.			
u.						v.			
v.						w.			
w.						x.			
x.						y.			
y.						z.			
z.						aa.			
aa.						ab.			
ab.						ac.			
ac.						ad.			
ad.						ae.			
ae.						af.			
af.						ag.			
ag.						ah.			
ah.						ai.			
ai.						aj.			
aj.						ak.			
ak.						al.			
al.						am.			
am.						an.			
an.						ao.			
ao.						ap.			
ap.						aq.			
aq.						ar.			
ar.						as.			
as.						at.			
at.						au.			
au.						av.			
av.						aw.			
aw.						ax.			
ax.						ay.			
ay.						az.			
az.						ba.			
ba.						bb.			
bb.						bc.			
bc.						bd.			
bd.						be.			
be.						bf.			
bf.						bg.			
bg.						bh.			
bh.						bi.			
bi.						bj.			
bj.						bk.			
bk.						bl.			
bl.						bm.			
bm.						bn.			
bn.						bo.			
bo.						bp.			
bp.						bq.			
bq.						br.			
br.						bs.			
bs.						bt.			
bt.						bu.			
bu.						bv.			
bv.						bw.			
bw.						bx.			
bx.						by.			
by.						bz.			
bz.						ca.			
ca.						cb.			
cb.						cc.			
cc.						cd.			
cd.						ce.			
ce.						cf.			
cf.						cg.			
cg.						ch.			
ch.						ci.			
ci.						cj.			
cj.						ck.			
ck.						cl.			
cl.						cm.			
cm.						cn.			
cn.						co.			
co.						cp.			
cp.						cq.			
cq.						cr.			
cr.						cs.			
cs.						ct.			
ct.						cu.			
cu.						cv.			
cv.						cw.			
cw.						cx.			
cx.						cy.			
cy.						cz.			
cz.						da.			
da.						db.			
db.						dc.			
dc.						dd.			
dd.						de.			
de.						df.			
df.						dg.			
dg.						dh.			
dh.						di.			
di.						dj.			
dj.						dk.			
dk.						dl.			
dl.						dm.			
dm.						dn.			
dn.						do.			
do.						dp.			
dp.						dq.			
dq.						dr.			
dr.						ds.			
ds.						dt.			
dt.						du.			
du.						dv.			
dv.						dw.			
dw.						dx.			
dx.						dy.			
dy.						dz.			
dz.						ea.			
ea.						eb.			
eb.						ec.			
ec.						ed.			
ed.						ee.			
ee.						ef.			
ef.						eg.			
eg.						eh.			
eh.						ei.			
ei.						ej.			
ej.						ek.			
ek.						el.			
el.						em.			
em.						en.			
en.						eo.			
eo.						ep.			
ep.						eq.			
eq.						er.			
er.						es.			
es.						et.			
et.						eu.			
eu.						ev.			
ev.						ew.			
ew.						ex.			
ex.						ey.			
ey.						ez.			
ez.						fa.			
fa.						fb.			
fb.						fc.			
fc.						fd.			
fd.						fe.			
fe.						ff.			
ff.						fg.			
fg.						fh.			
fh.						fi.			
fi.						fj.			
fj.						fk.			
fk.						fl.			
fl.						fm.			
fm.						fn.			
fn.						fo.			
fo.						fp.			
fp.						fq.			
fq.						fr.			
fr.						fs.			
fs.						ft.			
ft.						fu.			
fu.						fv.			
fv.						fw.			
fw.						fx.			
fx.						fy.			
fy.						fz.			
fz.						ga.			
ga.						gb.			
gb.						gc.			
gc.						gd.			
gd.						ge.			
ge.						gf.			
gf.						gg.			
gg.						gh.			
gh.						gi.			
gi.						gj.			
gj.						gk.			
gk.						gl.			
gl.						gm.			
gm.						gn.			
gn.						go.			
go.						gp.			
gp.						gq.			
gq.						gr.			
gr.						gs.			
gs.						gt.			
gt.						gu.			
gu.						gv.			
gv.						gw.			
gw.						gx.			
gx.						gy.			
gy.						gz.			
gz.						ha.			
ha.						hb.			
hb.						hc.			
hc.						hd.			
hd.						he.			
he.						hf.			
hf.						hg.			
hg.						hh.			
hh.						hi.			
hi.						hj.			
hj.						hk.			
hk.						hl.			
hl.						hm.			
hm.						hn.			
hn.						ho.			
ho.						hp.			
hp.						hq.			
hq.						hr.			
hr.						hs.			
hs.						ht.			
ht.						hu.			
hu.						hv.			
hv.						hw.			
hw.						hx.			
hx.						hy.			
hy.						hz.			
hz.						ia.			
ia.						ib.			
ib.						ic.			
ic.						id.			
id.						ie.			
ie.						if.			
if.						ig.			
ig.						ih.			
ih.						ii.			
ii.						ij.			
ij.						ik.			
ik.						il.			
il.						im.			
im.						in.			
in.						io.			
io.						ip.			
ip.						iq.			
iq.						ir.			
ir.						is.			
is.						it.			
it.						iu.			
iu.						iv.			
iv.						iw.			
iw.						ix.			
ix.						iy.			
iy.						iz.			
iz.						ja.			
ja.						jb.			
jb.						jc.			
jc.						jd.			
jd.						je.			
je.						jf.			
jf.						jg.			
jg.						jh.			
jh.						ji.			
ji.						jj.			
jj.						jk.			
jk.						jl.			
jl.						jm.			
jm.						jn.			
jn.						jo.			
jo.						jp.			
jp.						jq.			
jq.						jr.			
jr.						js.			
js.						jt.			
jt.						ju.			
ju.						jv.			
jv.						jw.			
jw.						jx.			
jx.						jy.			
jy.						jz.			
jz.						ka.			
ka.						kb.			
kb.						kc.			
kc.						kd.			
kd.						ke.			
ke.						kf.			
kf.						kg.			
kg.						kh.			
kh.						ki.			
ki.						kj.			
kj.						kk.			
kk.						kl.			
kl.						km.			
km.						kn.			
kn.						ko.			
ko.						kp.			
kp.						kq.			
kq.						kr.			
kr.						ks.			
ks.						kt.			
kt.						ku.			
ku.						kv.			
kv.						kw.			
kw.						kx.			
kx.						ky.			
ky.						kz.			
kz.						la.			
la.						lb.			
lb.						lc.			
lc.						ld.			
ld.						le.			
le.						lf.			
lf.						lg.			
lg.						lh.			
lh.						li.			
li.						lj.			
lj.						lk.			
lk.						ll.			
ll.						lm.			
lm.						ln.			
ln.						lo.			
lo.						lp.			
lp.						lq.			
lq.						lr.			
lr.						ls.			
ls.						lt.			
lt.						lu.			
lu.						lv.			
lv.						lw.			
lw.						lx.			
lx.						ly.			
ly.						lz.			
lz.						ma.			
ma.						mb.			
mb.						mc.			
mc.						md.			
md.						me.			
me.						mf.			
mf.						mg.			
mg.						mh.			
mh.						mi.			
mi.						mj.			
mj.						mk.			
mk.						ml.			
ml.						mm.			
mm.						mn.			
mn.						mo.			
mo.						mp.			
mp.						mq.			
mq.						mr.			
mr.						ms.			
ms.						mt.			
mt.						mu.			
mu.						mv.			
mv.						mw.			
mw.						mx.			
mx.						my.			
my.						mz.			
mz.						na.			
na.						nb.			
nb.						nc.			
nc.						nd.			
nd.						ne.			
ne.						nf.			
nf.						ng.			
ng.						nh.			
nh.						ni.			
ni.						nj.			
nj.						nk.			
nk.						nl.			
nl.						nm.			
nm.						nn.			
nn.						no.			
no.						np.			
np.						nq.			
nq.						nr.			
nr.						ns.			
ns.						nt.			
nt.						nu.			
nu.						nv.			
nv.						nw.			
nw.						nx.			
nx.						ny.			
ny.						nz.			
nz.						oa.			
oa.						ob.			
ob.						oc.			
oc.						od.			
od.						oe.			
oe.						of.			
of.						og.			
og.						oh.			
oh.						oi.			
oi.						oj.			
oj.						ok.			
ok.						ol.			
ol.						om.			
om.						on.			
on.						oo.			
oo.						op.			
op.						oq.			
oq.						or.			
or.						os.			
os.						ot.			
ot.						ou.			
ou.						ov.			
ov.						ow.			
ow.						ox.			
ox.						oy.			
oy.						oz.			
oz.						pa.			
pa.						pb.			
pb.						pc.			
pc.						pd.			
pd.						pe.			
pe.						pf.			
pf.						pg.			
pg.						ph.			
ph.						pi.			
pi.						pj.			
pj.						pk.			
pk.						pl.			
pl.						pm.			
pm.						pn.			
pn.						po.			
po.						pp.			
pp.						pq.			
pq.						pr.			
pr.						ps.			
ps.						pt.			
pt.						pu.			
pu.						pv.			
pv.						pw.			
pw.						px.			
px.						py.			
py.						pz.			
pz.						qa.			
qa.						qb.			
qb.						qc.			
qc.						qd.			
qd.						qe.			
qe.						qf.			
qf.						qg.			
qg.						qh.			
qh.						qi.			
qi.						qj.			
qj.						qk.			
qk.						ql.			
ql.						qm.			
qm.						qn.			
qn.						qo.			
qo.						qp.			
qp.						qq.			
qq.						qr.			
qr.						qs.			
qs.						qt.			
qt.						qu.			
qu.						qv.			
qv.						qw.			
qw.						qx.			
qx.						qy.			
qy.						qz.			
qz.						ra.			
ra.						rb.			
rb.						rc.			
rc.						rd.			
rd.						re.			
re.						rf.			
rf.						rg.			
rg.						rh.			
rh.						ri.			
ri.						rj.			
rj.						rk.			
rk.						rl.			
rl.						rm.			
rm.						rn.			
rn.						ro.			
ro.						rp.			
rp.						rq.			
rq.						rr.			
rr.						rs.			
rs.						rt.			
rt.						ru.			
ru.						rv.			
rv.						rw.			
rw.						rx.			
rx.						ry.			
ry.						rz.			
rz.						sa.			
sa.						sb.			
sb.						sc.			
sc.						sd.			
sd.						se.			
se.						sf.			
sf.						sg.			
sg.						sh.			
sh.						si.			
si.						sj.			
sj.						sk.			
sk.						sl.			
sl.						sm.			
sm.						sn.			
sn.						so.			
so.						sp.			
sp.						sq.			
sq.						sr.			
sr.						ss.			
ss.						st.			
st.						su.			
su.						sv.			
sv.						sw.			
sw.						sx.			
sx.						sy.			
sy.						sz.			
sz.						ta.			
ta.						tb.			
tb									



Please print or type.

(Form designed for use

with (12-pitch) typewriter.)

EPA Form 8700-22 (4)

Form Approved. OMB No. 2000-0404 Expires 7-31-87

UNIFORM HAZARDOUS WASTE MANIFEST		1. Generator's US EPA ID No. I L D 0 0 ' 2 ' 2 ' 9 ' 3 ' 1 ' 2 ' 4 ' 0 0 1 2	Manifest Document No. 0012	2. Page 1 of 1	Information in the shaded areas is not required by Federal law, but is required by Illinois law.
3. Generator's Name and Mailing Address Croda Inks Corporation 7777 N. Merrimac Avenue Niles, IL 60648-3490				A. Illinois Manifest Document Number 1473743	
4. Generator's Phone ( )				B. Illinois Generator's ID 101311121011510111	
5. Transporter 1 Company Name Set Liquid Waste				C. Illinois Transporter's ID 1010419	
6. US EPA ID Number I L D 0 0 0 8 1 0 5 4 9				D. (312) 537-9221 Transporter's Phone	
7. Transporter 2 Company Name				E. Illinois Transporter's ID	
8. US EPA ID Number				F. (312) 537-9221 Transporter's Phone	
9. Designated Facility Name and Site Address Chem-Clear Inc. 11800 S. Stony Island Chicago, IL 60617				G. Illinois Facility's ID 101311161010101511	
10. US EPA ID Number I L D 0 0 0 6 0 8 4 7 1				H. Facility's Phone (312) 646-2021	
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)				12. Containers No. Type	13. Total Quantity
a. HM X Hazardous Waste Liquid N. O. S. ORM-E NA 9189				0 0 1 T T	2 0 0 0
b.					
c.					
d.					
J. Additional Descriptions for Materials Listed Above.				K. Handling Codes for Wastes Listed Above In Item #14 1 = Gallons 2 = Cubic Yards	
15. Special Handling Instructions and Additional Information					
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national government regulations, and Illinois regulations.  Unless I am a small quantity generator who has been exempted by statute or regulation from the duty to make a waste minimization certification under Section 3002(b) of RCRA, I also certify that I have a program in place to reduce the volume and toxicity of waste generated to the degree I have determined to be economically practicable and I have selected the method of treatment, storage, or disposal currently available to me which minimizes the present and future threat to human health and the environment.					
Printed/Typed Name Dean R. Roeing				Signature Dean R. Roeing	Date 03/26/86
17. Transporter 1 Acknowledgement of Receipt of Materials Printed/Typed Name Michael H Kwiatkowski				Signature Michael H Kwiatkowski	Date 03/26/86
18. Transporter 2 Acknowledgement of Receipt of Materials Printed/Typed Name				Signature	Date
19. Discrepancy Indication Space 4. 312-967-7578					
20. Facility Owner or Operator Certification of receipt of hazardous materials covered by this manifest except as noted in item 19. Printed/Typed Name Mark E. Douglas				Signature Mark E. Douglas	Date 03/28/86

IN ILLINOIS: 217 / 782-3637

24 HOUR EMERGENCY AND SPILL ASSISTANCE NUMBERS\* OUTSIDE ILLINOIS: 800 / 424-8802 or 202 / 426-2677

DISTRIBUTION: PART - 1 GENERATOR PART - 2 IEPA PART - 3 FACILITY PART - 4 TRANSPORTER PART - 5 IEPA PART - 6 GENERATOR

GENERATOR COPY - PART 1 - DO NOT REMOVE PART 1 FROM SET UNTIL COMPLETED.

This Agency is authorized to require, pursuant to Illinois Revised Statutes, 1983, Chapter 111 1/2 Section 21, that this information be submitted to the Agency. Failure to provide the information may result in a civil penalty against or operator of not to exceed \$25,000 per day of violation. Falsification of this information may result in a fine up to \$50,000 per day of violation and imprisonment up to 5 years. This form has been approved by the Forms Center.

Please print or type.

(Form designed for use on 11x17 (12-pitch) typewriter)

EPA Form 8700-22 (3-87)

Form Approved. OMB No. 2000-0404 Expires 7-31-86

UNIFORM HAZARDOUS WASTE MANIFEST		1. Generator's US EPA ID No. I L D 0 0 2 2 9 3 1 2 4 0 0 0 1 4		Manifest Document No. 00014		2. Page 1 of 1		Information in the shaded areas is not required by Federal law, but is required by Illinois law.					
3. Generator's Name and Mailing Address Croda Inks Corporation 7777 N. Merrimac Avenue Niles, IL 60648-3490						A. Illinois Manifest Document Number 115001473741							
4. Generator's Phone (312) 967-7575						B. Illinois Generator's ID Number 0312015011							
5. Transporter 1 Company Name Set Liquid Waste						C. Illinois Transporter's ID 10101419							
6. US EPA ID Number I L D 0 0 0 8 1 0 5 4 9						D. (312) 537-9221 Transporter's Phone							
7. Transporter 2 Company Name						E. Illinois Transporter's ID							
8. US EPA ID Number						F. (312) 537-9221 Transporter's Phone							
9. Designated Facility Name and Site Address Chem-Clear Inc. 11800 S. Stony Island Chicago, IL 60617						G. Illinois Facility's ID 10131161010101511							
10. US EPA ID Number I L D 0 0 0 6 0 8 4 7 1						H. Facility's Phone (312) 646-6202							
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)						12. Containers		13. Total Quantity		14. Unit Wt/Vol		15. Waste No.	
a. <input checked="" type="checkbox"/> Hazardous Waste Liquid N. O. S. ORM-E NA 9189						0 0 1 T T		1500		1		EPA HW Number K 0 1 8 1 6 Authorization Number 0 0 1 0 1 2 1 0	
b.												EPA HW Number Authorization Number	
c.												EPA HW Number Authorization Number	
d.												EPA HW Number Authorization Number	
J. Additional Descriptions for Materials Listed Above						K. Handling Codes for Wastes Listed Above In Item #14 1 = Gallons 2 = Cubic Yards							
15. Special Handling Instructions and Additional Information													
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national government regulations, and Illinois regulations. Unless I am a small quantity generator who has been exempted by statute or regulation from the duty to make a waste minimization certification under Section 3002(b) of RCRA, I also certify that I have a program in place to reduce the volume and toxicity of waste generated to the degree I have determined to be economically practicable and I have selected the method of treatment, storage, or disposal currently available to me which minimizes the present and future threat to human health and the environment.													
Printed/Typed Name SEVERINO S. PARLINAS						Signature Severino Parlinas						Date 08/27/86	
17. Transporter 1 Acknowledgement of Receipt of Materials												Date	
Printed/Typed Name GORDON R BLUE						Signature Gordon R Blue						Date 08/27/86	
18. Transporter 2 Acknowledgement of Receipt of Materials												Date	
Printed/Typed Name						Signature						Date	
19. Discrepancy Indication Space													
20. Facility Owner or Operator Certification of receipt of hazardous materials covered by this manifest except as noted in item 19.													
Printed/Typed Name L. Belinsky						Signature L. Belinsky						Date 08/27/86	

IN ILLINOIS: 217 / 782-3637

\*24 HOUR EMERGENCY AND SPILL ASSISTANCE NUMBERS\* OUTSIDE ILLINOIS: 800 / 424-8802 or 202 / 426-2675

DISTRIBUTION: PART - 1 GENERATOR PART - 2 IEPA PART - 3 FACILITY PART - 4 TRANSPORTER PART - 5 IEPA PART - 6 GENERATOR

GENERATOR COPY - PART 1 - DO NOT REMOVE PART 1 FROM SET UNTIL COMPLETED.

Agency is authorized to require, pursuant to Illinois Revised Statutes, 1983, Chapter 111 1/2 Section 21, that this information be submitted to the Agency. Failure to provide the information may result in a civil penalty against the owner. Penalty of not less than \$25,000 per day of violation. Failure to provide this information may result in a fine up to \$50,000 per day of violation and imprisonment up to 5 years. This form has been approved by the Federal Management Agency.

Form Approved, OMB No. 2000-0404 Expires 7-31-86

This Agency is authorized to require, pursuant to Illinois Revised Statutes, 1993, Chapter 111½ Section 21, that this information be submitted to the Agency. Failure to provide the information may result in a civil penalty against the owner or operator of not to exceed \$25,000 per day of violation. Falsification of this information may result in a fine up to \$50,000 per day of violation and imprisonment up to 5 years. This form has been approved by the Forms Management

Please print or type

(Form designed for use

file (12-pitch) typewriter.)

EPA Form 8700-22 4)

Form Approved. OMB No. 2000-0404 Expires 7-31-87

**UNIFORM HAZARDOUS  
WASTE MANIFEST**

1. Generator's US EPA ID No.

I L D 0 0 2 2-9-3 1 2 4 0 0 1 1

2. Page 1

of 1

Information in the shaded areas is not required by Federal law, but is required by Illinois law.

3. Generator's Name and Mailing Address

Croda Inks Corporation

7777 N. Merrimac Avenue Niles, IL 60648-3490

4. Generator's Phone ( 312 ) 967-7575

5. Transporter 1 Company Name

Set Liquid Waste

6. US EPA ID Number

I L D 0 0 0 8 1 0 5 4 9

7. Transporter 2 Company Name

8. US EPA ID Number

9. Designated Facility Name and Site Address

Chem-Clear Inc.

11800 S. Stony Island

Chicago, IL 60617

10. US EPA ID Number

I L D 0 0 0 6 0 8 4 7 1

A. Illinois Manifest Document Number

1473744

B. Illinois Generator's ID

1031120115011

C. Illinois Transporter's ID

10101419

D. (312) 537-9221 Transporter's Phone

E. Illinois Transporter's ID

F. Transporter's Phone

G. Illinois Facility's ID

1031160000051

H. Facility's Phone

(312) 646-6202

11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)

HM

a. X Hazardous Waste Liquid  
N. O. S. ORM-E NA 9189

12. Containers

No.

Type

0 0 1 T T

13. Total Quantity

1500

2000

14. Unit Wt/Vol

1

G

I. Waste No.

EPA HW Number

1010101210

Authorization Number

EPA HW Number

Authorization Number

EPA HW Number

Authorization Number

EPA HW Number

Authorization Number

EPA HW Number

Authorization Number

J. Additional Descriptions for Materials Listed Above.

1. 100% Acetone

2. 100% Acetone

K. Handling Codes for Wastes Listed Above  
In Item #14

1 = Gallons 2 = Cubic Yards

15. Special Handling Instructions and Additional Information

16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national government regulations, and Illinois regulations.

Unless I am a small quantity generator who has been exempted by statute or regulation from the duty to make a waste minimization certification under Section 3002(b) of RCRA, I also certify that I have a program in place to reduce the volume and toxicity of waste generated to the degree I have determined to be economically practicable and I have selected the method of treatment, storage, or disposal currently available to me which minimizes the present and future threat to human health and the environment.

Printed/Typed Name

DENNIS PELKA

Signature

Dennis Pelka

Date

12/10/85

17. Transporter 1 Acknowledgement of Receipt of Materials

Printed/Typed Name

GEORGE ROVER

Signature

George Rover

Date

12/10/85

18. Transporter 2 Acknowledgement of Receipt of Materials

Printed/Typed Name

Signature

Date

19. Discrepancy Indication Space

20. Facility Owner or Operator Certification of receipt of hazardous materials covered by this manifest except as noted in item 19.

Printed/Typed Name

Robert Simon

Signature

Robert Simon

Date

12/10/85

IN ILLINOIS: 217 / 782-3637

\*24 HOUR EMERGENCY AND SPILL ASSISTANCE NUMBERS\* OUTSIDE ILLINOIS: 800 / 424-8802 or 202 / 426-26

DISTRIBUTION: PART - 1 GENERATOR PART - 2 IEPA PART - 3 FACILITY PART - 4 TRANSPORTER PART - 5 IEPA PART - 6 GENERATOR

IEV. #6 GENERATOR COPY - PART 1 - DO NOT REMOVE PART 1 FROM SET UNTIL COMPLETED.

This Agency is authorized to require, pursuant to Illinois Revised Statutes, 1983, Chapter 111 1/2 Section 21, that this information be submitted to the Agency. Failure to provide the information may result in a civil penalty against the generator or operator of not to exceed \$25,000 per day of violation. Falsification of this information may result in a fine up to \$50,000 per day of violation and imprisonment up to 5 years. This form has been approved by the Forms Management Agency.





Please print or type.

(Form designed for use on a

2-pitch typewriter.)

EPA Form 8700-22 (3-

Form Approved. OMB No. 2000-0404. Expires 7-31-86

UNIFORM HAZARDOUS WASTE MANIFEST		1. Generator's US EPA ID No. I L D 0 0 2 2 9 3 1 2 4 0 6 0	Manifest Document No. 0 6 1 0	2. Page 1 of 1	Information in the shaded areas is not required by Federal law, but is required by Illinois law.
3. Generator's Name and Mailing Address Croda Inks Corporation 7777 N. Merrimac Avenue Niles, IL 60648-3490				A. Illinois Manifest Document Number IL 1277159	
4. Generator's Phone ( 312 ) 967-7575				B. Illinois Generator's ID 0 3 1 2 0 1 5 0 1 1	
5. Transporter 1 Company Name Set Liquid Waste				C. Illinois Transporter's ID 0 0 4 9	
6. US EPA ID Number I L D 0 0 0 8 1 0 5 4 9				D. (312) 537-9221 Transporter's Phone	
7. Transporter 2 Company Name				E. Illinois Transporter's ID	
8. US EPA ID Number				F. ( ) Transporter's Phone	
9. Designated Facility Name and Site Address Chem-Clear Inc. 11800 S. Stony Island Chicago, IL 60617				G. Illinois Facility's ID 0 3 1 6 0 0 0 0 5 1	
10. US EPA ID Number I L D 0 0 0 6 0 8 4 7 1				H. Facility's Phone (312) 646-6202	
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)				12. Containers No. Type	13. Total Quantity
a. HM X Hazardous Waste Liquid N. O. S. ORM-E NA 9189				0 0 1 T T	2 0 0 0
b.					
c.					
d.					
J. Additional Descriptions for Materials Listed Above				K. Handling Codes for Wastes Listed Above In Item #14: 1 = Gallons 2 = Cubic Yards	
15. Special Handling Instructions and Additional Information Control any spill and have a program in place to reduce the volume and toxicity of waste generated to the degree I have determined to be economically practicable and I have selected the method of treatment, storage, or disposal currently available to me, which minimizes the present and future threat to human health and environment.					
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national governmental regulations, and Illinois regulations.					
Printed/Typed Name SEVERINO PARINAS				Signature <i>Severino Parinas</i>	Date Month Day Year 10 3 85
17. Transporter 1 Acknowledgement of Receipt of Materials				Date	
Printed/Typed Name Harry Swanson				Signature <i>Harry Swanson</i>	Month Day Year 10 3 85
18. Transporter 2 Acknowledgement or Receipt of Materials				Date	
Printed/Typed Name				Signature	Month Day Year
19. Discrepancy Indication Space					
20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in Item 19.					
Printed/Typed Name L. Belinsky				Signature <i>L. Belinsky</i>	Date Month Day Year 10 3 85

IN ILLINOIS: 217 / 782-3637

24 HOUR EMERGENCY AND SPILL ASSISTANCE NUMBERS\*

OUTSIDE ILLINOIS: 800 / 424-8802 or 202 / 426-2675

DISTRIBUTION: PART - 1 GENERATOR PART - 2 IEPA PART - 3 FACILITY PART - 4 TRANSPORTER PART - 5 IEPA PART - 6 GENERATOR

# 5

GENERATOR COPY - PART 1 - DO NOT REMOVE PART 1 FROM SET UNTIL COMPLETED.

This Agency is authorized to require, pursuant to Illinois Revised Statutes, 1963, Chapter 111 1/2 Section 21, that the information be submitted to the Agency. Failure to provide the information may result in a civil penalty against the owner or operator of not to exceed \$25,000 per day of violation. Falsification of this information may result in a fine up to \$80,000 per day of violation and imprisonment up to 8 years. This form has been approved by the Waste Management

Please print or type.

(Form designed for use with a (12-pitch) typewriter.)

EPA Form 8700-22 4)

Form Approved OMB No. 2000-0404 Expires 7-31-87

**UNIFORM HAZARDOUS WASTE MANIFEST**

1. Generator's US EPA ID No.

I L D 0 0 2 2 9 3 1 2 4 0 0 0 9

2. Page 1

of 1

Information in the shaded areas is not required by Federal law, but is required by Illinois law.

3. Generator's Name and Mailing Address

Croda Inks Corporation  
7777 N. Merrimac Ave.

Illinois Manifest Document Number

IL 1277151

4. Generator's Phone

Niles, IL 60648-3490 (312) 967-7575

Illinois Generator's ID

10311201150111

5. Transporter 1 Company Name

Set Liquid Waste

6. US EPA ID Number

I L D 0 0 0 8 1 0 5 4 9

Illinois Transporter's ID

10101419

7. Transporter 2 Company Name

8. US EPA ID Number

D( 312 537-9221 Transporter's Phone

Illinois Transporter's ID

F( ) Transporter's Phone

9. Designated Facility Name and Site Address

Chem-Clear Inc.  
11800 S. Stony Island  
Chicago, IL 60617

10. US EPA ID Number

I L D 0 0 0 6 0 8 4 7 1

Illinois Facility's ID

1031169010051

Facility's Phone

(312) 646-6202

11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)

12. Containers

No. Type

13. Total Quantity

14. Unit Wt/Vol

L Waste No.

HM

a.

X

Hazardous Waste Liquid  
N.O.S. ORM-E NA9189

0 0 1 T T

2 0 0 0 G

EPA HW Number

K101816

Authorization Number

0101010210

b.

EPA HW Number

Authorization Number

c.

EPA HW Number

Authorization Number

d.

EPA HW Number

Authorization Number

J. Additional Descriptions for Materials Listed Above

K. Handling Codes for Wastes Listed Above

In Item #14: 1 = Gallons  
2 = Cubic Yards

15. Special Handling Instructions and Additional Information

Contains lead and chromium

Control any spill

16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national governmental regulations, and Illinois regulations.

Printed/Typed Name

S. S. Parinas, Jr.

Signature

S. S. Parinas, Jr.

Date

Month Day Year

10 6 12 6 18

17. Transporter 1 Acknowledgement of Receipt of Materials

Printed/Typed Name

JOE FOIKENTS

Signature

Joe Foikents

Date

Month Day Year

10 6 12 6 18

18. Transporter 2 Acknowledgement or Receipt of Materials

Printed/Typed Name

Signature

Date

Month Day Year

1 1 1 1

19. Discrepancy Indication Space

20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in Item 19.

Printed/Typed Name

L. Belinsky

Signature

L. Belinsky

Date

Month Day Year

1 6 12 6 18

IN ILLINOIS: 217 / 782-3637

24 HOUR EMERGENCY AND SPILL ASSISTANCE NUMBERS\*

OUTSIDE ILLINOIS: 800 / 424-8802 or 202 / 426-2266

DISTRIBUTION: PART - 1 GENERATOR PART - 2 IEPA PART - 3 FACILITY PART - 4 TRANSPORTER PART - 5 IEPA PART - 6 GENERATOR

EV.# 5

GENERATOR COPY - PART 1- DO NOT REMOVE PART 1 FROM SET UNTIL COMPLETED.

This Agency is authorized to require, pursuant to Illinois Revised Statutes, 1983, Chapter 111 1/2, Section 21, that this information be submitted to the Agency. Failure to provide the information may result in a civil penalty against the owner or operator of not to exceed \$25,000 per day of violation. Falsification of this information may result in a fine up to \$50,000 per day of violation and imprisonment up to 5 years. This form has been approved by the Forms Management Center.



Please print or type.

(Form designed for use on

12-pitch) typewriter.)

EPA Form 8700-22 (3)

Form Approved OMB No. 2000-0404 Expires 7-31-86

UNIFORM HAZARDOUS  
WASTE MANIFEST1. Generator's US EPA ID No.  
I L D 0 0 2 2 9 3 1 2 4 0 0 0 82. Page 1  
of 1  
Information in the shaded areas is not required by Federal law, but is required by Illinois law.A. Illinois Manifest Document Number  
IL 1114938B. Illinois Generator's ID  
01312015011C. Illinois Transporter's ID  
D(312) 537-9221E. Illinois Transporter's ID  
F( )G. Illinois Facility's ID  
0336000051H. Facility's Phone  
(312) 646-6202

3. Generator's Name and Mailing Address

CRODA INKS CORPORATION  
7777 North Merrimac Avenue, Niles, IL 60648-3490

4. Generator's Phone ( 312 ) 967-7575

5. Transporter 1 Company Name

Set Liquid Waste

6. US EPA ID Number

I L D 0 0 0 9 1 0 5 4

7. Transporter 2 Company Name

8. US EPA ID Number

9. Designated Facility Name and Site Address

Chem-Clear, Inc.  
11800 S. Stoney Island  
Chicago, IL 60617

10. US EPA ID Number

I L D 0 0 0 6 0 8 4 7

11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)

12. Containers

13. Total

14. Unit

15. Waste No.

a. HM

X

Hazardous Waste Liquid  
N. O. S. ORM-E NA 9189

No.

Type

Quantity

Wt/Vol

Waste No.

b.

c.

d.

No.

Type

Quantity

Wt/Vol

Waste No.

e.

f.

g.

h.

i.

j.

k.

l.

m.

n.

o.

p.

q.

r.

s.

t.

u.

v.

w.

x.

y.

z.

aa.

ab.

ac.

ad.

ae.

af.

ag.

ah.

ai.

aj.

ak.

al.

am.

an.

ao.

ap.

aq.

ar.

as.

at.

au.

av.

aw.

ax.

ay.

az.

ba.

bb.

bc.

bd.

be.

bf.

bg.

bh.

bi.

bj.

bk.

bl.

bm.

bn.

bo.

bp.

bq.

br.

bs.

bt.

bu.

bv.

bw.

bx.

by.

bz.

ca.

cb.

cc.

cd.

ce.

cf.

cg.

ch.

ci.

cj.

ck.

cl.

cm.

cn.

co.

cp.

cq.

cr.

cs.

ct.

cu.

cv.

cw.

cx.

cy.

cz.

da.

db.

dc.

dd.

de.

df.

dg.

dh.

di.

dj.

dk.

dl.

dm.

dn.

do.

dp.

dq.

dr.

ds.

dt.

du.

dv.

dw.

dx.

dy.

dz.

ea.

eb.

ec.

ed.

ee.

ef.

eg.

eh.

ei.

ej.

ek.

el.

em.

en.

eo.

ep.

eq.

er.

es.

et.

eu.

ev.

ew.

ex.

ey.

ez.

fa.

fb.

fc.

fd.

fe.

fg.

fh.

fi.

fj.

fk.

fl.

fm.

fn.

fo.

fp.

fq.

fr.

fs.

ft.

fu.

fv.

fw.

fx.

fy.

fz.

ga.

gb.

gc.

gd.

ge.

gf.

gg.

gh.

gi.

gj.

gk.

gl.

gm.

gn.

go.

gp.

gq.

gr.

gs.

gt.

gu.

gv.

gw.

gx.

gy.

gz.

ha.

hb.

hc.

hd.

he.

hf.

hg.

hh.

hi.

hj.

hk.

hl.

hm.

hn.

ho.

hp.

hq.

hr.

hs.

ht.

hu.

hv.

hw.

hx.

hy.

hz.

ia.

ib.

ic.

id.

ie.

if.

ig.

ih.

ii.

ij.

ik.

il.

im.

in.

io.

ip.

iq.

ir.

is.

it.

iu.

iv.

iw.

ix.

iy.

iz.

ja.

jb.

jc.

jd.

je.

jf.

jg.

jh.

ji.

jj.

jk.

jl.

jm.

jn.

jo.

jp.

jq.

jr.

js.

jt.

ju.

jv.

jw.

jx.

jy.

jz.

ka.

kb.

kc.

kd.

ke.

kf.

kg.

kh.

ki.

kj.

kk.

kl.

km.

kn.

ko.

kp.

kq.

kr.

ks.

kt.

ku.

kv.

kw.

kx.

ky.

kz.

la.

lb.

lc.

ld.

le.

lf.

lg.

lh.

li.

lj.

lk.

ll.

lm.

ln.

lo.

lp.

lq.

lr.

ls.

lt.

lu.

lv.

lw.

lx.

ly.

lz.

ma.

mb.

mc.

Please print or type.

(Form designed for use on

(12-pitch) typewriter.)

EPA Form 8700-22 (3)

Form Approved. OMB No. 2000-0404. Expires 7-31-86

<b>UNIFORM HAZARDOUS WASTE MANIFEST</b>		1. Generator's US EPA ID No. I L D 0 0 2 2 9 3 1 2 4 0 0 0 8		Manifest Document No. 0 0 0 8		2. Page 1 of 1		Information in the shaded areas is not required by Federal law, but is required by Illinois law.					
3. Generator's Name and Mailing Address Croda Inks Corporation 7777 N. Merrimac Ave. Niles, IL 60648-3490 4. Generator's Phone (312) 967-7575						A. Illinois Manifest Document Number IL 1114941							
5. Transporter 1 Company Name Set Liquid Waste						B. Illinois Generator's ID 1 0 3 1 2 0 1 5 0 1 1							
6. US EPA ID Number I L D 0 0 0 8 1 0 5 4 9						C. Illinois Transporter's ID 1 0 1 0 4 9							
7. Transporter 2 Company Name						D. (312) 537-9221 Transporter's Phone							
8. US EPA ID Number						E. Illinois Transporter's ID							
9. Designated Facility Name and Site Address Chem-Clear Inc. 11800 S. Stony Island Chicago, IL 60617						F. ( ) Transporter's Phone							
10. US EPA ID Number I L D 0 0 0 6 0 8 4 7 1						G. Illinois Facility's ID 1 0 1 3 1 6 0 0 0 0 5 1							
H. Facility's Phone (312) 646-6202													
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)						12. Containers No. Type		13. Total Quantity		14. Unit Wt/Vol		1. Waste No.	
a. X Hazardous Waste Liquid N.O.S ORM-E NA 9189						0 0 1 TT		0.2145		1		EPA HW Number K 0 1 8 6	
b.												Authorization Number	
c.												EPA HW Number	
d.												Authorization Number	
J. Additional Descriptions for Materials Listed Above						K. Handling Codes for Wastes Listed Above							
15. Special Handling Instructions and Additional Information Contains lead and chromium Control any spill													
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national governmental regulations, and Illinois regulations.													
Printed/Typed Name S. S. Parinas, Jr.						Signature S. S. Parinas, Jr.		Date Month Day Year 12/28/84					
17. Transporter 1 Acknowledgement of Receipt of Materials						Printed/Typed Name Harry Swanson		Signature Harry Swanson		Date Month Day Year 12/28/84			
18. Transporter 2 Acknowledgement or Receipt of Materials						Printed/Typed Name		Signature		Date Month Day Year			
19. Discrepancy Indication Space													
20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in Item 19.													
Printed/Typed Name L. Belinsky						Signature L. Belinsky		Date Month Day Year 12/28/84					

IN ILLINOIS: 217 / 782-3637

\*24 HOUR EMERGENCY AND SPILL ASSISTANCE NUMBERS\*

OUTSIDE ILLINOIS: 800 / 424-8802 or 202 / 426-2675

DISTRIBUTION: PART - 1 GENERATOR PART - 2 IEPA PART - 3 FACILITY PART - 4 TRANSPORTER PART - 5 IEPA PART - 6 GENERATOR

1.5 GENERATOR COPY - PART 1. DO NOT REMOVE PART 1 FROM SET UNTIL COMPLETED.

This Agency is authorized to require, pursuant to Illinois Revised Statutes, 1983, Chapter 111 1/2 Section 21, that this information be submitted to the Agency. Failure to provide the information may result in a civil penalty against the owner or operator of not to exceed \$25,000 per day of violation. Falsification of this information may result in a fine up to \$50,000 per day of violation and imprisonment up to 5 years. This form has been approved by the Forms Management Council.

Please print or type.

(Form designed for use on a

2 pitch) typewriter.)

EPA Form 8700-22 (3)

Form Approved. OMB No. 2000-0404. Expires 7-31-86

**UNIFORM HAZARDOUS  
WASTE MANIFEST**

1. Generator's US EPA ID No.

Manifest  
Document No.

2. Page 1

Information in the shaded areas is not  
required by Federal law, but is required  
by Illinois law.

I L D 0 0 2 2 9 3 1 2 4

0 0 0 7

of 1

3. Generator's Name and Mailing Address

Croda Inks Corporation

7777 N. Merrimac Ave.

Niles, IL 60648-3490

4. Generator's Phone (312) 967-7575

5. Transporter 1 Company Name

Set Liquid Waste

6. US EPA ID Number

I L D 0 0 0 8 1 0 5 4 9

7. Transporter 2 Company Name

8. US EPA ID Number

9. Designated Facility Name and Site Address

Chem-Clear Inc.

11800 S. Stony Island

Chicago, IL 60617

10. US EPA ID Number

I L D 0 0 0 6 0 8 4 7 1

A. Illinois Manifest Document Number

IL 1114937

B. Illinois

Generator's

ID

0 3 1 2 0 1 5 0 1 1

C. Illinois Transporter's ID

D (312) 537-9221 Transporter's Phone

E. Illinois Transporter's ID

F ( ) Transporter's Phone

G. Illinois

Facility's

ID

0 1 3 1 6 0 0 0 0 5 1

H. Facility's Phone

(312) 646-6202

11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)

HM

a. X

Hazardous Waste Liquid

N.O.S. ORM-E NA 9189

b.

c.

d.

J. Additional Descriptions for Materials Listed Above

K. Handling Codes for Wastes Listed Above

15. Special Handling Instructions and Additional Information

Contains lead and chromium  
Control any spill16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described  
above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition  
for transport by highway according to applicable international and national governmental regulations, and Illinois regulations.

Printed/Typed Name

D. R. Roeding

Signature

D. R. Roeding

Date

Month Day Year

10 02 84

17. Transporter 1 Acknowledgement of Receipt of Materials

Printed/Typed Name

GORDON R BLUE

Signature

Gordon R Blue

Date

Month Day Year

10 02 84

18. Transporter 2 Acknowledgement or Receipt of Materials

Printed/Typed Name

Signature

Date

Month Day Year

19. Discrepancy Indication Space

20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in  
Item 19.

Printed/Typed Name

L. Belinsky

Signature

L. Belinsky

Date

Month Day Year

10 12 84

IN ILLINOIS: 217 / 782-3637

24 HOUR EMERGENCY AND SPILL ASSISTANCE NUMBERS

OUTSIDE ILLINOIS: 800 / 424-8802 or 202 / 426-2675

DISTRIBUTION: PART - 1 GENERATOR PART - 2 IEPA

PART - 3 FACILITY

PART - 4 TRANSPORTER

PART - 5 IEPA

PART - 6 GENERATOR

GENERATOR COPY - PART 1- DO NOT REMOVE PART 1 FROM SET UNTIL COMPLETED.

Agency is authorized to require, pursuant to Illinois Revised Statutes, 1983, Chapter 111 1/2 Section 21, that this information be submitted to the Agency. Failure to provide the information may result in a civil penalty against the owner  
operator of not to exceed \$25,000 per day of violation. Falsification of this information may result in a fine up to \$50,000 per day of violation and imprisonment up to 5 years. This form has been approved by the Forms Management  
Unit.

GENERATOR

TRANSPORTER

FACILITY

TO BE COMPLETED BY  
WASTE GENERATOR

STATE OF ILLINOIS  
ENVIRONMENTAL PROTECTION AGENCY  
DIVISION OF LAND POLLUTION CONTROL  
SPECIAL WASTE HAULING MANIFEST  
WASTE GENERATOR

HAZARDOUS 011330  
87-003

Authorization Number 8106 25  
NON-HAZARDOUS  
0312010011  
Generator Number

CRODA INKS CORP.

(Company Name)

7777 N. MERRIMAC AVE.

Address

NILES

City

ILL.

State

60648

Zip

WASTE HAULER(S)

WASTE WATCHER

6305 OGDEN

S.W.H. Registration Number 0467001  
25

Hauler Name

Hauler Address

N/A

Hauler Name

N/A

Hauler Address

S.W.H. Registration Number

32

DESTINATION - DISPOSAL STORAGE OR TREATMENT SITE

CHICAGO

(Facility Name)

CID IL

Address

03160030

39

Site Number

City

State

Zip

TO BE COMPLETED BY  
WASTE GENERATOR

WASTE NAME: WATER WASHES & SLUDGE

WASTE PHASE: LIQUID  
(Liquid, Gaseous, Solid)

THE SPECIAL WASTE BEING TRANSPORTED UNDER THIS MANIFEST IS OF THE DOT HAZARD CLASSIFICATION INDICATED IMMEDIATELY BELOW:

SHIPPING DESCRIPTION:

N/A

HAZARD CLASS:

N/A

THIS IS TO CERTIFY THAT THE ABOVE NAMED SPECIAL WASTE IS PROPERLY CLASSIFIED, DESCRIBED, PACKAGED, MARKED, AND LABELED AND IS IN PROPER CONDITION FOR TRANSPORTATION IN ACCORDANCE WITH THE APPLICABLE REGULATIONS OF THE DEPARTMENT OF TRANSPORTATION.

I HEREBY AGREE TO AND CERTIFY THE ABOVE WRITTEN INFORMATION

DATE: 3-11-82

William Hanning  
(Authorized Signature)

WASTE HAULER\*

QUANTITY OF WASTE RECEIVED: 1100

1 GALLONS (Circle One)  
2 CU. YDS. 1

METHOD OF SHIPMENT (Circle One)

DRUMS

TANK TRUCK

OPEN TRUCK

OTHER (Specify)

I HEREBY CERTIFY THAT THE ABOVE DESCRIBED SPECIAL WASTE AND QUANTITY HAS BEEN ACCEPTED IN PROPER CONDITION FOR TRANSPORT AND I ACKNOWLEDGE THE DESTINATION INDICATED.

(1) [Signature]  
(Authorized Signature)

DATE: 3/11/82

(2) [Signature]  
(Authorized Signature)

DATE: / /

DISPOSAL, STORAGE, OR TREATMENT FACILITY\*

I HEREBY CERTIFY THAT THE ABOVE DESCRIBED SPECIAL WASTE AND INDICATED QUANTITY HAS BEEN ACCEPTED:

[Signature]  
(Authorized Signature)

DATE: 3/11/82

MENTS OR SPECIAL INSTRUCTIONS:

IN ILLINOIS 217 / 782 3637

\*24 HOUR EMERGENCY AND SPILL ASSISTANCE NUMBERS\*

OUTSIDE ILLINOIS 800 / 474

DISTRIBUTION PART 1 GENERATOR

PART 2 EPA

PART 3 SH

PART 4 HAULER

PART 5 EPA

PART 6 GENERATOR

GENERATOR COPY - PART 1 - DO NOT REMOVE PART 1 FROM SET UNTIL COMPLETED.

TO BE COMPLETED BY  
WASTE GENERATOR

STATE OF ILLINOIS  
ENVIRONMENTAL PROTECTION AGENCY  
DIVISION OF LAND POLLUTION CONTROL  
SPECIAL WASTE HAULING MANIFEST  
WASTE GENERATOR

01155

87-004

Authorization Number 922205

CRODA INKS CORP.

(Company Name)

7777 NORTH MERRIMAC AVE

Address

NILES

City

IL

State

60648

Zip

0312010011

14

Generator Number

WASTE HAULER(S)

(1) BROWNING - FERRIS

Hauler Name

MELROSE PARK IL

Hauler Address

60160

S.W.H. Registration Number 0107

29

(2)

Hauler Name

Hauler Address

S.W.H. Registration Number

32

DESTINATION -- DISPOSAL STORAGE OR TREATMENT SITE

CHEN - CLEAR

(Facility Name)

CHICAGO IL

Address

03160051

39

Site Number

City

State

Zip

TO BE COMPLETED BY  
WASTE GENERATOR

WASTE NAME: WATER WASHES

AND SLUDGE

WASTE PHASE: LIQUID

(Liquid, Gaseous, Solid)

NON - HAZARDOUS

THE SPECIAL WASTE BEING TRANSPORTED UNDER THIS MANIFEST IS OF THE DOT HAZARD CLASSIFICATION INDICATED IMMEDIATELY BELOW:

SHIPPING DESCRIPTION:

N/A

HAZARD CLASS:

N/A

THIS IS TO CERTIFY THAT THE ABOVE-NAMED SPECIAL WASTE IS PROPERLY CLASSIFIED, DESCRIBED, PACKAGED, MARKED, AND LABELED AND IS IN PROPER CONDITION FOR TRANSPORTATION IN ACCORDANCE WITH THE APPLICABLE REGULATIONS OF THE DEPARTMENT OF TRANSPORTATION.

I HEREBY AGREE TO AND CERTIFY THE ABOVE WRITTEN INFORMATION

DATE:

(Authorized Signature)

WASTE HAULER\*

QUANTITY OF WASTE RECEIVED:

47

32

GALLONS (Circle One)  
2 CU. YDS.

53

METHOD OF SHIPMENT (Circle One)

DRUMS

TANK TRUCK

OPEN TRUCK

OTHER (Specify)

I HEREBY CERTIFY THAT THE ABOVE DESCRIBED SPECIAL WASTE AND QUANTITY HAS BEEN ACCEPTED IN PROPER CONDITION FOR TRANSPORT AND I ACKNOWLEDGE THE DESTINATION INDICATED:

(1)

(Authorized Signature)

DATE:

54

(2)

(Authorized Signature)

DATE:

54

DISPOSAL, STORAGE, OR TREATMENT FACILITY\*

I HEREBY CERTIFY THAT THE ABOVE DESCRIBED SPECIAL WASTE AND INDICATED QUANTITY HAS BEEN ACCEPTED:

(Authorized Signature)

DATE:

60

REMARKS OR SPECIAL INSTRUCTIONS:

IN ILLINOIS: 217 / 782-3637

\*24 HOUR EMERGENCY AND SPILL ASSISTANCE NUMBERS\*

OUTSIDE ILLINOIS: 800 / 424

DISTRIBUTION: PART 1 GENERATOR

PART 2 IEPA

PART 3 SITE

PART 4 HAULER

PART 5 IEPA

PART 6 GENERATOR

GENERATOR COPY - PART 6

## APPENDIX D

### SOIL ANALYTICAL RESULTS FROM BASE OF UST EXCAVATION




# TENCO LABORATORIES

BPM INDUSTRIES  
1150 Junction Avenue - Schererville, Indiana 46375  
1-219-322-2560 • 1-800-428-3311

Page 1 of 2

## REPORT TO:

Jean Millard  
Chem Clear  
1800 187th St  
Calumet City IL 60409  
EPA METHOD



Date: 12/21/88

Recd: 12/19/88

WO #: 21-0718

Laboratory Smp ID No.:	2987-9	2988-9	2989-9				
DESCRIPTION: —> otherwise noted; units in parts per million - ppm PARAMETERS: ↓	CC # 2 South 12/14/88	CC # 3 Center 12/14/88	CC # 1 North End 12/14/88				Detection Limit
acetone	ND	ND	ND				1 mg/kg
benzene	ND	ND	ND				1 mg/kg
Butyl Alcohol	ND	ND	ND				1 mg/kg
Carbon Disulfide	ND	ND	ND				1 mg/kg
Carbon Tetrachloride	ND	ND	ND				1 mg/kg
Chlorobenzene	ND	ND	ND				1 mg/kg
Esters	ND	ND	ND				1 mg/kg
Fatty Acid	ND	ND	ND				1 mg/kg
Gasoline	ND	ND	ND				1 mg/kg
Dichloro Benzene	ND	ND	ND				1 mg/kg
Isopropyl Ethanol	ND	ND	ND				1 mg/kg
Isyl Acetate	ND	ND	ND				1 mg/kg
Isyl Benzene	ND	ND	ND				1 mg/kg
Isyl Ether	ND	ND	ND				1 mg/kg
Isobutanol	ND	ND	ND				1 mg/kg
Isopropanol	ND	ND	ND				1 mg/kg
Isobutylene Chloride	ND	ND	ND				1 mg/kg

ND=Not Detected

Certified by:

*Carl A. Anderson*

CHEM-CLEAR/CHGO  
CHEM CLEAR/CHGO/IL  
81 312 868 5408

TEL No. 1 312 868 5408

ILL NO. 312 868 5408

Dec 22, 88 11:05 P.04

P.04


# TENCO LABORATORIES

BPM INDUSTRIES  
1150 Junction Avenue - Schererville, Indiana 46375  
1-219-322-2560 • 1-800-428-3311

Page 2 of 2

REPORT TO:  
Jean Millard  
Chem Clear  
1600 167th St  
Calumet City IL 60409

EPA METHOD



Date: 12/21/88  
Recd: 12/19/88  
WO #: 21-0718

Laboratory Samp ID No.:	2987-9	2988-9	2989-9				
DESCRIPTION: —>	CC # 2 South towards parking lot	CC # 3 Center	CC # 1 North End				DETECTION LIMIT
Less otherwise noted; results in parts per million - ppm PARAMETERS: ↓	12/14/88	12/14/88	12/14/88				
Methyl Ethyl Ketone	ND	ND	ND				1 mg/kg
Methyl Isobutyl Ketone	ND	1.79	3.34				1 mg/kg
Nitrobenzene	ND	ND	ND				1 mg/kg
2-Nitro Propane	ND	ND	ND				1 mg/kg
Pyridine	ND	ND	ND				1 mg/kg
Tetrachloroethylene	ND	ND	ND				1 mg/kg
Toluene	289.	3.52	35.1				1 mg/kg
Trichloroethylene	ND	ND	ND				1 mg/kg
1,1-Trichloroethane	ND	ND	ND				1 mg/kg
1,1,2-Trichloroethane	ND	ND	ND				1 mg/kg
1,1,1-Trichloro- 1,2,2-Trifluoroethane	ND	ND	ND				1 mg/kg
Trichlorofluoroethane:	ND	ND	ND				1 mg/kg
Xylene	2.08	ND	6.68				1 mg/kg

ND=Not Detected

Certified by:


*[Signature]*

CHEM-CLEAR/CHG0  
CHEM CLEAR/CHGU/PL

TEL No. 1 312 868 5408  
TEL No. 1 312 868 5408  
512 840 5581  
Dec 22, 88 11:05 P.03  
Dec 22, 88 10:30 P.04/04

**BPM INDUSTRIES**  
1150 Junction Avenue - Schererville, Indiana 46375  
1-219-322-2560 • 1-800-428-3311

Tom Simpson  
Chem Clear  
1600 167th St.  
Calumet City, IL 60409




40 #: 21-0718

[illegible]

Certified true

**1-219-322-2560 • 1-800-428-3311**

Cathy Ortiz  
Chem Clear  
11800 S. Stony Island Avenue  
Chicago, IL 60617



100 #: 21-0847

**3374-9**

PARAMETERS: ✓

#1 Down - 84"  
#2 Down - 42"  
#3 Down - 60"

#4 Down - 48"  
#5 Down - 48"  
#6 Down - 54"


maximum  
concentration  
(metals only)

**\*\* Allowa' 9 Range**

certified by: E. J. P. L.

**1-219-322-2560 • 1-800-428-3311**

Gary Freeman  
Chem Clear  
1600 167th St.  
Calumet City, IL 60409



WO #: 19-1472

Laboratory Smp ID No.:		6073-7 Croda - Soil Sample					
DESCRIPTION: —> less otherwise noted; units in parts per million - ppm] PARAMETERS: ↓		Croda Ink					maximum concentrations (metals only)
	AS RECEIVED	TOTAL	REACTIVE		TOTAL	EP TOXICITY	
FLASHPOINT-(140°F)	>200°F			SILVER	24.4	<0.005	5.0 ppm
Percent Acidity				ARSENIC	<0.100	<0.010	5.0 ppm
Percent Alkalinity	0.56			BARIUM	9991.0	0.311	100.0 ppm
pH (2-12.5**)	7.5			CADMIUM	156.0	0.300	1.0 ppm
Percent Total Solids	65.16			CHROMIUM***	11.6	0.021	5.0 ppm
CHLORIDE	<0.05		<0.05	MERCURY	<0.010	0.0018	0.2 ppm
CYANIDE	19.606		<0.20	LEAD	8148.0	0.254	5.0 ppm
PHENOL	1.68			SELENIUM	<0.100	<0.010	1.0 ppm
COLOUR	2500						
TOX	<0.05						
COLOR:	Green						
SPECIFIC GRAVITY	1.091						
FREE LIQUID	None Present						
COMPATIBILITY	No Reaction						
				*** Total			

allowable range

## APPENDIX E

### RCRA CHARACTERIZATION OF STOCKPILED SOIL FROM UST EXCAVATION

# Quality Analytical Laboratories, Inc.

"Precision, Accuracy and Service"

Warzyn Engineers, Inc.  
ATTN: James W. Wink  
1 Pierce Place  
Itasca, IL 60143

Job #:1-631  
Date: 6/12/1989

Sampling Date: unknown  
Analyses Date: 6/6-12/1989  
Technique/Method: The samples were analyzed as per USEPA SW-846 methods 8010 and 8020

Identification: Two samples identified as:

Project Name: Croda Inks Corp  
Project #: 40045.03  
Location: Niles, IL

All results expressed in ug/kg (ppb)

Results: Soil Pile #1

Parameter	method detection Limit	Analysis
Chloromethane	5	BDL
Bromomethane	5	BDL
Vinyl Chloride	5	BDL
Chloroethane	5	BDL
Methylene Chloride	1	BDL
Trichlorofluoromethane	1	BDL
Acetone	75	BDL
Carbon Disulfide	1	BDL
Dibromomethane	1	BDL
Dichlorofluoromethane	1	BDL
Ethanol	25	BDL
Iodomethane	1	BDL
1,1-Dichloroethane	1	BDL
1,1-Dichloroethene	1	BDL
trans-1,2-Dichloroethene	1	BDL
Trichloromethane (Chloroform)	1	BDL
1,2-Dichloroethane	1	BDL
1,1,1-Trichloroethane	1	BDL
1,2,3-Trichloropropane	1	BDL
Vinyl Acetate	25	BDL
Tetrachloromethane(Carbon Tet)	1	BDL
Bromodichloromethane	1	BDL
1,2-Dichloropropane	1	BDL
Tribromomethane (Bromoform)	1	BDL
4-Methyl-2-pentanone (MIBK)	25	BDL
trans-1,3-Dichloropropene	1	BDL
2-Chlorovinyl Ether	1	BDL
Trichloroethene	1	BDL
Benzene	1	BDL
Dibromochloromethane	1	BDL
1,1,2-Trichloroethane	1	BDL
cis-1,3-Dichloropropene	1	BDL

**Quality Analytical Laboratories, Inc.**  
*"Precision, Accuracy and Service"*

1-631 Page 2

Parameter	method detection Limit	Analysis
trans-1,3-Dichloropropene	1	BDL
1,1,2,2-Tetrachloroethane	1	BDL
Tetrachloroethene	1	BDL
Methylbenzene (Toluene)	1	451
Ethyl Benzene	1	BDL
Xylenes (Total)	3	44
2-Hexanone	10	BDL
Acrolien	1	BDL
Acrylonitrile	1	BDL
1,4-Dichloro-2-butane	1	BDL
Ethyl Methacrylate	1	BDL
Chlorobenzene	1	BDL
2-Butanone (Methyl Ethyl Ketone)	50	BDL
Styrene	1	BDL

Note: Bromofluorobenzene present

Results: Soil Pile #2

Parameter	method detection Limit	Analysis
Chloromethane	5	BDL
Bromomethane	5	BDL
Vinyl Chloride	5	BDL
Chloroethane	5	BDL
Methylene Chloride	1	BDL
Trichlorofluoromethane	1	BDL
Acetone	75	BDL
Carbon Disulfide	1	BDL
Dibromomethane	1	BDL
Dichlorofluoromethane	1	BDL
Ethanol	25	BDL
Iodomethane	1	BDL
1,1-Dichloroethane	1	BDL
1,1-Dichloroethene	1	BDL
trans-1,2-Dichloroethene	1	BDL
Trichloromethane (Chloroform)	1	BDL
1,2-Dichloroethane	1	BDL
1,1,1-Trichloroethane	1	BDL
1,2,3-Trichloropropane	1	BDL
Vinyl Acetate	25	BDL
Tetrachloromethane(Carbon Tet)	1	BDL
Bromodichloromethane	1	BDL
1,2-Dichloropropane	1	BDL
Tribromomethane (Bromoform)	1	BDL
4-Methyl-2-pentanone (MIBK)	25	BDL
trans-1,3-Dichloropropene	1	BDL
2-Chlorovinyl Ether	1	BDL
Trichloroethene	1	BDL
Benzene	1	BDL




1-631 Page 3

Parameter	method detection Limit	Analysis
Dibromochloromethane	1	BDL
1,1,2-Trichloroethane	1	BDL
cis-1,3-Dichloropropene	1	BDL
trans-1,3-Dichloropropene	1	BDL
1,1,2,2-Tetrachloroethane	1	BDL
Tetrachloroethene	1	BDL
Methylbenzene (Toluene)	1	BDL
Ethyl Benzene	1	BDL
Xylenes (Total)	3	15
2-Hexanone	10	BDL
Acrolien	1	BDL
Acrylonitrile	1	BDL
1,4-Dichloro-2-butane	1	BDL
Ethyl Methacrylate	1	BDL
Chlorobenzene	1	BDL
2-Butanone (Methyl Ethyl Ketone)	50	BDL
Styrene	1	BDL

Note: Bromofluorobenzene present

(BDL = Below Detection Limit)

Respectfully Submitted,



William F. Eberhardt  
Lab Director  
Quality Analytical Labs, Inc.

**"Precision, Accuracy and Service"**

Warzyn Engineers, Inc.  
ATTN: James W. Wink  
1 Pierce Place  
Itasca, IL 60143

Job #: 1-630  
Date: 6/13/1989

Sampling Date: unknown  
Analyses Date: 6/6-12/1989  
Technique/Method: The samples were analyzed as per USEPA  
SW-846

Identification: Two samples identified as:

Project Name: Croda Inks Corp  
Project #: 40045.03  
Location: Niles, IL

Results: Soil Pile #1

	<u>Total Metals</u>	<u>E.P. Toxicity Metals</u>
Cu	NA	NA
Cd	NA	<1.0mg/l
Cr	NA	<1.0mg/l
Pb	NA	<1.0mg/l
Ag	NA	<1.0mg/l
Se	NA	<1.0mg/l
As	NA	<1.0mg/l
Hg	NA	<0.01mg/l
Zn	NA	NA
Ni	NA	NA
Fe	NA	NA
Ba	NA	<50.0mg/l

CN (Tot) ..... <1.0mg/kg  
Sulfide (Tot) .. <1.0mg/kg  
Chlorine ..... NA  
Flashpoint ..... >140 degrees F (Pensky-Martens C.C.)  
Paint Filter ... pass  
Total Solids ... NA  
PH ..... 8.2

**RECEIVED**

**JUN 19 1989**

**WARZYN-ILLINOIS**

Results: Soil Pile #2

Total Metals		E.P. Toxicity Metals	
-----		-----	
Cu	NA		NA
Cd	NA		<1.0mg/l
Cr	NA		<1.0mg/l
Pb	NA		<1.0mg/l
Ag	NA		<1.0mg/l
Se	NA		<1.0mg/l
As	NA		<1.0mg/l
Hg	NA		<0.01mg/l
Zn	NA		NA
Ni	NA		NA
Fe	NA		NA
Ba	NA		<50.0mg/l
CN (Tot)	<1.0mg/kg		
Sulfide (Tot)	<1.0mg/kg		
Chlorine	NA		
Flashpoint	>140 degrees F (Pensky-Martens C.C.)		
Paint Filter	pass		
Total Solids	NA		
pH	8.4		

NA = Not Applicable

Respectfully Submitted,



Maureen M. Gibbons  
Lab Manager  
Quality Analytical Labs, Inc.

# PDC Laboratories, Inc.

4349 Southport Rd. • Peoria, IL 61615

309 6-5-4803

CLIENT Warzyn Engineering

DATE RECEIVED 06-28-89

DATE OF REPORT 06-29-89

SAMPLE DESCRIPTION Stockpile #1

P.O. NUMBER \_\_\_\_\_ James Wink

LAB NUMBER 906558

[illegible]

John R. LoPresti (STC)  
Laboratory Manager  
PDC Laboratories, Inc.

Subsidiary of PDC Technical

John P. Dennis (STE)  
Quality Assurance Officer  
PDC Laboratories, Inc.

APPENDIX F  
CLOSURE CERTIFICATION DOCUMENTS

Attachment 5


This statement is to be completed and attached to each of the 4 copies of the closure plan. At least one of the copies must contain original signatures.

Closure Plan  
Certification Statement

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

ILD002293124  
USEPA ID Number

Croda Inks Croporation  
Facility Name

  
Signature of Owner/Operator

Lawrence L. Rokosz  
Director of Finance and Administration  
Name and Title

October 5, 1989  
Date

Attachment 6

This statement is to be completed by both the responsible officer and by the registered professional engineer upon completion of closure. Submit three copies of this certification, including at least one copy with original signatures.

Closure Certification Statement

The hazardous waste management unit(s) at the facility described in this document has (have) been closed in accordance with the specifications in the approved closure plan. I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

If this is the closure of a unit which is subject to post-closure care requirements, the Owner/Operator hereby certifies that he has recorded the notation specified in 35 Ill. Adm. Code, Section 725.219(b)(1) as amended March 24, 1987.

\_\_\_\_\_  
USEPA ID Number

\_\_\_\_\_  
Facility Name

\_\_\_\_\_  
Signature of Owner/Operator

\_\_\_\_\_  
Name and Title

\_\_\_\_\_  
Signature of Registered P.E.

\_\_\_\_\_  
Name of Registered P.E. and Illinois  
Registration Number

\_\_\_\_\_  
Date

(P.E. Seal)

APPENDIX G  
ISWS WELL LOGS



GEOLOGICAL AND WATER SURVEYS WELL RECORD  
Completed 6-19-73

10. Property owner Richard Weise Well No. \_\_\_\_\_  
Address 6120 Lincoln Ave. Morton Grove.  
Driller DuPage Pump, Inc License No. 92-147  
11. Permit No. 22751 Date 4-20-73  
12. Water from Limestone 13. County Cook

at depth \_\_\_\_\_ to \_\_\_\_\_ ft. Sec. 19  
14. Screen: Diam. \_\_\_\_\_ in. Twp. 41 N  
Length: \_\_\_\_\_ ft. Slot \_\_\_\_\_ Rge. 13 E  
Elev. \_\_\_\_\_


15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
5	Steel 14.98	0	112

SHOW  
LOCATION IN  
SECTION PLAT  
Lot 10 Schmitz  
Morton Grove  
(Permit)

16. Size Hole below casing: 5 in.  
17. Static level \_\_\_\_\_ ft. below casing top which is 3 ft.  
above ground level. Pumping level 110 ft. when pumping at 10  
gpm for 2 hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Drift	112	112
Limestone	63	175

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Owner Heoman DATE 6-19-73

4386

HOWE MORTON GROVE TOWNSHIP  
 COMPANY Gray Well Drilling Co.  
 JOHN PEEHMAN PRES.

AUTHORITY  
 ELEVATION 628' (66.000)  
 COLLECTOR Thwaites DATE DRILLED  
 CONFIDENTIAL Aug. 1, 1926-April 15, 1927

No.	STRATA	Thickness		Feet	In.
		Feet	In.		
	DRIFT				
	Drift, no record	65			
	NIAGARA				
	Dolomite, light gray	10			
	Dolomite, black, bl- tuminous, light gray, and pink; shale, blue, dolomitic, all broken	30		100	
	No samples	20		120	
	Like 75-105; shoe	10		130	
	Dolomite, white; chert white; 140' of 20"				
	drive pipe	50		180	
	Dolomite, light gray	20		200	
	Dolomite, light gray; chert, white	10		210	
	Dolomite, light gray	70		280	
	Shale, blue, dolomitic	10		290	
	Dolomite, light gray some	120		410	
	RICHMOND				
	Shale, blue, dolomitic	105		520	
	GALENA-BLACK RIVER				
	Dolomite, gray	20		540	
	No sample	10		550	
	Dolomite, gray; 568' of 19" hole; 568' of 1 1/2"	210		760	
	g.w.i. pipe seal set				
	Dolomite, gray and blue	20		780	
	Dolomite, gray	30		810	
	Dolomite, gray, some blue	35		845	

County Cook  
 Y-DRILL RECORD

SHEET		41N P 15E S 20		WELL NO.	
COMPANY					
No.	STRATA	Thickness		Depth	
		Feet	In.	Feet	In.
	ST. PETER				
	Sandstone, fine to medium white	75		920	
	Sandstone, medium, white	90		1010	
	552' of 15 1/2" hole				
	580' of 12 1/2" 50 lb.				
	G.W. 1. pipe	55		1065	
	Conglomerate-pebbles white chert in coarse gray sandstone	25		1090	
	Shale, red and green; dolomite, gray	10		1100	
	Chert, white; shale, red and green; dolomite, gray--conglomerate	30		1130	
	1120' shes				
	Sandstone, coarse, pink; shale, red and green; 90' of 12 1/2" hole	70		1200	
	104' of 10" liner			1210	
	No sample	10		1210	
	Shale, gray	20		1230	
	Sandstone, fine, gray, dolomitic, glauconitic	50		1280	
	MAZOMANIE				
	Sandstone, fine, light gray, dolomitic, glauconitic	10		1270	
	Sandstone, coarse, white	10		1280	
	Sandstone, fine, gray, dolomitic	10		1290	
	THRESBACH				
	Sandstone, medium to fine white, slightly dolomitic	50		1330	
	Sandstone, coarse to medium, white	100		1430	
County COOK		Index No. 1000-20			
T-DRILL RECORD					
(67120-2M-8-87)					

STRATA		Thickness		Depth
		Feet	In.	Feet
Sandstone, fine to very fine, light gray		20		1440
Sandstone, coarse to fine white		20		1460
EAU CLAIRE				
Sandstone, fine, gray and pink, dolomitic; shale, gray		20		1480
Shale, gray with layers of sandstone like 1460-1480		120		1600
Sandstone, very fine, gray, very dolomitic, glauconitic; some gray shale		120		1720
Sandstone, fine, light gray		40		1760
Sandstone, fine, light gray, dolomitic		30		1790
Sandstone, fine to very fine, light gray		50		1840
Sandstone, medium-fine, light gray		20		1860
Sandstone, very fine, gray		80		1940
Sandstone, medium to fine, light gray, pink		26		1966
MOUNT SIMON from 1790-1966				
Plugged to depth 1960' at 1122'				
See Sample Study by C.E. Needham in file.				
County COOK				
Drill Record				
Date 12-1-17				

TOWN **Marion Township**  
 COMPANY **Gray Well Drilling Co.**  
 FARM **Packman Bros.** No. **41**  
 AUTHORITY **Geo. Otto**  
 ELEVATION **699'** (Geo. Otto)  
 COLLECTOR **Thurston** DATE DRILLED  
 CONFIDENTIAL  
**Aug. 1, 1928-April 18, 1927**

Map No. **10**  
 R. **12 E.**

T	Sec.
41	20.25
N.	

No.	STRATA	Thickness		Depth	
		Feet	In.	Feet	In.
	<b>DRIFT</b>				
	Drift, no record	65		65	
	<b>NIAGARA</b>				
	Dolomite, light gray	10		75	
	Dolomite, black, bitum- inous, light gray, and pink; shale, blue, calc- mitic, all broken	30		105	
	No samples	20		125	
	Like 75-105; shes	10		135	
	Dolomite, white; short, white; 140° at 20° drive pipe	20		155	
	Dolomite, light gray	20		175	
	Dolomite, light gray; short, white	10		185	
	Dolomite, light gray	70		255	
	Shale, blue, dolomitic	10		265	
	Dolomite, light gray, some white chert	120		385	
	<b>RICHMOND</b>				
	Shale, blue, dolomitic	105		490	
	<b>GALENA-BLACK RIVER</b>				
	Dolomite, gray	20		510	
	No sample	10		520	
	Dolomite, gray; 540° at 15° hole; 540° at 15 1/2°	210		730	
	G.U.I. pipe coal 540°	20		750	
	Dolomite, gray and blue	20		770	
	Dolomite, gray	20		790	

County **COOK**  
 T.-DRILL RECORD

**CHAS. D. MAYLE** Index No. **1000.20**

SHEET

COMPANY

FARM

Foothills Farm

HOLE NO.

HOLE NO.

No.	STRATA	Thickness		Depth	
		Feet	In.	Feet	In.
	Dolomite, gray, some blue	25		945	
	ST. PETER				
	Sandstone, fine to medium, white	75		1020	
	Sandstone, medium, white	90		1110	
	55' or 12 1/2" hole				
	500' or 12 1/2" 50 lb.				
	6" i. pipe				
	Sandstone, fine to medium, white	65		1175	
	Conglomerate-pebbles white				
	chert in coarse gray sandstone	25		1200	
	Shale, red and green;				
	dolomite, gray	10		1210	
	Chert, white; shale, red and green; dolomite, gray--conglomerate?				
	120' shoe	50		1260	
	Sandstone, coarse, pink; shale, red and green;				
	90' or 12 1/2" hole	70		1330	
	104' or 12" liner 1210'				
	No sample	10		1340	
	Shale, gray	50		1390	
	MAXIMIANE				
	Sandstone, fine, gray;				
	dolomite, greenish	50		1440	
	Sandstone, fine, light gray, dolomite, siliceous	10		1450	
	Sandstone, coarse, white	10		1460	
	Sandstone, fine, gray;				
	dolomite	10		1470	
	DEERBACH				
	Sandstone, medium to fine,				

County

COOK

T-DRILL RECORD

(6772-6M-11-51)

Index No.

1000.20

SHEET  
COMPANY  
FARM

Producers, Inc.

HOLE NO.

HOLE NO.

No.	STRATA	Thickness		Depth	
		Feet	In.	Feet	In.
	white, slightly dolomitic	20		1280	
	Sandstone, coarse to medium white	100		1380	
	740' of 10" hole				
	Sandstone, fine to very fine, light gray	20		1400	
	Sandstone, coarse to fine, white	20		1420	
	BAU CLAIRE				
	Sandstone, fine, gray and pink, dolomitic; shale, gray	20		1440	
	Shale, gray with layers of sandstone like 1420-1440	120		1560	
	Sandstone, very fine, gray, very dolomitic, ammonitic; some gray shale	120		1680	
	Sandstone, fine, light gray	40		1720	
	Sandstone, fine, light gray, dolomitic	20		1740	
	MOUNT SIMON from 1720-1900				
	Sandstone, fine to very fine, light gray	20		1760	
	Sandstone, medium-fine, light gray	20		1780	
	Sandstone, very fine, gray	20		1800	
	Sandstone, medium to fine, light gray, pink	20		1820	
	plugged to depth 1840'				
	in 1928				
	See Sample Study and description of insoluble residues by C.E. Needham in file.				

County COOK

T. DRILL RECORD  
(67728-5M-11-31)

Index No.

1020, 20

TOWNSHIP Morton Grove TOWNSHIP  
 COMPANY Town well (F.M. Gray). 1  
 FARM Morton Grove No.  
 AUTHORITY  
 ELEVATION 627' T. M. - Ground-  
 COLLECTOR water Section N  
 CONFIDENTIAL DATE DRILLED 1914

Mo. 10  
 R. 13 E


Sec.  
 20.2F  
 77 1/2 Cor.

1600' N line, 700' W line of NW

No.	STRATA	Thickness		Depth	
		Feet	In.	Feet	In.
	Drift	128		128	
	Limestone	162		290	
	Shale	25		315	
	Shale and lime	30		345	
	Shale, sticky	165		510	
	Trenton and Galena lime- stone	335		845	
	Shale, sandy	242		1087	
	Marl, red	8		1095	
	Lime marl, hard, streaks	11		1106	
	Marl streaks, shelly lime	14		1120	
	Lime marl and shale	22		1142	
	Magnesian limestone	48		1190	
	Marl, red	22		1212	
	Shale, sandy	63		1275	
	St. Peters sandstone	87		1462	TD

This well was originally drilled with a 4-inch bottom, later it was reamed out to 8-inch diameter to the 1462 feet in depth, lined and sealed with 6 inch pipe to cut off the upper levels. This 6 inch pipe extends to about 232 feet from the bottom. Ordinarily this 232 ft. of exposed St. Peters sandstone should develop a flow of over 300 gallons per minute, but the pump after working an hour begins to churn and the water level drops below the suction. I am of the opinion that the 232 ft. is not delivering enough water

County COOK  
 -DRILL RECORD

Index No. 2020.2F  
 20-41N-13E




20

20-41N-153  
1020.2F

From Niles Center Township Niles  
Company Snelten Brothers  
Pore Schladt, Albert  
Authority Snelten Brothers  
Elevation 624 Topo. Map

Map No. 10  
R. 13E

No.  
T. 41  
N



Sec. 29

Collector  
Confidential

Date Drilled Feb. 1940

*200' N. of Grass Point Rd. (also known as Harts Rd.) and 100' W. of  
half blk. west of Railroad Ave. (also known as Harts Ave.)*

No.	Strata	Thickness		Depth	
		Feet	In.	Feet	In.
	Clay, yellow, sandy	18		18	
	Clay, blue	69		87	
	Sand	7		94	
	Rock	85		179	
	Cased with 4" to 84'				
	Water level from surface 40'				
	Capacity 5 g.p.m.				
	Water lowered to 95' in 1 hr.				
	Total length of test run 1 hr.				
	NO ENVELOPE				

COUNTY Cook  
DRILL RECORD

INDEX NO. 1029

ILLINOIS

ILLINOIS GEOLOGICAL SURVEY, URBANA

29-41N-13E



Sec.  
32

**Date Drilled**

~~200' S line 3100' W line of Section~~

No.	Strata	Thickness		Depth	
		Feet	In.	Feet	In.
	Yellow clay and sand	12		12	
	Blue clay and little gravel	26		38	
	Hard clay, sand and gravel	3		41	
	Soft clay, sand and gravel;	9		50	
	Blue clay, sand and gravel	6		56	
	Hard pan, sand and gravel	25		81	
	Gravel	5		86	
	Limestone	44		130	
	Water level 13'6"				
	Drawdown <sup>5</sup> at 30 g.p.m.				
	Total depth 130'				
	Depth in rock 44'				
	NO ENVELOPE				

COUNTY Cook

SS 1945

32-41 N-182

(40430-20M)

ILLINOIS GEOLOGICAL SURVEY, URBANA

(3-43) ~~SECRET~~

VOLATILE ORGANIC COMPOUND ANALYTICAL RESULTS  
CRODA INKS CORPORATION  
MILES, ILLINOIS

PARAMETER	SB01-1	SB01-2	SB01-3	SB02-1	SB02-2	SB02-3	SB03-1	SB03-2
METHYLENE CHLORIDE	(B) 23	(B) 30	(B) 60	(B) 20	(B) 28	(B) 53	(B) 23	(B) 43
ACETONE	(B) 40	(B) 10	(B) 18	(B) 27	BDL	(B) 64	BDL	(B) 33
TRICHLOROETHENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
TOLUENE	BDL	BDL	7	BDL	BDL	BDL	BDL	BDL
TICS	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
TOTAL VOLATILES	0.0	0.0	7.0	0.0	0.0	0.0	0.0	0.0

NOTES: 1. RESULTS ARE REPORTED IN MICROGRAMS PER KILOGRAM (UG/KG)

2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 1 TO 3 FEET ETC.

3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 3.5 TO 5.5 FEET ETC.

4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 6 TO 8 FEET ETC.

5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 8.5 TO 10.5 FEET ETC.

6. BDL STANDS FOR "BELOW DETECTION LIMIT"

7. J INDICATES AN ESTIMATED VALUE

8. B INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE

VOLATILE ORGANIC COMPOUND ANALYTICAL RESULTS (CONT'D)  
CRODA INKS CORPORATION  
NILES, ILLINOIS

PARAMETER	SB04-1	SB04-2	SB04-3	SB05-1	SB05-2	SB05-4	SB06-1	SB06-2
METHYLENE CHLORIDE	(B) 50	(B) 55	(B) 130	(B) 30	(B) 21	(B) 92	(B) 31	(B) 34
ACETONE	BDL	(B) 7	(B) 46	(B) 54	BDL	(B) 38	(B) 10	(B) 6
TRICHLOROETHENE	BDL	BDL	4	BDL	BDL	BDL	BDL	BDL
TOLUENE	BDL	BDL	26	9	BDL	8	(J) 3	BDL
TICS	BDL	BDL	7.5	BDL	BDL	BDL	11	BDL
TOTAL VOLATILES	0.0	0.0	37.5	9.0	0.0	8.0	14.0	0.0

NOTES: 1. RESULTS ARE REPORTED IN MICROGRAMS PER KILOGRAM (UG/KG)

2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 1 TO 3 FEET ETC.

3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 3.5 TO 5.5 FEET ETC.

4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 6 TO 8 FEET ETC.

5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 8.5 TO 10.5 FEET ETC.

6. BDL STANDS FOR "BELOW DETECTION LIMIT"

7. J INDICATES AN ESTIMATED VALUE

8. B INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE

VOLATILE ORGANIC COMPOUND ANALYTICAL RESULTS (CONT'D)  
CRODA INKS CORPORATION  
NILES, ILLINOIS

PARAMETER	SB07-1	SB07-2	SB08-1	SB08-2	SB09-1	SB09-2	SB10-1	SB10-2	SB11-1	SB11-2	SB11-4
METHYLENE CHLORIDE	(B) 24	(B) 110	(B) 30	(B) 120	(B) 31	(B) 29	(B) 19	(B) 32	(B) 23	(B) 28	(B) 44
ACETONE	(B) 18	(B) 17	(B) 14	(B) 38	(B) 26	(B) 6	BDL	(B) 26	BDL	(B) 17	(B) 14
TRICHLOROETHENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
TOLUENE	(J) 2	(J) 3	(J) 2	(J) 1	60	(J) 5	BDL	BDL	BDL	BDL	BDL
TICS	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
TOTAL VOLATILES	2.0	3.0	2.0	1.0	60.0	5.0	0.0	0.0	0.0	0.0	0.0

NOTES: 1. RESULTS ARE REPORTED IN MICROGRAMS PER KILOGRAM (UG/KG)

2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 1 TO 3 FEET ETC.

3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 3.5 TO 5.5 FEET ETC.

4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 6 TO 8 FEET ETC.

5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 8.5 TO 10.5 FEET ETC.

6. BDL STANDS FOR "BELOW DETECTION LIMIT"

7. J INDICATES AN ESTIMATED VALUE

8. 0 INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE

VOLATILE ORGANIC COMPOUND ANALYTICAL RESULTS (CONT'D)  
CRODA INKS CORPORATION  
NILES, ILLINOIS

PARAMETER	SB12-1	SB12-2	SB12-3	SB13-1	SB13-2	SB14-1	SB14-2	SB14-3	SB15-1	SB15-2
METHYLENE CHLORIDE	(B) 28	(B) 25	(B) 25	(B) 40	(B) 20	(B) 17	(B) 16	(B) 19	(B) 16	(B) 26
ACETONE	BDL	BDL	(B) 11	73	(B) 9	(B) 19	BDL	BDL	(B) 6	(B) 23
TRICHLOROETHENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
TOLUENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	(J) 5	(J) 4	BDL
TICS	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
TOTAL VOLATILES	0.0	0.0	0.0	0.0	0.0	0.0	0.0	5.0	4.0	0.0

- NOTES: 1. RESULTS ARE REPORTED IN MICROGRAMS PER KILOGRAM (UG/KG)  
2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 1 TO 3 FEET ETC.  
3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 3.5 TO 5.5 FEET ETC.  
4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 6 TO 8 FEET ETC.  
5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 8.5 TO 10.5 FEET ETC.  
6. BDL STANDS FOR "BELOW DETECTION LIMIT"  
7. J INDICATES AN ESTIMATED VALUE  
8. B INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE



VOLATILE ORGANIC COMPOUND ANALYTICAL RESULTS (CONT'D)  
CRODA INKS CORPORATION  
NILES, ILLINOIS

PARAMETER	SB16-1	SB16-2	SB16-3	SB16-4
METHYLENE CHLORIDE	(B) 17	(B) 31	(B) 43	(B) 30
ACETONE	(B) 5	(B) 13	(B) 9	(B) 6
TRICHLOROETHENE	BDL	BDL	BDL	8
TOLUENE	BDL	BDL	20	BDL
TICS	BDL	BDL	BDL	BDL
TOTAL VOLATILES	0.0	0.0	20.0	8.0

NOTES: 1. RESULTS ARE REPORTED IN MICROGRAMS PER KILOGRAM (UG/KG)

2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 1 TO 3 FEET ETC.

3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 3.5 TO 5.5 FEET ETC.

4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 6 TO 8 FEET ETC.

5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 8.5 TO 10.5 FEET ETC.

6. BDL STANDS FOR "BELOW DETECTION LIMIT"

7. J INDICATES AN ESTIMATED VALUE

8. B INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE

POLYNUCLEAR AROMATIC HYDROCARBON ANALYTICAL RESULTS  
CRODA INKS CORPORATION  
NILES, ILLINOIS

PARAMETER	SB01-1	SB01-2	SB01-3	SB02-1	SB02-2	SB02-3	SB03-1	SB03-2
PHENANTHRENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
FLUORANTHENE	BDL	11	BDL	BDL	BDL	BDL	BDL	BDL
PYRENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
BENZO(A)ANTHRACENE	BDL	4	BDL	BDL	BDL	BDL	BDL	BDL
BENZO(B)FLUORANTHENE	BDL	4.3	BDL	BDL	BDL	BDL	BDL	BDL
BENZO(K)FLUORANTHENE	BDL	2.5	BDL	BDL	BDL	BDL	BDL	BDL
BENZO(A)PYRENE	BDL	4	BDL	BDL	BDL	BDL	BDL	BDL
BENZO(G,H,I)PERYLENE	BDL	BDL	4.8	BDL	BDL	4.7	BDL	BDL
IDENO(1,2,3)PYRENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
TOTAL PNA'S	0.0	25.8	4.8	0.0	0.0	4.7	0.0	0.8

- NOTES: 1. RESULTS ARE REPORTED IN MICROGRAMS PER KILOGRAM (UG/KG)  
2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 1 TO 3 FEET ETC.  
3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 3.5 TO 5.5 FEET ETC.  
4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 6 TO 8 FEET ETC.  
5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 8.5 TO 10.5 FEET ETC.  
6. BDL STANDS FOR "BELOW DETECTION LIMIT"  
7. J INDICATES AN ESTIMATED VALUE  
8. B INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE

POLYNUCLEAR AROMATIC HYDROCARBON ANALYTICAL RESULTS (CONT'D)  
CRODA INKS CORPORATION  
NILES, ILLINOIS

PARAMETER	SB04-1	SB04-2	SB04-3	SB05-1	SB05-2	SB05-4	SB06-1	SB06-2
PHEANANTHRENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
FLUORANTHENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	4.4
PYRENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
BENZO(A)ANTHRACENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	2
BENZO(B)FLUORANTHENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
BENZO(K)FLUORANTHENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
BENZO(A)PYRENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	2.3
BENZO(G,H,I)PERYLENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	5.4
IDENOC(1,2,3)PYRENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
TOTAL PNA'S	0.0	0.0	0.0	0.0	0.0	0.0	0.0	14.1

NOTES: 1. RESULTS ARE REPORTED IN MICROGRAMS PER KILOGRAM (UG/KG)

2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 1 TO 3 FEET ETC.

3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 3.5 TO 5.5 FEET ETC.

4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 6 TO 8 FEET ETC.

5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 8.5 TO 10.5 FEET ETC.

6. BDL STANDS FOR "BELOW DETECTION LIMIT"

7. J INDICATES AN ESTIMATED VALUE

8. B INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE

POLYNUCLEAR AROMATIC HYDROCARBON ANALYTICAL RESULTS (CONT'D)  
CRODA INKS CORPORATION  
NILES, ILLINOIS

PARAMETER	SB07-1	SB07-2	SB08-1	SB08-2	SB09-1	SB09-2	SB10-1	SB10-2	SB11-1	SB11-2	SB11-4
PHENANTHRENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
FLUORANTHRENE	5.8	13	BDL	BDL	BDL	BDL	BDL	BDL	3.4	BDL	BDL
PYRENE	BDL	BDL	2.4	BDL	BDL	BDL	BDL	BDL	BDL	BDL	36
BENZO(A)ANTHRACENE	2.1	3.2	1.5	BDL	BDL	BDL	BDL	BDL	1.4	BDL	BDL
BENZO(B)FLUORANTHENE	2.2	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
BENZO(K)FLUORANTHENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
BENZO(A)PYRENE	1.7	2.8	BDL	BDL	BDL	BDL	BDL	BDL	1.3	BDL	BDL
BENZO(G,H,I)PERYLENE	BDL	BDL	BDL	BDL	BDL	6.9	BDL	BDL	BDL	BDL	BDL
IDENO(1,2,3)PYRENE	BDL	BDL	BDL	BDL	BDL	12	BDL	BDL	BDL	BDL	BDL
TOTAL PHA'S	11.8	19.0	3.9	0.0	0.0	18.9	0.0	0.0	6.1	0.0	36.0

NOTES: 1. RESULTS ARE REPORTED IN MICROGRAMS PER KILOGRAM (UG/KG)

2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 1 TO 3 FEET ETC.

3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 3.5 TO 5.5 FEET ETC.

4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 6 TO 8 FEET ETC.

5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 8.5 TO 10.5 FEET ETC.

6. BDL STANDS FOR "BELOW DETECTION LIMIT"

7. J INDICATES AN ESTIMATED VALUE

8. B INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE

POLYNUCLEAR AROMATIC HYDROCARBON ANALYTICAL RESULTS (CONT'D)  
CRODA INKS CORPORATION  
NILES, ILLINOIS

PARAMETER	SB12-1	SB12-2	SB12-3	SB13-1	SB13-2	SB14-1	SB14-2	SB14-3	SB15-1	SB15-2
PHENANTHRENE	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
FLUORANTHENE	BDL	BDL	BDL	140	BDL	3.2	32	BDL	4.1	BDL
PYRENE	BDL	BDL	BDL	110	BDL	BDL	40	BDL	BDL	BDL
BENZO(A)ANTHRACENE	BDL	BDL	BDL	47	BDL	1.4	12	BDL	1.4	BDL
BENZO(B)FLUORANTHENE	BDL	BDL	BDL	40	BDL	2.1	16	4	BDL	BDL
BENZO(K)FLUORANTHENE	BDL	BDL	BDL	25	BDL	BDL	9.4	BDL	BDL	BDL
BENZO(A)PYRENE	BDL	BDL	BDL	38	BDL	1.4	15	BDL	BDL	BDL
BENZO(G,H,I)PERYLENE	BDL	BDL	BDL	29	BDL	BDL	13	8.4	BDL	BDL
IDENO(1,2,3)PYRENE	BDL	BDL	BDL	BDL	BDL	BDL	11	BDL	BDL	BDL
TOTAL PHA'S	0.0	0.0	0.0	429.0	0.0	8.1	148.4	12.4	5.5	0.0

NOTES: 1. RESULTS ARE REPORTED IN MICROGRAMS PER KILOGRAM (UG/KG)

2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 1 TO 3 FEET ETC.

3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 3.5 TO 5.5 FEET ETC.

4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 6 TO 8 FEET ETC.

5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 8.5 TO 10.5 FEET ETC.

6. BDL STANDS FOR "BELOW DETECTION LIMIT"

7. J INDICATES AN ESTIMATED VALUE

8. B INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE

POLYNUCLEAR AROMATIC COMPOUND ANALYTICAL RESULTS (CONT'D)  
CRODA INKS CORPORATION  
NILES, ILLINOIS

PARAMETER	SB16-1	SB16-2	SB16-3	SB16-4
PHENANTHRENE	BDL	BDL	BDL	BDL
FLUORANTHENE	9.5	BDL	2.9	BDL
PYRENE	BDL	BDL	BDL	BDL
BENZO(A)ANTHRACENE	3.3	BDL	1.3	BDL
BENZO(B)FLUORANTHENE	4.5	BDL	2.8	BDL
BENZO(K)FLUORANTHENE	2.4	BDL	BDL	BDL
BENZO(A)PYRENE	3.6	BDL	BDL	BDL
BENZO(G,H,I)PERYLENE	BDL	BDL	5.3	4.3
IDENO(1,2,3)PYRENE	BDL	BDL	BDL	10
TOTAL PMA'S	23.3	0.0	12.3	14.3

- NOTES: 1. RESULTS ARE REPORTED IN MICROGRAMS PER KILOGRAM (UG/KG)  
2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH  
3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH  
4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH  
5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH  
6. BDL STANDS FOR "BELOW DETECTION LIMIT"  
7. J INDICATES AN ESTIMATED VALUE  
8. B INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE

HEAVY METAL ANALYTICAL RESULTS  
CRODA INKS CORPORATION  
NILES, ILLINOIS

PARAMETER	SB01-1	SB02-1	SB03-1	SB04-1	SB05-1	SB06-1	SB07-1	SB08-1
PH	8.16	7.84	7.88	7.41	7.79	8.00	8.00	7.84
CHROMIUM	11.2	11.2	9.40	24.6	10.8	14.2	9.59	12.2
LEAD	28.0	BDL	BDL	BDL	BDL	BDL	BDL	BDL

- NOTES: 1. RESULTS ARE REPORTED IN MILLIGRAMS PER KILOGRAM (MG/KG)
2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 1 TO 3 FEET ETC.
3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 3.5 TO 5.5 FEET ETC.
4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 6 TO 8 FEET ETC.
5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 8.5 TO 10.5 FEET ETC.
6. BDL STANDS FOR "BELOW DETECTION LIMIT"
7. J INDICATES AN ESTIMATED VALUE
8. B INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE

HEAVY METAL ANALYTICAL RESULTS (CONT'D)  
CRODA INKS CORPORATION  
NILES, ILLINOIS

PARAMETER	SB09-1	SB10-1	SB11-1	SB12-1	SB13-1	SB14-1	SB15-1	SB16-1
PH	7.86	7.58	7.45	7.75	7.70	7.73	8.09	8.10
CHROMIUM	8.00	9.00	13.3	7.78	19.4	6.60	13.2	12.8
LEAD	BDL	BDL	BDL	BDL	67.9	BDL	BDL	BDL

NOTES: 1. RESULTS ARE REPORTED IN MILLIGRAMS PER KILOGRAM (MG/KG)

2. SB01-1 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 1 TO 3 FEET ETC.

3. SB01-2 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 3.5 TO 5.5 FEET ETC.

4. SB01-3 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 6 TO 8 FEET ETC.

5. SB01-4 DENOTES SOIL BORING NUMBER ONE AT A SPLIT SPOON INTERVAL DEPTH OF 8.5 TO 10.5 FEET ETC.

6. BDL STANDS FOR "BELOW DETECTION LIMIT"

7. J INDICATES AN ESTIMATED VALUE

8. B INDICATES THE ANALYTE WAS FOUND IN THE BLANK AS WELL AS THE SAMPLE



10/13/86

## LABORATORY REPORT

PAGE 1

**CBC-AquaSearch**

ENVIRONMENTAL SERVICES:  
 Analytical, Field & Consulting  
 Air  
 Water & Wastewater  
 Solid & Hazardous Waste  
 Industrial Hygiene

S026 8410095 JBU

S.E.T. LIQUID WASTE SYSTEMS, INC.  
 350 SUMAC ROAD  
 WHEELING, IL 60090  
 ATTN: KATHLEEN KROEPIL

SAMPLE 86274-S07325 #6762-110/UNDERGROUND TANK SLUDGE/CRODA INKS  
 DATE COLLECTED 9/30/86 DATE RECEIVED 10/01/86

TEST NAME	RESULT	UNITS	EP TOXICITY	EP LIMIT	HAZ. CODE
CADMIUM - EP	0.64		MG/L	1.0	
CHROMIUM - EP	0.10		MG/L	5.0	
LEAD - EP	0.8		MG/L	5.0	
BARIUM - EP	0.87		MG/L	100.0	
SILVER - EP	<0.01		MG/L	5.0	
ARSENIC - EP	0.004		MG/L	5.0	
SELENIUM - EP	0.066		MG/L	1.0	
MERCURY - EP	<0.0004		MG/L	0.2	
PH (UNITS)	9.5			2.0-12.5	
TOTAL SULFIDE	<1	PPM			
FLASH POINT (FAHRENHEIT)	110	DEG. F		140.0	D001
SPECIFIC GRAVITY	0.64	G/ML			
BTU'S	14000	BTU'S/LB			
% CHLORINE	0.19	%			
TOTAL SOLIDS	29	%			
ASH CONTENT	3.6	%			

METHODS FOR CHEMICAL ANALYSIS OF WATER AND WASTES, 1979, EPA-600/4-79-020.

TEST METHODS FOR EVALUATING SOLID WASTE, PHYSICAL/CHEMICAL METHODS, 1982, EPA SW846.


ANNUAL BOOKS OF ASTM STANDARDS, 1982.

IF YOU HAVE ANY QUESTIONS PLEASE CONTACT OUR CLIENT SERVICE DEPARTMENT AT (414) 764-7005 OR CALL TOLL FREE; 1-800-592-5900, WAIT FOR DIAL TONE AND DIAL EXTENSION 332.

ANY REMAINING WASTE SAMPLES WILL BE RETURNED TO THE ADDRESS LISTED ABOVE 8 WEEKS FROM THE RECEIVING DATE OF THIS REPORT.

N/T - NOT TESTED

N/A - NOT APPLICABLE

APPROVAL 

DIVISION OF CHEM-BIO CORPORATION

140 EAST RYAN ROAD OAK CREEK, WISCONSIN 53154-4599 (414) 764-7005

B1 312 868 5408

CHEM-CLEAR/CHGO

TEL No.1 312 868 5408

May 31, 89 13:44 P.02

**CleanHarbors**

## WASTE ANALYSIS REPORT/DECISION SHEET

8132

LAB SAMPLE TRACKING #

154

BOX RETAIN #

R 32811

PROFILE SHEET #

DATE IN 3-6-89 DATE OUT \_\_\_\_\_ LAB # 022203ANALYSIS: Accepts RESULT/NOTE \_\_\_\_\_ ANALYST: VNDPHYSICAL DESCRIPTION: Semi-solidAPPEARANCE: gray% SOLID: 50%PH: 6.2WATER MIX: sinksIGNITABLE SCREEN: 2140BTU: 7002% CHLORINE: NDREACTIVE CYANIDES SCREEN: NDREACTIVE SULFIDES SCREEN: ND

PCB'S: \_\_\_\_\_

TOC: \_\_\_\_\_

SUPPLEMENTAL ANALYSIS: \_\_\_\_\_

RESULTS APPROVED: Marjella Mahoney DATE: 3-6-89  
LABORATORY MANAGER☐ APPROVED☐ DISAPPROVEDDISPOSAL OUTLET: CWR - ChicagoCODE: CCR-SO



Engineers & Scientists  
Environmental Services  
Waste Management  
Water Resources  
Site Development  
Special Structures  
Geotechnical Analysis

July 28, 1989  
40045.03

Mr. Larry Rokosz  
Croda Inks Corporation  
7777 North Merrimac Avenue  
Niles, Illinois 60648-3490

ILD 002293 124

RECEIVED  
WMD RCRA  
RECORD CENTER

1/29/93

2539

RECEIVED

OCT 17 1989

OFFICE OF RCRA  
WASTE MANAGEMENT DIVISION  
EPA, REGION V

RE: Demonstration and Certification for Hazardous Waste Landfill Disposal  
Croda Inks Corporation  
Niles, Illinois

Dear Mr. Rokosz:

As requested by the Croda Inks Corporation, Warzyn Engineering Inc. (Warzyn) has prepared this demonstration and certification, pursuant to 40 Code of Federal Regulations (CFR) Section 268.8a(2). The demonstration and certification state that the Croda Inks Corporation, through services provided by Warzyn, has made a good faith effort to locate and contract with practically available treatment and recovery facilities and that landfilling of the below described waste is the most practical disposal alternative currently available.

#### DEMONSTRATION

The waste material is soil which was contaminated when ink sludge (a K086 waste solvent sludge subcategory) leaked and/or spilled during underground storage tank (UST) use at the above address. Soil contaminated with K086 hazardous waste qualifies as a first third soft hammer waste. The volume of contaminated concrete and soil to be disposed of is estimated to be approximately 60 cubic yards. Two representative soil samples were collected by Warzyn Engineering Inc. (Warzyn) on June 6, 1989, from the stockpiled soil and analyzed for volatile organic compounds (VOCs) (SW-846 methods 8010 and 8020 of the Resource Conservation and Recovery Act (RCRA)) and RCRA hazardous waste characteristics.

VOC analysis identified total xylene and toluene in sample one as 44 parts per billion (ppb) and 451 ppb respectively. VOC analysis identified total xylene levels at 15 ppb in the second sample. The E.P. Toxicity analysis showed that all eight primary metals were below the defined limit identifying the waste as hazardous. The laboratory analysis is attached.

K086 waste (solvent sludge subcategory) is hazardous as defined by RCRA for containing constituents in excess of the EPA hazardous limits for hexavalent chromium and lead. The analysis revealed chromium and lead levels below E.P. Toxicity hazardous waste criteria. VOC levels were identified at relatively low concentrations within the soil matrix. Because the waste material consists of soil and some large concrete fragments, recycling or recovery is not practical. Since the detected VOC and heavy metal levels are low and the volume of excavated soil is small, in-situ bioremediation or fixation is also not a practical alternative. The facility does not possess a Part A or Part B RCRA permit to perform on-site treatment and/or disposal of the excavated soil.

One of the best available treatment alternatives for this waste is off-site incineration. Three incinerator facilities were contacted by Warzyn for disposal purposes. The facility information is shown in Table 1. This alternative is not believed to be practical as demonstrated from a cost analysis. The cost of incineration, including shipment but excluding concrete crushing, ranges from approximately \$1,100/ton to \$2,125/ton. The cost to landfill the excavated soil, including shipment, is approximately \$150/ton. Based on the fact that soil is below E.P. Toxicity levels for the constituents defining this material as a hazardous waste, and that the ratio of incineration versus landfilling costs is greater than 2.0 (which U.S. EPA has defined as not practical), landfilling is believed to be the only practical disposal alternative presently available.

CERTIFICATION

I certify, under penalty of law, that the requirements of 40 CFR 268.8(a)1 have been met and that disposal in a landfill or surface impoundment is the only practical alternative to treatment currently available. I believe that the information submitted is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

CERTIFICATION FOR CRODA INKS

Walter Banker

Name

Vice President of Finance

Title

Signature

July 28, 1989

Date



Mr. Larry Rokosz  
Croda Inks Corporation  
Project No. 40045.03

July 28, 1989  
Page 4

Warzyn appreciates the opportunity to be of service to you on this project.  
If you have any questions, contact us at (312) 773-8484.

Sincerely,

WARZYN ENGINEERING INC.

*Mark Rothas*

Mark S. Rothas  
Senior Project Engineer

Attachment: Table 1

WP  
40045L04JDW/gmg/MSR



TABLE 1  
TREATMENT FACILITY CONTACT INFORMATION  
CRODA INKS CORPORATION  
NILES, ILLINOS

<u>Facility</u>	<u>Contact Person</u>	<u>Facility Location</u>	<u>Telephone</u>	<u>Contact Date</u>	<u>Cost/Ton</u>
Rollins Incinerator	David Kurweg	Deer Park, Texas	(312) 260-9470	06/16/89	\$ 2,125
LWD, Inc.	Rose Burton	Calvert City, Kentucky	(502) 395-8313	06/16/89	\$ 1,100
ENSCO	Jenny Henson	Little Rock, Arkansas	(501) 223-4100	06/16/89	\$ 2,075(1)

(1) Cannot accept waste in bulk - waste must be received in drums.

Landfill Facilities

Adams Center	Kim Bigalski	Fort Wayne, Indiana	(312) 513-4519	06/20/89	\$ 160(2)
Peoria Disposal	Cheryl Franks	Peoria, Illinois	(309) 688-0760	06/21/89	\$ 125

(2) Adams Center is not accepting any new waste streams for this year and possibly for the next 3 to 5 years.



# Quality Analytical Laboratories, Inc.

"Precision, Accuracy and Service"

Warzyn Engineers, Inc.  
ATTN: James W. Wink  
1 Pierce Place  
Itasca, IL 60143

Job #: 1-631  
Date: 6/12/1989

Sampling Date: unknown  
Analyses Date: 6/6-12/1989  
Technique/Method: The samples were analyzed as per USEPA SW-846  
methods 8010 and 8020

Identification: Two samples identified as:

Project Name: Croda Inks Corp  
Project #: 40045.03  
Location: Niles, IL

All results expressed in ug/kg (ppb)

Results: Soil Pile #1

Parameter	method detection Limit	Analysis
Chloromethane	5	BDL
Bromomethane	5	BDL
Vinyl Chloride	5	BDL
Chloroethane	5	BDL
Methylene Chloride	1	BDL
Trichlorofluoromethane	1	BDL
Acetone	75	BDL
Carbon Disulfide	1	BDL
Dibromomethane	1	BDL
Dichlorofluoromethane	1	BDL
Ethanol	25	BDL
Iodomethane	1	BDL
1,1-Dichloroethane	1	BDL
1,1-Dichloroethene	1	BDL
trans-1,2-Dichloroethene	1	BDL
Trichloromethane (Chloroform)	1	BDL
1,2-Dichloroethane	1	BDL
1,1,1-Trichloroethane	1	BDL
1,2,3-Trichloropropane	1	BDL
Vinyl Acetate	25	BDL
Tetrachloromethane(Carbon Tet)	1	BDL
Bromodichloromethane	1	BDL
1,2-Dichloropropane	1	BDL
Tribromomethane (Bromoform)	1	BDL
4-Methyl-2-pentanone (MIBK)	25	BDL
trans-1,3-Dichloropropene	1	BDL
2-Chlorovinyl Ether	1	BDL
Trichloroethene	1	BDL
Benzene	1	BDL
Dibromochloromethane	1	BDL
1,1,2-Trichloroethane	1	BDL
cis-1,3-Dichloropropene	1	BDL



# Quality Analytical Laboratories Inc.

precision, Accuracy and Service"

1-630 Page 2

Results: Soil Pile #2

Total Metals		E.P. Toxicity Metals	
-----		-----	
Cu	NA		NA
Cd	NA		<1.0mg/l
Cr	NA		<1.0mg/l
Pb	NA		<1.0mg/l
Ag	NA		<1.0mg/l
Se	NA		<1.0mg/l
As	NA		<1.0mg/l
Hg	NA		<0.01mg/l
Zn	NA		NA
Ni	NA		NA
Fe	NA		NA
Ba	NA		<50.0mg/l

CN (Tot) ..... <1.0mg/kg  
Sulfide (Tot) .. <1.0mg/kg  
Chlorine ..... NA  
Flashpoint ..... >140 degrees F (Pensky-Martens C.C.)  
Paint Filter ... pass  
Total Solids ... NA  
pH ..... 8.4

NA = Not Applicable

Respectfully Submitted,



Maureen M. Gibbons  
Lab Manager  
Quality Analytical Labs, Inc.

# Quality Analytical Laboratories Inc.

"Precision, Accuracy and Service"

1-631 Page 2

Parameter	method detection Limit	Analysis
trans-1,3-Dichloropropene	1	BDL
1,1,2,2-Tetrachloroethane	1	BDL
Tetrachloroethene	1	BDL
Methylbenzene (Toluene)	1	451
Ethyl Benzene	1	BDL
Xylenes (Total)	3	44
2-Hexanone	10	BDL
Acrolien	1	BDL
Acrylonitrile	1	BDL
1,4-Dichloro-2-butane	1	BDL
Ethyl Methacrylate	1	BDL
Chlorobenzene	1	BDL
2-Butanone (Methyl Ethyl Ketone)	50	BDL
Styrene	1	BDL

Note: Bromofluorobenzene present

Results: Soil Pile #2

Parameter	method detection Limit	Analysis
Chloromethane	5	BDL
Bromomethane	5	BDL
Vinyl Chloride	5	BDL
Chloroethane	5	BDL
Methylene Chloride	1	BDL
Trichlorofluoromethane	1	BDL
Acetone	75	BDL
Carbon Disulfide	1	BDL
Dibromomethane	1	BDL
Dichlorofluoromethane	1	BDL
Ethanol	25	BDL
Iodomethane	1	BDL
1,1-Dichloroethane	1	BDL
1,1-Dichloroethene	1	BDL
trans-1,2-Dichloroethene	1	BDL
Trichloromethane (Chloroform)	1	BDL
1,2-Dichloroethane	1	BDL
1,1,1-Trichloroethane	1	BDL
1,2,3-Trichloropropane	1	BDL
Vinyl Acetate	25	BDL
Tetrachloromethane(Carbon Tet)	1	BDL
Bromodichloromethane	1	BDL
1,2-Dichloropropane	1	BDL
Tribromomethane (Bromoform)	1	BDL
4-Methyl-2-pentanone (MIBK)	25	BDL
trans-1,3-Dichloropropene	1	BDL
2-Chlorovinyl Ether	1	BDL
Trichloroethene	1	BDL
Benzene	1	BDL

# Quality Analytical Laboratories Inc.

"Precision, Accuracy and Service"


1-631 Page 3

Parameter	method detection Limit	Analysis
Dibromochloromethane	1	BDL
1,1,2-Trichloroethane	1	BDL
cis-1,3-Dichloropropene	1	BDL
trans-1,3-Dichloropropene	1	BDL
1,1,2,2-Tetrachloroethane	1	BDL
Tetrachloroethene	1	BDL
Methylbenzene (Toluene)	1	BDL
Ethyl Benzene	1	BDL
Xylenes (Total)	3	15
2-Hexanone	10	BDL
Acrolein	1	BDL
Acrylonitrile	1	BDL
1,4-Dichloro-2-butane	1	BDL
Ethyl Methacrylate	1	BDL
Chlorobenzene	1	BDL
2-Butanone (Methyl Ethyl Ketone)	50	BDL
Styrene	1	BDL

Note: Bromofluorobenzene present

(BDL = Below Detection Limit)

Respectfully Submitted,



William F. Eberhardt

Lab Director

Quality Analytical Labs, Inc.

# Quality Analytical Laboratories Inc.

"Precision, Accuracy and Service"

Warzyn Engineers, Inc.

ATTN: James W. Wink

1 Pierce Place

Itasca, IL 60143

Job #:1-630

Date: 6/13/1989

Sampling Date: unknown

Analyses Date: 6/6-12/1989

Technique/Method: The samples were analyzed as per USEPA SW-846

Identification: Two samples identified as:

Project Name: Croda Inks Corp

Project #: 40045.03

Location: Niles, IL

Results: Soil Pile #1

	<u>Total Metals</u>	<u>E.P. Toxicity Metals</u>
Cu	NA	NA
Cd	NA	<1.0mg/l
Cr	NA	<1.0mg/l
Pb	NA	<1.0mg/l
Ag	NA	<1.0mg/l
Se	NA	<1.0mg/l
As	NA	<1.0mg/l
Hg	NA	<0.01mg/l
Zn	NA	NA
Ni	NA	NA
Fe	NA	NA
Ba	NA	<50.0mg/l
CN (Tot)	<1.0mg/kg	
Sulfide (Tot)	<1.0mg/kg	
Chlorine	NA	
Flashpoint	>140 degrees F (Pensky-Martens C.C.)	
Paint Filter	pass	
Total Solids	NA	
pH	8.2	

RECEIVED

JUN 19 1989

WARZYN-ILLINOIS

*John R. Dennis (STE)*  
Quality Assurance Officer  
PDC Laboratories, Inc.